




भारतीय रिजर्व बैंक नोट मुद्रण प्राईवेट लिमिटेड
नैगमिक कार्यालय, बेंगलूरु
**BHARATIYA RESERVE BANK NOTE MUDRAN
PRIVATE LIMITED
CORPORATE OFFICE, BENGALURU**



NATIONAL COMPETITIVE BIDDING (NCB) – OPEN TENDER

Tender Document for

**Construction of Compound Wall, Pathway and Security Building &
Refurbishment of Existing Signage Tower at BRBNMPL, Bengaluru**

निविदा सं. 008/CO/OT/2021-22 दिनांक December 31, 2021

Tender No: 008/CO/OT/2021-22 dated December 31, 2021

बंद होने की तिथि और निविदा अप्राप्ति का समय/ Closing Date & Time for receipt of Tender	14:30 Hrs on February 01, 2022
दस्ती निविदा प्राप्ति की जगह / Place of receipt of tender by Hand	बीआरबीएनएमपीएल, बेंगलूरु BRBNMPL, Bangalore
निविदा खोलने की तिथि और समय / Time & Date of Opening of Tender	15:00 Hrs on February 01, 2022
निविदा खोलने की जगह/ Place of Opening of Tenders	बीआरबीएनएमपीएल, बेंगलूरु BRBNMPL, Bangalore

भारतीय रिजर्व बैंक नोट मुद्रण (प्रा.) लिमिटेड, बेंगलूरु
BHARATIYA RESERVE BANK NOTE MUDRAN (P) LTD
BANGALORE -560029

दूरभाष / Phone: 080-66602000, 66602034

फैक्स / Fax: 080 – 66602039, ई-मेल / E-Mail: cobangalore@brbnmpl.co.in

वैबसाइट / Website: www.brbnmpl.co.in

अहस्तांतरणीय / **Not Transferable**

**Tender Document for Construction of Compound Wall, Pathway and Security Building
& Refurbishment of Existing Signage Tower at BRBNMPL, Bengaluru**

निविदा सं. 008/CO/OT/2021-22 दिनांक **December 31, 2021**
Tender No: 008/CO/OT/2021-22 dated December 31, 2021

इस निविदा दस्तावेज़ में सम्मिलित / This document contains **103** pages

निविदा दस्तावेज़ विक्रेता (बोलीदाता का नाम) डाउनलोडकर्ता // The tender document is sold to:

मैसर्स / M/s. _____

पता / Address _____

इस निविदा से संबंधित बी.आर.बी.एन. एम. पी. एल. के संपर्क व्यक्ति का / Details of Contact person in BRBNMPL regarding this tender:

नाम / Name : एस एम पावले / S M Pawale

पदनाम / Designation : उप महाप्रबंधक / Deputy General Manager

पता /Address:

भारतीय रिजर्व बैंक नोट मुद्रण प्राइवेट लिमिटेड

Bharatiya Reserve Bank Note Mudran Private Limited,

पंजीकृत एवं नैगमिक कार्यालय/Regd. & Corporate Office,

न./No. 3 & 4, 1ला स्टेज, 1ला फेज /1st Stage, 1st Phase,

बीटीएम लेआउट , जल भवन के पास /BTM Layout, Near Jal Bhavan,

बनेर्घट्टा रोड / Bannerghatta Road,

बेंगलूरु /Bengaluru - 560029

ई-मेल/Email: smpawale@brbnmpl.co.in

दूरभाष / Phone: 080 – 66602000, 66602034, Fax: 080-66602039

CONTENTS OF THIS TENDER ENQUIRY: (In SBD Format)

Tender Clause / Section Reference	Tender Clause Description	Remarks
Section I	Notice Inviting Tender (NIT)	Enclosed
Section II	General Instructions for Tenderer (GIT)	Enclosed
Section III	Special Instructions to Tenderers (SIT)	Enclosed
Section IV	General Conditions of Contract (GCC)	Enclosed
Section V	Special Conditions of Contract (SCC)	Enclosed
Section VI	List of Requirements	Enclosed
Section VII	Technical Specification	Enclosed
Section VIII	Quality Control Requirements / Compliance Statement by Tenderer	Enclosed
Section IX	Qualification/Eligibility Criteria	Enclosed
Section X	Tender form	Enclosed
Section XI	Price Schedule (Price Bid)	Enclosed
Section XII	Questionnaire / Checklist	Enclosed
Section XIII	Bank Guarantee Form for EMD	<u>Not Applicable to this tender</u>
Section XIV	Manufacturer's Authorization Form	<u>Not applicable to this tender</u>
Section XV	Bank Guarantee Form for Performance Security / SD	Enclosed
Section XVI	Contract Form	Enclosed
Section XVII	Letter of Authority for attending a Bid Opening	Enclosed
Section XVIII	Shipping arrangement for liner cargo-	<u>Not applicable to this tender</u>
Section XIX	Proforma of Bills for Payments	Enclosed
Section XX	Pre contract Integrity Pact	<u>Not applicable to this tender</u>
Checklist	Checklist for Tenderers	Enclosed
Annexure - A	Performa of Financial Turnover Certificate	Enclosed
Annexure - B	NEFT – Model Mandate Form	Enclosed
Annexure - C	Undertaking to fulfil the Security Deposit	Enclosed
Annexure - D	Confidentiality Statement and Declaration	Enclosed
Annexure – E	Salient features of revised 'Public Procurement (Preference to Make in India) Order, 2017	Enclosed
Annexure – F	Salient features of 'Public Procurement Policy for Micro and Small Enterprises (MSEs) Order, 2012'	Enclosed
Annexure – G	Conditions For Conditions For Start-Up Companies	Enclosed
Annexure – H	Procedure to be adopted when the Bidder Qualifies as both MSE and Class-I Local Supplier	Enclosed
Annexure – I	Declaration & Undertaking by Micro & Small Scale Enterprises / Start-up Companies / Entities seeking purchase preference under Make In India Policy / Women entrepreneurs / Registration with TReDS/GeM	Enclosed
Annexure – J	Bid Security Declaration in lieu of Earnest Money Deposit	Enclosed
Annexure – H	Tender Drawing	Enclosed

भारतीय रिजर्व बैंक नोट मुद्रण (प्रा.) लिमिटेड, बेंगलूरु
BHARATIYA RESERVE BANK NOTE MUDRAN (P) LTD
BANGALORE -560029

दूरभाष / Phone: 080-66602000, 66602034

फैक्स / Fax: 080 – 66602039, ई-मेल / E-Mail: cobangalore@brbnmpl.co.in

वेबसाइट / Website: www.brbnmpl.co.in

भाग / SECTION- I: निविदा आमंत्रण की सूचना / NOTICE INVITING TENDER (NIT)

दिनांक / Dated: December 31, 2021

M/s.

निविदा सं. 008/CO/OT/2021-22 दिनांक December 31, 2021
Tender No: 008/CO/OT/2021-22 dated December 31, 2021

विषय / Sub: Tender Document for Construction of Compound Wall, Pathway and Security Building & Refurbishment of Existing Signage Tower at BRBNMPL, Bengaluru

Dear Sir/Madam,

Sealed tenders in TWO parts (Part-I - Technical and Part-II Commercial (Price) bid) are invited for **“Construction of Compound Wall, Pathway and Security Building & Refurbishment of Existing Signage Tower at BRBNMPL, Bengaluru”**.

Sl. No.	Brief Description of Goods / Services	Quantity (Unit)	Earnest Money Deposit	Remarks
01	Construction of Compound Wall, Pathway and Security Building & Refurbishment of Existing Signage Tower at BRBNMPL, Bengaluru. (Non-Splitable) As per Bill of quantities and scope of work mentioned at Section-VI, VII, & XI.	As per BOQ	NIL Note: bidder is required to submit declaration for bid security as per proforma at Annexure-J	Estimate Value: ₹ 52,75,000/- (Rupees Fifty Two Lakhs Seventy Five Thousand) only

Type of Tender (Two Bid / PQB / EOI / RC / Development / Indigenization / Disposal of Scrap / Security item etc.	Two Bid System (Part – 1 Techno-commercial Bid and Part-2 Financial/Price Bid)
Date of Sale of tender documents	From December 31, 2021 to January 31, 2022 during office hours
Price of the Tender Document	₹ 1,500/- (Inclusive of all applicable taxes)
Closing date and time for receipt of tenders	14:30 Hours on February 01, 2022
Place of receipt of tenders	Technical section, Bharatiya Reserve Bank Note Mudran Private Limited, Corporate Office, Bengaluru-560 029. (OR)

	Can be downloaded from our website www.brbnmpl.co.in , in which case Price of tender document should be enclosed along with your offer.
Time and date of opening of tenders	15:00 Hours on February 01, 2022
Place of opening of tenders	Board / Conference room at Corporate Office, BRBNMPL.
Nominated Person / Designation to Receive Bulky Tender (Clause 21.1 of GIT)	Shri. S.M. Pawale, DGM & CISO

2. Interested tenderers may obtain further information about this requirement from the above office selling the documents. They may also visit our website www.brbnmpl.co.in mentioned above for further details.
3. Tender documents may be purchased on payment of non-refundable fee of ₹ 1,500/- (amount) per set through:
 - a. Online Bank Transfer (proof of online transfer to be submitted along with the tender papers) through NEFT/RTGS can be made at the following BRBNMPL account maintained with State Bank of India, Overseas Branch, Bengaluru.
SBI A/c No.: **00000010605523157**
IFSC: **SBIN0006861**
 - OR
 - b. Through any other Electronic mode of payment such as Debit Card powered by RuPay, Unified Payments Interface (UPI) (BHIM-UPI), Unified Payments Interface Quick Response Code (UPI QR Code) (BHIM-UPI QR Code)



- OR
- c. In the form of account payee demand draft/Banker's cheque, drawn on a scheduled commercial bank in India, in favour of Bharatiya Reserve Bank Note Mudran Private Limited, payable at Bengaluru.

Note: In case of (a) & (b) mode of payments, bidders are requested to send proof of the same after completion of transaction to the contact mail given in the tender by giving reference of Tender number, Name of company/firm and mobile number.

4. If requested, the tender documents will be mailed by registered post / speed post to the domestic tenderers, for which extra expenditure per set will be ₹ 500/- for domestic post. The tenderer is to add the applicable postage cost in the non-refundable fee mentioned in Para 3 above.
5. Tenderer may also download the tender documents from the web site and submit its bid by utilizing the downloaded document, along with the required non-refundable fee as mentioned in Para 3 above.
6. Tenderers shall ensure that their tenders, duly sealed and signed, complete in all respects as per instructions contained in the Tender Documents, are dropped in the

tender box located at the address given below on or before the closing date and time indicated in the Para 1 above, failing which the tenders will be treated as late and rejected.

7. In the event of any of the above mentioned dates being declared as a holiday / closed day for the purchase organization, the tenders will be sold / received / opened on the next working day at the appointed time.
8. The tender documents are not transferable.
9. BRBNMPL reserves the right to Cancel the tendering Process / Reject all Bids / Re-tender without assigning any reason thereof. BRBNMPL also reserves the right to accept the Bid in whole or in part. Incomplete Bid documents submitted not in accordance with the directions issued shall be liable for rejection.
10. Tenderer shall note that the tender document is kept same for all schedules, if more than one schedule is specified, for administrative convenience. BRBNMPL reserves the right to conclude contract for each schedule independently as per the response and qualification.
11. The eligible bidder shall be selected as per the eligibility criteria mentioned in Section IX of the tender and Tender shall be finalized on overall **Lowest L1 bidder** from eligible bidders as per section XI.
12. **Relaxations, exemptions and other conditions for Micro and Small Enterprises (MSEs) Order 2012 for MSEs & Start-ups;**
Bidders are advised to refer the following annexures for relaxations, exemptions and other conditions of Public Procurement Policy.
Annexure-E: Salient Features of Revised 'Public Procurement (Preference to Make In India) Order, 2017'
Annexure-F: Salient Features of 'Public Procurement Policy for Micro and Small Enterprises (MSEs) Order, 2012'; Conditions for Micro and Small Enterprises (MSEs)
Annexure-G: Conditions for Start-Up Companies
Annexure-H: Procedure to be adopted when the Bidder qualifies as both MSE and Class-I Local Supplier
13. Product Reservation/Purchase Preference shall be given to MSEs as per Public Procurement Policy for Micro and Small Enterprises (MSEs) Order, 2012 along with amendments, if any, notified by Govt. of India.
14. Purchase preference shall be given to Local Suppliers as per Public Procurement (Preference to Make in India) Order, 2017 along with amendments, if any, notified by Govt. of India.

Guidelines for filling two-part tender: (if applicable)

Please send your competitive bidding in sealed cover super scribed as **“Construction of Compound Wall, Pathway and Security Building & Refurbishment of Existing Signage Tower at BRBNMPL, Bengaluru ”** against Tender Enquiry No. **008/CO/OT/2021-22 dated December 31, 2021** to reach us on or before **14.30 hrs on February 01, 2022 at BRBNMPL, Bengaluru** with the following separate sealed covers inside:

1. **Part I:** First sealed cover should contain the cost of tender form, technical offer (catalogue/brochure/specifications etc.), supportive documents related to eligibility criteria, tax related documents etc. along with ALL annexures of this tender **except Section XI (Price Schedule)**. All the pages included as Tender Document should be legible, neatly numbered and signed by authorized person with official seal of the Firm as acceptance of the terms and conditions. Offers with Counter Conditions is liable for Rejections. This first sealed cover should be clearly super-scribed with **“Part I - Technical Bid - For “Construction of Compound Wall, Pathway and Security Building & Refurbishment of Existing Signage Tower at BRBNMPL, Bengaluru”** against Tender Enquiry No. **008/CO/OT/2021-22 dated December 31, 2021**. *In case of any price indication in the Technical Bid, the tender will be summarily rejected.*
2. **Part II:** Second sealed cover should contain only section XI (Price Schedule) (duly sealed and signed). Format provided in the tender document for price schedule should be followed and any other format will be liable for rejection. This second sealed cover should be clearly super-scribed with **“Part II - Price Bid - for “Construction of Compound Wall, Pathway and Security Building & Refurbishment of Existing Signage Tower at**

BRBNMPL, Bengaluru” against Tender Enquiry No. 008/CO/OT/2021-22 dated December 31, 2021.

3. The above mentioned sealed covers (Part I & II) should be put in another big cover, sealed and super-scribed as **“Offer “Construction of Compound Wall, Pathway and Security Building & Refurbishment of Existing Signage Tower at BRBNMPL, Bengaluru”** against Tender Enquiry No. **008/CO/OT/2021-22 dated December 31, 2021** with due date of opening as 15:00 Hours on February 01, 2022 and should be addressed to The General Manager (Name and address).
4. BIDS submitted not in accordance with above guidelines will be liable to be rejected.
5. If the sealed tenders are sent by post or courier service, the tenderers shall ensure that the tenders are posted or dispatched sufficiently early so that the tenders are received by the BRBNMPL within the stipulated date and time. BRBNMPL will not be responsible for any delay in post or courier. If the tenders are to be delivered in person at the above address, the sealed tenders shall be deposited before the stipulated date and time, at the aforesaid office. BRBNMPL shall not accept responsibility for late receipt of tenders if delivered in person or sent by post or courier service.

The Technical part (part I) tenders will be opened at 15.00 hrs on February 01, 2022 in the presence of available tenderers or their authorized representatives. In the second stage, the financial bids of only the technically acceptable offers shall be opened for further scrutiny and evaluation. The date of opening of Price bids will be intimated to qualified bidders. Other financial bids would be returned unopened to the respective bidders under Registered AD/ Reliable Courier or any other mode with proof of delivery.

[Name, designation, address, tel. no. etc.
of the officer signing the document]



For and on behalf of BRBNMPL,
(S M Pawale).

बोलीदाताओं के ध्यानार्थ निविदा की महत्वपूर्ण शर्तों पर एक नज़र
IMPORTANT TENDER CONDITIONS AT A GLANCE FOR ATTENTION OF BIDDERS

1. **निविदा की वैधता / Validity of Tender:** The quoted rates shall be valid for a period of 120 days from the date of opening of the tenders. If any tenderer withdraws his tender before the said period or makes any modification in the Price Bid or terms and conditions of the tender then, BRBNMPL, without prejudice to any other right or remedy will be at liberty to take action as deemed fit.
2. **ई.एम.डी / E.M.D:** As per GIT Clause 18 under Section II
 - a. All bidders shall be exempted from submission of EMD.
 - b. All bidders shall be required to sign the bid securing declaration as per proforma attached at Annexure-L:
3. **संविदा का मूल्य / Contract Price:**

The rates quoted in the tender shall be based on the technical specifications, scope of work and actual work carried out. The rates quoted in the tender shall include all charges for clearing of site before commencement as well after completion. The rate quoted shall be deemed to be for the finished work to be measured at site. The rate quoted shall also be firm irrespective of any variation in quantities of items given in the schedule of items.
4. **Tenure:** The work should be completed as per as per bill of quantities and scope of work within Eight (08) months from date issue of LoI / work order / contract. Any requests for extension of time may be initiated two weeks before the scheduled completion date citing the reasons for delay which may be granted with or without imposition of LD.
5. **वैकल्पिक मात्रा / अतिरिक्त कार्य आदेश / Optional Quantity/Additional Work order:**

Quantities mentioned in the schedule of items are approximate and may vary as per actual work done/ site requirement. The contractor shall not claim any extra rate on this account and the payment shall be made as per the actual work done. BRBNMPL may extend the Work order/place additional work order at a later date at the quoted rates.
6. The successful contractor has to visit the site before commencement of work and procure the materials as per the site requirement. Payment shall be made as per actual certified work and no payment will be made against the extra quantity brought to site.
7. **अवार्ड की अधिसूचना / Notification of Award:** BRBNMPL shall issue Notification of award / LOI to the L1 bidder by post or by fax/email (to be confirmed by post) that its tender for Captioned Subject, has been accepted, briefly indicating therein the essential details of work and corresponding prices accepted. The successful tenderer/Contractor shall mobilize all men required for timely performance involving various activities and start the work from the date mentioned in Notification of Award. Contractor should return back the duplicate copy of Notification of Award duly signed and stamped in each page as acceptance.
8. **सुरक्षा जमा/निष्पादन बॉन्ड / Security Deposit/Performance Bond:**

Within twenty-one days after the issue of notification of award by BRBNMPL, the supplier shall furnish Security Deposit to BRBNMPL for an amount equal to 3% of the Order Value by way of DD/BG, valid up to Sixty days after date of completion of all contractual obligations, including warranty period. (Please refer GCC Clause 6 under Section IV.). Failure of the successful tenderer in providing performance security within 21 days of receipt of notification of award and / or returning of duplicate copy of Notification of Award/ LOI duly signed shall make the tenderer liable for forfeiture of its EMD and, also, for further sanctions by BRBNMPL against it.
9. **संविदा का करार / Contract Agreement:** A formal agreement has to be executed between the contractor and BRBNMPL on ₹ 100/-Non-judicial stamp paper purchased by the contractor within two weeks of receipt of Security Deposit/Performance Bond as per the format given in SECTION-XVI. In case Contractor fails to complete the formalities for execution of agreement, Work Order shall be cancelled. In such case, EMD / SD of the contractor shall be forfeited and BRBNMPL may initiate appropriate action as deemed fit.

10. उप संविदा / Sub-contract: Sub-contracting in any form before and after placement of the work order will not be allowed. In case the contractor is found engaging sub-contractor, the contract is liable for terminated forthwith and forfeiture of Security Deposit.
11. परिसमापन हर्जाना / Liquidated Damages - Compensation for Delay:
If the supplier fails to deliver any or all of the goods within the time frame (s) [delivery schedule] incorporated in the contract, BRBNMPL shall, under the contract deduct from the contract price, as liquidated damages, a sum equivalent to the 0.5% of the delivered price of the delayed goods and/ or services for each week of delay or part thereof until actual delivery or performance, subject to a maximum deduction of the 10% (or any other percentage if prescribed in the SCC) of the delayed goods' or services' contract price(s). [Please refer GCC Clause 24 under Section IV].
12. Payment Terms:
- a. R/A Bills:
- The value of work done, less recovery if any will be payable as per progress of work as running account bills subject to satisfactory completion of work as per measurements submitted for certification to BRBNMPL Officer in MS excel, MS sheets in standard measurements sheets. Deductions will comprise the deductions as stipulated including statutory deduction.
 - All progress payments made / R/A bills paid shall be regarded as payment by way of advance against final payment only and not as payment for the work completed.
 - The contractors must finally complete the work strictly in accordance with the specifications and drawings, if required, by reconstructing or rectifying faulty work.
 - All R/A bills / invoices for progress payments as well as for final payments shall be submitted in prescribed computerized forms supported by detailed measurement of items of work.
 - The minimum value of interim bill/monthly bill/progressive running account (R/A) bill shall not be less than ₹ 15 lakhs (Rupees Fifteen Lakhs) only as mentioned in the tender form. The contractor has to submit the final bill within two months from the date of completion of work.
 - The bill should be submitted along with the all the supporting documents.
 - All payments to the Bidder shall normally be made by Electronics clearing facility.
- b. Final Bill:
- The Bidder shall submit the final bill within 2 (two) months from the date of completion of the works. The final bill submitted by the Bidder shall be processed for payment only after receipt of "No claim certificate" and the clearance of site of all rubbish, debris, vats, tanks, materials, temporary structures, machinery, etc. and handing over the site in a tidy and clean condition to the BRBNMPL.
 - All payments to the Bidder shall normally be made by Account Payee Cheques/Electronics clearing facility. All Bank charges in connection with payment by way of Demand Draft on specific request to the Bidder shall be borne by the Bidder /RTGS on submission of the request by the bidder as per Finance Department requirement.
13. Extra Items: Any extra items that are found to be necessary during the course of work, the same shall have to be executed by the contractor. The rates for the same shall be derived from KPWD/CPWD Schedule of rates or Market rates (for items which are not included in the schedule of rates + 10% over head /profit. However, before executing, prior approval shall be obtained from BRBNMPL.
14. The calculations made by the tenderer should be based upon probable quantities of several items of work, which are furnished for the tenderer's convenience in the schedule of probable quantities, but it must be clearly understood that the contract is not a lump sum contract.

15. The successful tenderer is bound to carry out any items of work necessary for the completion of the job though such items as are not included in the quantities and rates with the written approval of the employer.
16. Parties who have been black listed /debarred by BRBNMPL or any PSU or any Government Departments are not eligible for submission of this tender.
17. BRBNMPL does not pledge itself to accept the lowest or any tender and reserves to itself the right of accepting/rejecting the whole or any part of the tender or portion of the quantity tendered without assigning any reason thereof.
18. If the tenderer is registered under NSIC/MSE, New Delhi they have to clearly mention and submit a copy of supporting documents. In absence of any such declaration, tenderer shall be considered as not registered under NSIC/MSE, New Delhi. Tenderer registered with NSIC are eligible for exemption of only EMD. As regarding SD, the tenderer who are registered with NSIC/MSE should submit an undertaking for payment of SD in case they become L1 firm in bid process and this undertaking letter should be attached to the Technical Bid-Part-I.
19. The Contractor's co-ordination with other agencies appointed by BRBNMPL is essential to maintain smooth progress of the work and any delay, which in the opinion of BRBNMPL if due to non-co-ordination and inefficient management of the contractor will not be entertained.
20. प्रमाण-पत्रों की प्रतियाँ / Copies of Certificates / Documents related to company profile like GST Registration, PAN and Professional Tax Registration Certificate etc., to be provided along with the Technical Bid-Part-I.
21. अन्य अनुदेश / Other Instructions:
 - a. A tenderer should quote the tender in figures as well as in words. The amount for each item should be worked out and the requisite totals given. The Rates and total amounts should be rounded off to nearest rupee value. In case of discrepancy between the rates in words and figures the rate quoted by the tender in words shall be taken as correct.
 - b. The tender document should be signed on each page by the tenderer or his duly authorized representative. A certified true copy of an absolute power of Attorney in favour of signatory should accompany tender documents.
 - c. Any discrepancies, omissions, ambiguities or conflicts in or among contract documents or any doubt as to their meaning should be called to the attention of The Deputy General Manager: 080 – 66602000, 66602034 within three (3) days of issue of tender. Where information sought is not clearly indicated or specified, the company will issue a clarifying bulletin to all tenderers, which will become part of the contract. Any oral instructions will not form any part of contract.
 - d. The use of whitener / eraser in this tender is prohibited. If any correction becomes of necessary, the same should be done by striking off originally written rates & figures etc. and then rewritten should be done under initials of person filling the tender.
 - e. Please note that the contractors who have worked earlier with BRBNMPL and their performance was not found satisfactory for any of the jobs awarded to them, their tenders shall not be opened during technical bid stage and their offers shall be considered as invalid and shall be rejected.
22. No counter conditions shall be accepted.
23. All terms & conditions of this NIT shall be treated as part & parcel of the contract.
24. कंपनी के अधिकार / Rights of company:

If the successful bidder refuses to accept the work order or take up the job or leave the job half way after opening the quotation and becoming lowest party, BRBNMPL reserve the right to terminate the contract and forfeit the Security Deposit and no correspondence will be entertained and decision of the BRBNMPL will be final. In such case Company reserve the right to take necessary action as deemed fit against the contractor and assign another agency for completion of the leftover job and the additional cost incurred thus shall be recovered from the original contractor.
25. क्षतिपूर्ति / Indemnity: The Contractor shall indemnify the Employer from and against all actions, suits claims and demands brought or made against the Employer in respect of any matter or thing done or omitted to be done by the Contractor or any of his Sub-Contractor(s) or nominated Sub-Contractor(s) or their employees or workmen in the

execution of or in connection with the Works of this Contract and against any loss or damage to the Employer in consequence of any action or suit being brought against the Contractor or any of his Sub-Contractor(s) or nominated Sub-Contractor(s) or their employees or workmen for anything done or omitted to be done in the execution of the Works under this Contract.

26. समाप्ति / Termination: If the Contractor shall be adjudged bankrupt or if he should make a general assignment for the benefit of his creditors, or if a receiver shall be appointed on account of his insolvency, or if he should persistently or repeatedly refuse to carry out the work diligently, or if he should fail to provide enough properly skilled workmen or proper materials or equipment or plant and machinery or tools or anything else necessary for the progress of the works in accordance with the approved scope of work or if he should persistently disregard laws or ordinances or instructions of the Employer, or if he should be guilty of a Violation of breach of any provision of the Contract, or if he has abandoned the Contract, or if he has failed to commence the works, or if he has suspended the Works, then the Employer/Employer on the basis that sufficient cause exists to justify such action, may without prejudice to any other right or remedy and after giving the Contractor seven day's notice in writing, terminate the employment of the Contractor and take possession of the premises and of all materials, equipment, tools, and plant and machinery thereon and use these as Employer's property for the completion of the Works.
27. विवादों का निपटारा / Resolution of Disputes / Arbitration: If any dispute arises after the issue of LOI /Work Order and during the execution of the project which is not resolved within 30 days of their arising, they shall be referred to a sole arbitrator to be appointed by the Managing Director of BRBNMPL. The governing law in this regard will be The Arbitration and Conciliation Act, 1996 of India. The court of Bengaluru (Karnataka State) only shall have jurisdiction to deal with and decide any legal matter of dispute whatsoever arising out of any LOI/ Work order placed by us. However, the right of giving the list of arbitrators for selection of sole arbitrator by the parties is exclusively kept reserved by BRBNMPL whose decision shall be final and binding on the parties.
28. Exemption for MSEs and Start-ups: The tenderers who are currently registered and shall continue to remain registered during the tender validity period with Central Purchase Organisation (CPO) or as a Micro and Small Enterprise (MSE) as defined in MSEs Order 2012 issued by Ministry of Micro, Small and Medium Enterprises (MSME) or as a Start-up as recognised by Department for Promotion of Industry and Internal Trade (DPIIT), are exempted from payment of tender fee and earnest money. In case the tenderer falls in these categories, it should furnish certified copy of its valid registration details (registration with CPO or as a MSE or Start-up, as the case may be).
- a. Micro & Small Enterprises must attach Registration Certificate issued by DIC / KVIC / KVIB / Coir Board / NSIC / Directorate of Handicrafts and Handlooms, or any other body specified by MSME for authentication such as Udyog Aadhaar Memorandum / Acknowledgment.
 - b. SC/ST/Women entrepreneurs registered under MSEs need to submit valid documentary evidence.
29. All statutory provisions / requirements should be complied with. Records to this effect are to be maintained by the contractor / Service provider and to be shown on demand to the authorities concerned and are responsible directly to them.
30. Tenderers must mention their Income Tax Permanent Account No. (PAN), GST registration, MSME, Professional Tax Registration along with the offer, failing which the offer will liable to be rejected.
31. Parties who have been black listed /debarred by BRBNMPL/PSU or any Govt. Departments are not eligible for submission of this tender.
32. BRBNMPL does not pledge itself to accept the lowest or any tender and reserves to it the right of accepting/rejecting the whole or any part of the tender or portion of the quantity tendered without assigning any reason thereof.
33. If the tenderers registered under MSME/ NSIC, they have to clearly mention and submit a copy of supporting documents. In absence of any such declaration, tenderer shall be considered as not registered under MSME/NSIC.

(To be signed & stamped and submitted along with Techno-commercial Bid Part -I)

सेक्शन / **Section II: टेंडर कर्ता की सामान्य शर्तें /**
General Conditions of Tenderers (GIT)

भाग/Part I: सभी प्रकार के निविदाओं पर लागू
सामान्य अनुदेश / General Instructions
Applicable to all Types of Tenders

A PREAMBLE

1. Introduction

- 1.1 Definitions and abbreviations, which have been used in these documents, shall have the meanings as indicated in GCC.
- 1.2 For sake of convenience, whole of this Standard Bidding Document (including all sections) is written in reference to Procurement of Goods Tenders. However this SBD would be utilized for all types of Tenders e.g. EOI, PQB, Rate Contract, Tenders involving Samples, Sale / Disposal of Scrap Material and Development / indigenization etc, Procurement of Services etc. Therefore the construction of all clauses are to be interpreted in the context of particular type of tender beyond the letter of the clause, read with the additional clauses for the specific type of tenders in Part II GIT/ GCC.
- 1.3 These tender documents have been issued for the requirements mentioned in Section - VI - "List of Requirements", which also indicates, inter-alia, the required delivery schedule and terms & place (i.e. destination) of delivery.
- 1.4 This section (Section II - "General Instruction to Tenderers" - GIT) provides the relevant information as well as instructions to assist the prospective tenderers in preparation and submission of tenders. It also includes the mode and procedure to be adopted for receipt and opening as well as scrutiny and evaluation of tenders and subsequent placement of contract. With this limited objective, GIT is not intended to be complete by itself and the rest of this document - SIT, GCC and SCC in particular may also be thoroughly studied before filling up the Tender Document. There would be certain topics covered in GIT/SIT as well as in GCC/ SCC from different perspectives. In case of any conflict between these, provisions of GCC/ SCC would prevail.
- 1.5 The tenderers shall also read the Special Instructions to Tenderers (SIT) related to this purchase, as contained in Section III of these documents and follow the same accordingly. Whenever there is a conflict between the GIT and the SIT, the

provisions contained in the SIT shall prevail over those in the GIT.

2. Language of Tender

The tender submitted by the tenderer and all subsequent correspondence and documents relating to the tender exchanged between the tenderer and BRBNMPL, shall be written in English or Hindi language, unless otherwise specified in the Tender. However, the language of any printed literature furnished by the tenderer in connection with its tender may be written in any other language provided the same is accompanied by Hindi or English translation. For purposes of interpretation of the tender, the English translation shall prevail.

3. Eligible Tenderers

This invitation for tenders is open to all suppliers who fulfill the eligibility criteria specified in these documents. Please refer to Section IX: Qualification/ Eligibility Criteria

4. Eligible Goods and Services

All goods and related services to be supplied under the contract shall have their origin in India or other countries, subject to any restriction imposed in this regard in Section III (SIT). The term "origin" used in this clause means the place where the goods are mined, grown, produced or manufactured or from where the related services are arranged and supplied.

5. Tendering Expense

The tenderer shall bear all costs and expenditure incurred and/ or to be incurred by it in connection with its tender including preparation, mailing and submission of its tender and for subsequent processing the same. BRBNMPL will, in no case be responsible or liable for any such cost, expenditure etc regardless of the conduct or outcome of the tendering process.

B TENDER DOCUMENTS

6. Content of Tender Documents

6.1 The tender documents includes:

1. Section I - Notice Inviting Tender (NIT)
2. Section II - General Instructions to Tenderers (GIT)
3. Section III - Special Instructions to Tenderers (SIT)
4. Section IV - General Conditions of Contract (GCC)
5. Section V - Special Conditions of Contract (SCC)
6. Section VI - List of Requirements
7. Section VII - Technical Specifications

8. Section VIII - Quality Control Requirements
9. Section IX — Qualification/ Eligibility Criteria
10. Section X - Tender Form
11. Section XI - Price Schedule
12. Section XII - Questionnaire
13. Section XIII - Bank Guarantee Form for EMD
14. Section XIV - Manufacturer's Authorization Form
15. Section XV - Bank Guarantee Form for Performance Security
16. Section XVI - Contract Form
17. Section XVI I: Letter of Authority for attending a Bid Opening
18. Section XVIII: Shipping Arrangements for Liner Cargoes
19. Section XIX: Proforma of Bills for Payments

6.2 The relevant details of the required goods and services, the terms, conditions and procedure for tendering, tender evaluation, placement of contract, the applicable contract terms and, also, the standard formats to be used for this purpose are incorporated in the above-mentioned documents. The interested tenderers before formulating the tender and submitting the same to BRBNMPL, should read and examine all the terms, conditions, instructions etc. contained in the tender documents. Failure to provide and/ or comply with the required information, instructions etc. incorporated in these tender documents may result in rejection of its tender.

7. Amendments to Tender Documents

7.1 At any time prior to the deadline for submission of tenders, BRBNMPL may, for any reason deemed fit by it, modify the tender documents by issuing suitable amendments) to it.

7.2 Such an amendment will be uploaded in the website and notified in writing by registered/ speed post or by fax / telex / e-mail, followed by copy of the same by suitable recorded post to all prospective tenderers, which have received the tender documents and will be binding on them.

7.3 In order to provide reasonable time to the prospective tenderers to take necessary action in preparing their tenders as per the amendment, BRBNMPL may, at its discretion extend the deadline for the submission of tenders and other allied time frames, which are linked with that deadline.

8. Pre-Bid conference

If found necessary, a pre-bid conference may be stipulated in the SIT, for clarification/ amendment to Technical specifications/techno-commercial conditions in two bid tender.

9. Clarification of Tender Documents

A Tenderer requiring any clarification or elucidation on any issue of the tender documents may take up the same with BRBNMPL in writing or by fax ! e-mail! telex. BRBNMPL will respond in writing to such request provided the same is received by BRBNMPL not later than twenty one days (unless otherwise specified in the SIT) prior to the prescribed date of submission of tender. Copies of the query and clarification shall be sent to all prospective bidders who have received the bidding documents.

C PREPARATION OF TENDERS

10. Documents Comprising the Tender

10.1 The tender to be submitted by Tenderer shall contain the following documents, duly filled in, as required:

- a) Tender Form and Price Schedule along with list of deviations (ref Clause 19.19.4) from the clauses of this SBD, if any.
 - b) Documentary evidence, as necessary in terms of GIT clauses 3 and 16 establishing that the tenderer is eligible to submit the tender and, also, qualified to perform the contract if its tender is accepted.
 - c) Documents and relevant details to establish in accordance with GIT clause 17 that the goods and the allied services to be supplied by the tenderer conform to the requirement of the tender documents along with list of deviations if any (ref clause 17.17.3 of GIT).
 - d) Earnest money furnished in accordance with GIT clause 18.18.1 alternatively, documentary evidence as per GIT clause 18.18.2 for claiming exemption from payment of earnest money. and
 - e) Questionnaire as per Section XII.
 - f) Manufacturer's Authorization Form (ref Section XIV, if applicable)
- NB: The tenderers may also enclose in their tenders, technical literature and other documents as and if considered necessary by them.

10.2 A tender, that does not fulfill any of the above requirements and / or gives evasive information / reply against any such requirement, shall be liable to be ignored and rejected.

10.3 Tender sent by fax/email/ telex/ cable shall be ignored.

11. Tender currencies

- 11.1 Unless otherwise specified, the tenderer shall quote only in Indian rupees.
- 11.2 Where the tender condition specifies acceptance of quotations in different currencies, then, for domestic goods, prices shall be quoted in Indian rupees only and for imported goods, prices shall be quoted either in Indian rupees or in the currency stipulated in the SIT, mentioning, inter-alia, the exchange rate adopted for converting foreign currency into Indian Rupees. As regards price(s) for allied services, if any, required with the goods, the same shall be quoted in Indian Rupees if such services are to be performed / undertaken in India.
- 11.3 Tenders, where prices are quoted in any other way shall be treated as unresponsive and rejected.

12. Tender Prices

- 12.1 The Tenderer shall indicate on the Price Schedule provided under Section XI all the specified components of prices shown therein including the unit prices and total tender prices of the goods and services it proposes to supply against the requirement. All the columns shown in the price schedule should be filled up as required. If any column does not apply to a tenderer, same should be clarified accordingly by the tenderer.
- 12.2 If there is more than one schedule in the List of Requirements, the tenderer has the option to submit its quotation for any one or more schedules and, also, to offer special discount for combined schedules. However, while quoting for a schedule, the tenderer shall quote for the complete requirement of goods and services as specified in that particular schedule.
- 12.3 The quoted prices for goods offered from within India (goods manufactured in India or goods of foreign origin already located in India) and that for goods of foreign origin offered from abroad are to be indicated separately in the applicable Price Schedules attached under Section XI.
- 12.4 While filling up the columns of the price schedule, the following aspects should be noted for compliance:
- 12.5 For goods offered from within India (goods manufactured in India or goods of foreign origin already located in India), the prices in the corresponding price schedule shall be entered separately in the following manner:

- a) The price of the goods, quoted ex-factory, ex-showroom, ex-warehouse or off-the-shelf, as applicable, including Goods and services Tax, Customs duty or any other similar duties and taxes already paid or payable on the components and raw material used in the manufacture or assembly of the goods quoted ex-factory etc. or on the previously imported goods of foreign origin quoted ex-showroom etc.
 - b) Goods and Services Tax, which will be payable on the goods in India if the contract is awarded.
 - c) Charges towards inland transportation, insurance and other local costs incidental to delivery of the goods to their final destination as specified in the List of Requirements and
 - d) The price of incidental services, as and if mentioned in List of Requirements.
- 12.6 For goods of foreign origin offered from abroad, the prices in the corresponding price schedule shall be entered separately in the following manner:

- a) The price of goods quoted FAS / FOB port of shipment, CIF port of entry in India or CIF specified place of destination in India as indicated in the List of Requirements,
- b) Wherever applicable, the amount of custom duty and import duty on the goods to be imported.
- c) The charges for inland transportation, insurance and other local costs incidental to delivery of the goods from the port of entry in India to their final destination, as specified in the List of Requirements. and
- d) The charges for incidental services, as and if mentioned in the List of Requirements.

12.7 Additional information and instruction on Duties and Taxes:

For goods offered from within India (goods manufactured in India or goods of foreign origin already located in India), if the Tenderer desires to ask for Goods and services Tax, Customs duty or any other similar duties and taxes to be paid extra, the same must be specifically stated. In the absence of any such stipulation the price will be taken inclusive of such duties and taxes and no claim for the same will be entertained later.

12.8 Goods and Services Tax

- a) If reimbursement of Goods and Services

Tax is intended as extra over the quoted prices, the supplier must specifically say so also indicating the rate, quantum and nature of the tax applicable. In the absence of any such stipulation, it will be presumed that the prices quoted are firm and final and no claim on account of Goods and Services Tax will be entertained after the opening of tenders.

- b) If a Tenderer chooses to quote a price inclusive of Goods and Services Tax and also desires to be reimbursed for variation, if any, in the Goods and Services Tax during the time of supply, the tenderer must clearly mention the same and also indicate the rate and quantum of Goods and Services Tax included in its price. Failure to indicate all such details in clear terms may result in statutory variations being denied to the tenderer.
- c) Subject to sub clauses 12.8 (a) & (b) above, any change in Goods and Services Tax upward / downward as a result of any statutory variation in Goods and Services Tax taking place within original Delivery Period shall be allowed to the extent of actual quantum of Goods and Services Tax paid by the supplier. In case of downward revision in Goods and Services Tax, the actual quantum of reduction of Goods and Services Tax shall be reimbursed to BRBNMPL by the supplier. All such adjustments shall include all reliefs, exemptions, rebates, concession etc. if any obtained by the supplier.

12.9 Goods and Services Tax...contd...

If a tenderer asks for GST to be paid extra, the rate and nature of such taxes applicable should be shown separately. Such taxes will be paid as per the rate at which it is liable to be assessed or has actually been assessed provided the transaction of sale is legally liable to such taxes and is payable as per the terms of the contract.

12.10 Goods and Services Tax...contd...

- i) The tenderer should quote the exact percentage of GST that they will be charging extra.
- ii) While quoting the rates, tenderers should pass on (by way of reduction in prices) the input tax credit that would become available to them by switching over to the new system of GST from the existing system of tax, duly stating the

quantum of such credit per unit of the item quoted for.

- iii) The tenderer while quoting for tenders should give the following declaration:
"We agree to pass on such additional input tax credit as may become available in future in respect of all the inputs used in the manufacture of the final product on the date of supply under the GST scheme by way of reduction in price and advise the purchaser accordingly."
- iv) The supplier while claiming the payment shall furnish the following certificate to the paying authorities:
"We hereby declare that additional input tax credit to the tune of Rs..... has accrued and accordingly the same is being passed on to the purchaser and to that effect the payable amount may be adjusted."

12.11 Duties, taxes and other levies of Local bodies

Unless otherwise stated in the SIT, the goods supplied against contracts placed by BRBNMPL are not exempted from levy of duties, taxes and other Levies of local bodies. In such cases, the supplier should make the payment to avoid delay in supplies and forward the receipt of the same to the purchasing department for reimbursement and, also, for further necessary action.

In cases where exemption is available, suppliers should obtain the exemption certificate from the purchasing department to avoid payment of such levies and taxes.

12.12 Duties / Taxes on Raw Materials

BRBNMPL is not liable for any claim from the supplier on account of fresh imposition and / or increase (including statutory increase) of Customs duty, Goods and Services Tax or any other similar duties and taxes on raw materials and/or components used directly in the manufacture of the contracted goods taking place during the pendency of the contract, unless such liability is specifically agreed to in terms of the contract.

12.13 Imported Stores not liable to Above-mentioned Taxes and Duties:

Above mentioned Taxes and Duties are not leviable on imported goods (goods of foreign origin offered from abroad) and hence would not be reimbursed.

12.14 Customs Duty:

In respect of imported goods of foreign origin offered from abroad, the tenderer shall specify the rate as well as the total amount of customs duty payable. The tenderer shall also indicate the corresponding Indian Customs Tariff Number applicable for the goods in question.

12.14.1 For transportation of imported goods offered from abroad, relevant instructions as incorporated under GCC Clause 11 shall be followed.

12.14.2 For insurance of goods to be supplied, relevant instructions as provided under GCC Clause 12 shall be followed.

12.14.3 Unless otherwise specifically indicated in this tender document, the terms FOB, FAS, CIF etc. for imported goods offered from abroad, shall be governed by the rules & regulations prescribed in the current edition of INCOTERMS, published by the International Chamber of Commerce, Paris

12.14.4 The need for indication of all such price components by the tenderers, as required in this clause (viz., GIT clause 12) is for the purpose of comparison of the tenders by BRBNMPL and will no way restrict BRBNMPL's right to award the contract on the selected tenderer on any of the terms offered.

13. Authorized Dealer/Distributor/Representative

Principal manufacturers/OEMs, manufacturers under license or their authorized

Dealers/Distributors/Representatives who are exclusively appointed by the principal manufacturers/OEMs to represent them in the country shall be eligible to apply or to take part in the bid. One Principal manufacturer/OEM can authorize only one Dealer/Distributor/Representative for a particular tender. Similarly, one authorized Dealer/Distributor/Representative can represent only one Principal manufacturer/OEM in a particular tender. There can be only one bid from either: -

1. The Principal manufacturer/OEM directly; or
2. Any of its branch/division/subsidiary; or

3. Authorized Dealer/Distributor/Representative on behalf of the Principal manufacturer/OEM

Note

- (i) In a tender, either the Principal manufacturer/OEM or its authorized dealer/ distributor/representative can bid but both cannot bid simultaneously in the same tender.
- (ii) In case the bidder is an authorized Dealer/Distributor/Representative, except in case of Commercially-Off-the-Shelf (COTS) items, then
 - (a) the bidder should have been associated as authorised dealer/ distributor/representative of the same or other Principal Manufacturer/OEM for same set of services as in present bid (supply, installation, satisfactorily commissioning, after sales service as the case may be) for same or similar 'Product' for past three years ending on 31st March (or any other year ending followed in relevant country) of the previous financial year; and
 - (b) the principal manufacturer/OEM should furnish a legally enforceable tender-specific authorisation in the prescribed form (Section XIV of SBD) assuring full guarantee and warranty obligations as per the general and special conditions of contract and to abide by other tender terms and conditions. The letter of authorisation should be signed by a person competent and having the power of attorney to legally bind the manufacturer; and
 - (c) the principal manufacturer/OEM should meet all the pre-qualification criteria without exemption.
- (iii) For commercially off the shelf (COTS) items with clear and standard specifications, a valid dealership certificate will have to be submitted.

14. Firm Price / Variable Price

14.1 Unless otherwise specified in the SIT, prices quoted by the tenderer shall remain firm and fixed during the currency of the contract and not subject to variation on any account.

14.2 In case the tender documents require offers on variable price basis, the price quoted by the tenderers will be subject to adjustment during original Delivery Period to take care of the changes in the cost of labour and material components in accordance with the price variation formula to be specified in the SIT. If a

tenderer submits firm price quotation against the requirement of variable price quotation, that tender will be prima-facie acceptable and considered further, taking price variation asked for by the tenderer as zero.

14.3 However, as regards taxes and duties, if any, chargeable on the goods and payable, the conditions stipulated in GIT clause 12 will apply for both firm price tender and variable price tender.

14.4 Subject to provisions of Clause 11 above, where prices are quoted in foreign currencies, involving imports - Foreign Exchange Rate Variation (ERV) would be borne by the Purchaser within the original Delivery Period. The offer of the Tenderer should indicate import content and the currency used for calculating import content.

14.5 Base Exchange rate of each major currency used for calculating FE content of the contract should be indicated. The base date of ERV would be contract date and variation on the base date can be given up to the midpoint manufacture, unless firm has already indicated the time schedule within which material will be imported by the firm.

14.6 In case delivery period is refixed / extended, ERV will not be admissible, if this is due to default of the supplier.

14.7 Documents for claiming ERV:

- i. A bill of ERV claim enclosing working sheet
- ii. Banker's Certificate/debit advice detailing FE paid and exchange rate
- iii. Copies of import order placed on supplier
- iv. Invoice of supplier for the relevant import order

15. Alternative Tenders

Unless otherwise specified in the Schedule of Requirements, alternative tenders shall not be considered.

16. Documents Establishing Tenderer's Eligibility and Qualifications

16.1 Pursuant to GIT clause 10, the tenderer shall furnish, as part of its tender, relevant details and documents establishing its eligibility to quote and its qualifications to perform the contract if its tender is accepted.

16.2 The documentary evidence needed to establish the tenderer's qualifications shall fulfil the following requirements:

a) In case the tenderer offers to supply goods, which are manufactured by some other firm, the tenderer has been duly authorized by the goods manufacturer to quote for and supply the goods to BRBNMPL. The tenderer shall submit the Manufacturer's Authorization Letter to this effect as per the standard form provided under Section XIV in this document.

b) The tenderer has the required financial, technical and production capability necessary to perform the contract and, further, it meets the qualification criteria incorporated in the Section IX in these documents.

c) In case the tenderer is not doing business in India, it is / will be duly represented by an authorized Dealer/Distributor/Representative stationed in India fully equipped and able to carry out the required contractual functions and duties of the supplier including after sale service, maintenance & repair etc. of the goods in question, stocking of spare parts and fast moving components and other obligations, if any, specified in the conditions of contract and/or technical specifications.

17. Documents establishing Good's Conformity to Tender document

17.1 The tenderer shall provide in its tender the required as well as the relevant documents like technical data, literature, drawings etc. to establish that the goods and services offered in the tender fully conform to the goods and services specified by BRBNMPL in the tender documents. For this purpose, the tenderer shall also provide a clause-by-clause commentary on the technical specifications and other technical details incorporated by BRBNMPL in the tender documents to establish technical responsiveness of the goods and services offered in its tender.

17.2 In case there is any variation and/or deviation between the goods & services prescribed by BRBNMPL and that offered by the tenderer, the tenderer shall list out the same in a chart form without ambiguity along with justification, and provide the same along with its tender.

17.3 If a tenderer furnishes wrong and/or misleading data, statement(s) etc. about technical acceptability of the

goods and services offered by it, its tender will be liable to be ignored and rejected in addition to other remedies available to BRBNMPL in this regard.

18. Earnest Money Deposit (EMD)

- 18.1 Pursuant to GIT clause 10.1(d) the tenderer shall furnish along with its tender, earnest money for amount as shown in the List of Requirements. The earnest money is required to protect BRBNMPL against the risk of the Tenderer's unwarranted conduct as amplified under sub-clause 23.23.2 below.
- 18.2 The tenderers who are currently registered and, also, will continue to remain registered during the tender validity period with Central Purchase Organisation or as a Micro and Small Enterprise (MSE) as defined in MSEs Order 2012 issued by Ministry of Micro, Small and Medium Enterprises (MSME) or as a Startup as recognised by Department for Promotion of Industry and Internal Trade (DPIIT), are exempted from payment of earnest money. In case the tenderer falls in these categories, it should furnish certified copy of its valid registration details (registration with CPO or as a MSE or as a Startup, as the case may be).
Micro & Small Enterprises must attach Registration Certificate issued by DIC / KVIC / KVIB / Coir Board / NSIC / Directorate of Handicrafts and Handlooms, or any other body specified by MSME for authentication such as Udyog Aadhaar Memorandum / Acknowledgment.
- 18.3 The earnest money shall be denominated in Indian Rupees or in equivalent foreign exchange in case of GTE/ICB tenders.
- 18.4 The earnest money shall be furnished in one of the following forms:
- Account Payee Demand Draft from any scheduled commercial bank in India or
 - Banker's cheque from any scheduled commercial bank in India or
 - Online Bank Transfer (Proof of online transfer to be submitted)
 - Other Electronic Modes of Payment
 - Debit Card powered by RuPay
 - Unified Payments Interface (UPI) (BHIM-UPI)
 - Unified Payments Interface Quick

Response Code (UPI QR Code) (BHIM-UPI QR Code)

- Bank Guarantee issued/confirmed by any scheduled commercial bank in India in the proforma given in Section XIII of SBD in case the amount is more than Rs.5 lakh and in case of foreign bidders in GTE/ICB tenders (in equivalent foreign exchange amount)
- 18.5 The earnest money shall be valid for a period of forty-five days beyond the validity period of the tender.
- 18.6 Unsuccessful tenderers' earnest monies will be returned to them without any interest whatsoever within 15 days of determination of the tenderers as unsuccessful after opening of Price Bid. The successful bidder's bid security (EMD) can be adjusted against the SD or returned as per the terms of the tender document. The balance can be deducted from the supplier's bill/invoice before release of payment. Unlike Procurement of Works, in Procurement of Goods, the concept of taking part of Performance Guarantee as money retained from first or progressive bills of the supplier is not acceptable.
- 18.7 Earnest money of a tenderer will be forfeited, if the tenderer withdraws or amends its tender or impairs or derogates from the tender in any respect within the period of validity of its tender. The successful tenderer's earnest money will be forfeited if it fails to furnish the required performance security within the specified period.

19. Tender Validity

- 19.1 If not mentioned otherwise in the SIT, the tenders shall remain valid for acceptance for a period of 90 days (Ninety days) in case of single bid tender system and 120 days in case of two-bid system after the date of tender opening prescribed in the tender document. Any tender valid for a shorter period shall be treated as unresponsive and rejected.
- 19.2 In exceptional cases, the tenderers may be requested by BRBNMPL to extend the validity of their tenders up to a specified period. Such request(s) and responses thereto shall be conveyed by surface mail or by fax/email/ telex/cable followed by surface mail. The tenderers, who agree to extend the tender validity, are to extend the same without any change or modification of their original

- tender and they are also to extend the validity period of the EMD accordingly.
- 19.3 In case the day up to which the tenders are to remain valid falls on/ subsequently declared a holiday or closed day for BRBNMPL, the tender validity shall automatically be extended up to the next working day.
- 19.4 Compliance with the Clauses of this Tender Document: Tenderer must comply with all the clauses of this Tender Document. In case there are any deviations, these should be listed in a chart form without any ambiguity along with justification.
- 20. Signing and Sealing of Tender**
- 20.1 An authenticated copy of the document which authorizes the signatory to commit on behalf of the firm shall accompany the offer. The individual signing the tender or any other documents connected therewith should clearly indicate his full name and designation and also specify whether he is signing,
- (a) As Sole Proprietor of the concern or as attorney of the Sole Proprietor;
- (b) As Partner (s) of the firm;
- (c) As Director, Manager or Secretary in case the of Limited Company duly authorized by a resolution passed by the Board of Directors or in pursuance of the Authority conferred by Memorandum of Association.
- 20.2 The authorized signatory of the tenderer must sign the tender at appropriate places and initial the remaining pages of the tender.
- 20.3 The tenderers shall submit their tenders as per the instructions contained in GIT Clause
- 20.4 Unless otherwise mentioned in the SIT, a tenderer shall submit two copies of its tender marking them as "Original" and "Duplicate".
- 20.5 The original and other copies of the tender shall either be typed or written in indelible ink and the same shall be signed by the tenderer or by a person(s) who has been duly authorized to bind the tenderer to the contract. The letter of authorization shall be by a written power of attorney, which shall also be furnished along with the tender.
- 20.6 All the copies of the tender shall be duly signed at the appropriate places as indicated in the tender documents and all other pages of the tender including printed literature, if any shall be

initialled by the same person(s) signing the tender. The tender shall not contain any erasure or overwriting, except as necessary to correct any error made by the tenderer and, if there is any such correction; the same shall be initialled by the person(s) signing the tender.

- 20.7 The tenderer is to seal the original and each copy of the tender in separate envelopes, duly marking the same as "Original", "Duplicate" and so on and writing the address of BRBNMPL and the tender reference number on the envelopes. The sentence 'NOT TO BE OPENED' before (The tenderer is to put the date & time of tender opening) are to be written on these envelopes. The inner envelopes are then to be put in a bigger outer envelope, which will also be duly sealed, marked etc. as above. If the outer envelope is not sealed and marked properly as above, BRBNMPL will not assume any responsibility for its misplacement, premature opening, late opening etc.
- 20.8 For purchasing capital equipment, high value plant, machinery etc. of complex and technical nature, tender document will seek quotation in two parts (Two Bid System) - first part containing the relevant technical details of the equipment / machinery etc., and in the second part, price quotation along with other allied issues. First part will be known as 'Technical Bid', and the second part 'Financial bid'. Tenderer shall seal separately 'Technical Bid' and 'Financial bid' and covers will be suitably super scribed. Both these sealed covers shall be put in a bigger cover and sealed and evaluation would be done as described in clause 25.24.4 below. Further details would be given in SIT, if considered necessary.
- 20.9 If permitted in the SIT, the tenderer may submit its tender through e-tendering procedure.

D SUBMISSION OF TENDERS

21. Submission of Tenders

- 21.1 Unless otherwise specified, the tenderers are to deposit the tenders in the tender box kept for this purpose at a place as indicated in para 1 of NIT. In case of bulky tender, which cannot be put into tender box, the same shall be submitted by the tenderer by hand to the designated officers of BRBNMPL, as indicated in clause 1 of NIT. The officer receiving the tender will give the

tenderer an official receipt duly signed with date and time.

- 21.2 The tenderers must ensure that they deposit their tenders not later than the closing time and date specified for submission of tenders. In the event of the specified date for submission of tender falls on / is subsequently declared a holiday or closed day for BRBNMPL, the tenders will be received up to the appointed time on the next working day.

22. Late Tender

A tender, which is received after the specified date and time for receipt of tenders will be treated as "late" tender and will be ignored.

23. Alteration and Withdrawal of Tender

- 23.1 The tenderer, after submitting its tender, is permitted to alter / modify its tender so long as such alterations / modifications are received duly signed, sealed and marked like the original tender, within the deadline for submission of tenders. Alterations / modifications to tenders received after the prescribed deadline will not be considered.
- 23.2 No tender should be withdrawn after the deadline for submission of tender and before expiry of the tender validity period. If a tenderer withdraws the tender during this period, it will result in forfeiture of the earnest money furnished by the tenderer in its tender besides other sanctions by BRBNMPL.

E TENDER OPENING

24. Opening of Tenders

- 24.1 BRBNMPL will open the tenders at the specified date and time and at the specified place as indicated in clause 1 of NIT. In case the specified date of tender opening falls on / is subsequently declared a holiday or closed day for BRBNMPL, the tenders will be opened at the appointed time and place on the next working day.
- 24.2 Authorized representatives of the tenderers, who have submitted tenders on time may attend the tender opening, provided they bring with them letters of authority as per the format in SBD XVII from the corresponding tenderers. The tender opening official(s) will prepare a list of the representatives attending the tender opening. The list will contain the representatives' names & signatures

and corresponding tenderers' names and addresses.

- 24.3 During the tender opening, the tender opening official(s) will read the salient features of the tenders like description of the goods offered, price, special discount if any, delivery period, whether earnest money furnished or not and any other special features of the tenders, as deemed fit by the tender opening official(s).
- 24.4 In the case of two bid system mentioned in clause 20.8 above, the technical bids are to be opened in the first instance, at the prescribed time and date. These bids shall be scrutinized and evaluated by the competent committee / authority with reference to parameters prescribed in the tender document. Thereafter, in the second stage, the financial bids of only the technically acceptable offers (as decided in the first stage) shall be opened for further scrutiny and evaluation. Other financial bids would be returned unopened to the respective bidders under Registered AD / Reliable Courier or any other mode with proof of delivery.

F SCRUTINY AND EVALUATION OF TENDERS

25. Basic Principle

Tenders will be evaluated on the basis of the terms & conditions already incorporated in the tender document, based on which tenders have been received and the terms, conditions etc. mentioned by the tenderers in their tenders. No new condition will be brought in while scrutinizing and evaluating the tenders.

26. Preliminary Scrutiny of Tenders

- 26.1 The tenders will first be scrutinized to determine whether they are complete and meet the essential and important requirements, conditions etc. as prescribed in the tender document, the tenders, that do not meet the basic requirements, are liable to be treated as unresponsive and ignored.
- 26.2 The following are some of the important aspects, for which a tender may be declared unresponsive and ignored;
- a) Tender is not in the prescribed format or is unsigned or not signed as per the stipulations in the bid document.
 - b) Tenderer is not eligible.
 - c) Tender validity is shorter than the required period.

- d) Required EMD has not been provided or exemption from EMD is claimed without acceptable proof of exemption.
- e) Tenderer has quoted for goods manufactured by a different firm without the required authority letter from that manufacturer.
- f) Tenderer has not agreed to give the required performance security.
- g) Goods offered are sub-standard, not meeting the required specification etc.
- h) Tenderer has not agreed to essential condition(s) specially incorporated in the tender enquiry.
- i) Against a schedule in the List of Requirement (incorporated in the tender enquiry), the Tenderer has not quoted for the entire requirement as specified in that schedule. (Example: In a schedule, it has been stipulated that the Tenderer will supply the equipment, install and commission it and also train BRBNMPL's operators for operating the equipment. The Tenderer has however, quoted only for supply of the equipment).

27. Minor Infirmary / Irregularity / Non-Conformity

If during the preliminary examination, BRBNMPL find any minor infirmity and / or irregularity and / or non-conformity in a tender, BRBNMPL may waive the same provided it does not constitute any material deviation and financial impact and, also, does not prejudice or affect the ranking order of the tenderers. Wherever necessary, BRBNMPL will convey its observation on such 'minor' issues to the tenderer by registered / speed post etc. asking the tenderer to respond by a specified date. If the tenderer does not reply by the specified date or gives evasive reply without clarifying the point at issue in clear terms, that tender will be liable to be ignored.

28. Discrepancy in Prices

- 28.1 If, in the price structure quoted by a tenderer, there is discrepancy between the unit price and the total price (which is obtained by multiplying the unit price by the quantity), the unit price shall prevail and the total price corrected accordingly, unless BRBNMPL feels that the tenderer has made a mistake in placing the decimal point in the unit price, in which case the total price as quoted shall prevail over the unit price

and the unit price corrected accordingly.

- 28.2 If there is an error in a total price, which has been worked out through addition and / or subtraction of subtotals, the subtotals shall prevail and the total corrected; and
- 28.3 If there is a discrepancy between the amount expressed in words and figures, the amount in words shall prevail, subject to sub clause 28.1 and 28.2 above.
- 28.4 If, as per the judgment of BRBNMPL, there is any such arithmetical discrepancy in a tender, the same will be suitably conveyed to the tenderer by registered / speed post. If the tenderer does not agree to the observation of BRBNMPL, the tender is liable to be ignored.

29. Discrepancy between original and copies of Tender

In case any discrepancy is observed between the text etc. of the original and that of other copies of the same tender set, the text etc. of the original shall prevail. Here also, BRBNMPL will convey its observation suitably to the tenderer by registered / Speed post and, if the tenderer does not accept BRBNMPL's observation, that tender will be liable to be ignored.

30. Clarification of Bids

During evaluation and comparison of bids, purchaser may, at its discretion ask the bidder or clarification of its bid. The clarification should be received within 7 days from the bidder from date of receipt of such request. The request for clarification shall be in writing and no change in prices or substance of the bid shall be sought, offered or permitted. No post bid clarification at the initiative of the bidder shall be entertained.

31. Qualification / Eligibility Criteria

Tenders of the tenderers, who do not meet the required qualification / eligibility criteria prescribed in Section IX, will be treated as unresponsive and will not be considered further.

32. Conversion of tender currencies to Indian Rupees

In case the tender document permits the tenderers to quote their prices in different currencies, all such quoted prices of the responsive tenderers will be converted to a single currency viz., Indian Rupees for the purpose of

equitable comparison and evaluation, as per the Bill Currency Selling exchange rates established by the State Bank of India for similar transactions, as on the date of tender opening.

33. Schedule-wise Evaluation

In case the List of Requirements contains more than one schedule, the responsive tenders will be evaluated and compared separately for each schedule. The tender for a schedule will not be considered if the complete requirements prescribed in that schedule are not included in the tender. However, as already mentioned in GIT sub clause 12.2, tenderers have the option to quote for any one or more schedules and offer discounts for combined schedules. Such discounts, wherever applicable, will be taken into account to determine the tender or combination of tenders offering the lowest evaluated cost for BRBNMPL in deciding the successful tenderer for each schedule, subject to that tenderer(s) being responsive.

34. Comparison on CIF/FOR Destination Basis

Unless mentioned otherwise in Section - III - Special Instructions to Tenderers and Section - VI - List of Requirements, the comparison of the responsive tenders shall be on CIF/FOR destination basis, duly delivered, commissioned, etc. as the case may be.

35. Additional Factors and Parameters for Evaluation and Ranking of Responsive Tenders

35.1 Further to GIT Clause 33 above, BRBNMPL's evaluation of a tender will include and take into account the following:

- a) In the case of goods offered from within India (goods manufactured in India or goods of foreign origin already located in India), Goods and Services Tax or any other similar duties and taxes, which will be contractually payable (to the tenderer), on the goods if a contract is awarded on the tenderer; and
- b) In the case of goods of foreign origin offered from abroad, customs duty and other similar import duties/taxes, which will be contractually payable (to the tenderer) on the goods if the contract is awarded on the tenderer.

35.2 BRBNMPL's evaluation of tender will also take into account the additional

factors, if any, incorporated in SIT in the manner and to the extent indicated therein.

35.3 As per policies of the Government from time to time, the purchaser reserves its option to give price preference to Micro & Small Scale Industries in comparison to the large scale Industries. This price preference cannot however be taken for granted and every endeavour need to be made by such firms to bring down cost and achieve competitiveness.

35.4 If the tenders have been invited on variable price basis, the tenders will be evaluated, compared and ranked on the basis of the position as prevailing on the day of tender opening and not on the basis of any future date.

36. Tenderer's capability to perform the contract

36.1 BRBNMPL, through the above process of tender scrutiny and tender evaluation will determine to its satisfaction whether the tenderer, whose tender has been determined as the lowest evaluated responsive tender is eligible, qualified and capable in all respects to perform the contract satisfactorily. If, there is more than one schedule in the List of Requirements, then, such determination will be made separately for each schedule.

36.2 The above mentioned determination will, inter-alia, take into account the tenderer's financial, technical and production capabilities for satisfying all the requirements of BRBNMPL as incorporated in the tender document. Such determination will be based upon scrutiny and examination of all relevant data and details submitted by the tenderer in its tender as well as such other allied information as deemed appropriate by BRBNMPL.

37. Cartel Formation / Pool Rates

Cartel formation or quotation of Pool / Co-ordinated rates, leading to 'Appreciable Adverse Effect on Competition' (AAEC) as identified in Competition Act, 2002, as amended by Competition (Amendment) Act, 2007, would be considered as a serious misdemeanour and would be dealt accordingly as per Clause 44 below.

38. Negotiations

Normally there would be no price negotiations. But BRBNMPL reserves its right to negotiate with the lowest acceptable bidder (L1), who is techno-

commercially cleared / approved for supply of bulk quantity and on whom the contract would have been placed but for the decision to negotiate, under special circumstances in accordance with CVC guidelines. Selection of contractors by negotiations should be a rare exception rather than the rule and may be resorted to only in the exceptional circumstances under the following circumstances: -

- (i) Where the procurement is done on nomination basis (PAC and STE without PAC);
- (ii) Procurement is from a single or limited sources of supply;
- (iii) Procurements where there is suspicion of cartel formation.

39. Contacting BRBNMPL

39.1. From the time of submission of tender to the time of awarding the contract, if a tenderer needs to contact BRBNMPL for any reason relating to this tender enquiry and / or its tender, it should do so only in writing.

39.2. It will be treated as a serious misdemeanour in case a tenderer attempts to influence BRBNMPL's decision on scrutiny, comparison, evaluation and award of the contracts. In such a case the tender of the tenderer shall be liable for rejection in addition to appropriate administrative actions being taken against that tenderer, as deemed fit by BRBNMPL, in terms of clause 44 of GIT.

G AWARD OF CONTRACT

40. BRBNMPL's Right to Accept any Tender and to Reject any or all Tenders

BRBNMPL reserves the right to accept in part or in full any tender or reject any tender without assigning any reason or to cancel the tendering process and reject all tenders at any time prior to award of contract, without incurring any liability, whatsoever to the affected tenderer or tenderers.

41. Award Criteria

Subject to GIT clause 36 above, the contract will be awarded to the lowest evaluated responsive tenderer decided by BRBNMPL in terms of GIT Clause 34.

42. Variation of Quantities at the Time of Award

Normally, there will be no variation of quantities at the time of awarding the contract. However, at the time of

awarding the contract, the quantity to be procured shall be re-judged based on the current data, since the ground situation may have very well changed. In that case, BRBNMPL reserves the right to increase or decrease the tendered quantity by 25 (Twenty-Five) per cent for ordering, if so warranted. A clause would be included in SIT giving further details.

43. Parallel Contracts

BRBNMPL reserves its right to conclude Parallel contracts, with more than one bidder (for the same tender). If this is foreseen at the time of Tendering, a clause would be included in SIT giving further details.

44. Serious Misdemeanours

44.1. Following would be considered serious misdemeanours:

- i. Submission of misleading / false / fraudulent information/ documents by the bidder in their bid
- ii. Submission of fraudulent / un-encashable Financial Instruments stipulated under Tender or Contract Condition.
- iii. Violation of Code of Ethics laid down in Clause 32 of the GCC.
- iv. Cartel formation or quotation of Pool / coordinated rates leading to "Appreciable Adverse Effect on Competition" (AAEC) as identified under the Competition Act, 2002.
- v. Deliberate attempts to pass off inferior goods or short quantities.
- vi. Violation of Fall Clause by Rate Contract holding Firms.
- vii. Attempts to influence BRBNMPL's Decisions on scrutiny, comparison, evaluation and award of Tender.

44.2. Besides, suitable administrative actions, like rejecting the offers or delisting of registered firms, BRBNMPL would ban / blacklist Tenderers committing such misdemeanour, including declaring them ineligible to be awarded BRBNMPL contracts for indefinite or for a stated period.

45. Notification of Award

45.1 Before expiry of the tender validity period, BRBNMPL will notify the successful tenderer(s) in writing, by registered / speed post or by fax / email / telex / cable (to be confirmed by registered / speed post) that its tender for goods & services, which have been selected by BRBNMPL, has been accepted, also briefly indicating therein

the essential details like description, specification and quantity of the goods & services and corresponding prices accepted. The successful tenderer must furnish to BRBNMPL the required performance security within twenty one days from the date of this notification. Relevant details about the performance security have been provided under GCC Clause 6 under Section IV.

45.2 The notification of award shall constitute the conclusion of the contract.

46. Issue of Contract

46.1 Within seven working days of receipt of performance security, BRBNMPL will send the contract form (as per Section XVI) duly completed and signed, in duplicate, to the successful tenderer by registered / speed post.

46.2 Within seven days from the date of issue of the contract, the successful tenderer will return the original copy of the contract, duly signed and dated, to BRBNMPL by registered / speed post.

47. Non-receipt of Performance Security and Contract by BRBNMPL

Failure of the successful tenderer in providing performance security within 21 days of receipt of notification of award and / or returning contract copy duly signed in terms of GIT clauses 45 and 46 above shall make the tenderer liable for forfeiture of its EMD and, also, for further sanctions by BRBNMPL against it.

48. Return of EMD

The earnest money of the successful tenderer and the unsuccessful tenderers will be returned to them without any interest, whatsoever, in terms of GIT Clause 18.6.

49. Publication of Tender Result

The name and address of the successful tenderer(s) receiving the contract(s) will be mentioned in the notice board/bulletin/ web site of BRBNMPL.

Part II: Additional General Instructions Applicable to Specific Types of Tenders:

50. Rate Contract Tenders

50.1 In addition to GIT in Part I above, following GIT will be applicable to rate contract Tenders:

- i. Earnest Money Deposit (EMD) is to be furnished by unregistered bidders only.
- ii. In the Schedule of Requirement, no commitment of quantity is mentioned;

only the anticipated requirement is mentioned without any commitment.

- iii. BRBNMPL reserves the right to conclude more than one rate contract for the same item.
- iv. Unless otherwise specified in SIT, the currency of a Rate Contract would normally be for one year.
- v. During the currency of the Rate Contract, BRBNMPL may withdraw the rate contract by serving suitable notice. The prescribed notice period is generally thirty days.
- vi. During the currency of the Rate Contract, BRBNMPL would have the option to renegotiate the price with the rate contract holders.
- vii. During the currency of the Rate Contract, in case of emergency, BRBNMPL may purchase the same item through ad hoc contract with a new supplier.
- viii. Usually, the terms of delivery in rate contracts are FOR dispatching station.
- ix. Supply orders, incorporating definite quantity of goods to be supplied along with all other required conditions following the rate contract terms, will be issued by nominated Direct Demanding Officers (DDO) for obtaining supplies through the rate contract.
- x. BRBNMPL is entitled to place supply orders up to the last day of the validity of the rate contract and, though supplies against such supply orders will be affected beyond the validity period of the rate contract, all such supply will be guided by the terms & conditions of the rate contract.
- xi. The rate contract will be guided by "Fall Clause" as described below.

50.2 Fall Clause

If the rate contract holder reduces its price or sells or even offers to sell the rate contracted goods, following conditions of sale similar to those of the rate contract, at a price lower than the rate contract price, to any person or organization during the currency of the rate contract, the rate contract price will be automatically reduced with effect from that date for all the subsequent supplies under the rate contract and the rate contract amended accordingly. Any violation of the fall clause would be considered a serious misdemeanour under clause 44 of the GIT and action, as appropriate, would be taken as per provision of that clause.

50.3 Performance Security

Depending on the anticipated overall drawal against a rate contract and, also, anticipated number of parallel rate contracts to be issued for an item, the procuring entity shall consider obtaining Performance Security @ 5% (Five percent) of the value of supply order in the supply orders issued against rate contracts on the rate contract holder.

50.4 Renewal of Rate Contracts

In case it is not possible to conclude new rate contracts before the expiry of existing ones, due to some special reasons, the existing rate contracts would be extended with same terms, conditions etc. for a suitable period, with the consent of the rate contract holders. Rate contracts of the firms, who do not agree to such extension, will be left out, Period of such extension would generally not be more than three months.

51. Prequalification Bidding

51.1 Prequalification Bidding is for short listing of qualified Bidders who fulfil the Prequalification criteria as laid down in SIT or in Section IX of SBD - "Qualification Criteria" for procurement of Goods or Services as listed in Section VI of SBD - "List of Requirements". Short listed Bidders would be informed of their qualification and short listing in accordance with the stipulations laid down in the SIT. Unless otherwise stipulated in the SIT the PQB short listing would be valid only till the next procurement tender. Further conditions will be elaborated in the SIT.

51.2 If stipulated in the SIT, only these short listed qualified bidders would be invited to participate in the Procurement of the requirements. Otherwise SIT may also indicate that instead of floating a separate PQB tender, it may be combined with the Procurement Tender, as a three bid tender. Initially the first Packet containing PQB would be opened and evaluation would be done. Thereafter the rest of tender would be handled as a two bid system for only those bidders who succeed in PQB.

52. Tenders involving Samples

52.1 Normally no sample would be called along with the offer for evaluation.

52.2 Purchaser's Samples: If indicated in the SIT, a Purchaser's sample may be displayed to indicate required characteristics over and above the Specifications for perusal of the bidders. Name and Designation of the Custodian, Place, Dates and Time of inspection of Purchaser's sample will be

indicated in the SIT. The supplies in the contract will have to meet the indicated required characteristics for which the Purchaser's sample was displayed, besides meeting the specification listed in Section VII - "Technical Specifications" of the SBD. He would be issued a sealed Purchaser's sample for the purpose at the time of award of the contract.

52.3 Pre-Production Samples: If stipulated in SIT, successful contractor would be required to submit a Pre-Production sample(s) to the Inspecting Officer/ or the nominated authority mentioned in the contract within the time specified therein. If the Contractor is unable to do so, he must apply immediately to the Office issuing the acceptance of tender for extension of time stating the reasons for the delay. If the Purchaser is satisfied that a reasonable ground for an extension of time exists, he may allow such additional time as he considers to be justified (and his decision shall be final) with or without alteration in the delivery period stipulated in the contract and on such conditions as he deems fit. In the event of the failure of the Contractor to deliver the pre-production sample by the date specified in the acceptance of tender or any other date to which the time may be extended as aforesaid by the Purchaser or of the rejection of the sample, the Purchaser shall be entitled to cancel the contract and, if so desired, purchase or authorize the purchase of the stores at the risk and cost of the Contractor (unless specified otherwise in the SIT). In such an event, in case of Security Items where urgency develops due to such delays, BRBNMPL reserves its right to procure not more than one year's requirement against this "Risk & Cost" tender from existing pre-qualified and security cleared firms. Bulk production and supply will only be allowed if this sample(s) pass the Tests laid down in the Section VIII "Quality Control Requirements" in the SBD.

52.4 Testing of Samples: Tests, procedures and testing laboratories for testing samples would be detailed in the Section VIII - "Quality Control Requirements" in the SBD.

52.5 Validation / Prolonged Trials: If specified in SIT or in the Section VIII - "Quality Control Requirements" in the

SBD, pre-production samples may have to undergo validation or extended trial before their performance can be declared satisfactory.

52.6 Parameters Settings and duration of Validation Tests would be indicated in the Section VIII - "Quality Control Requirements" in the SBD. It would also stipulate the period or event marking end of validation trials. It would also be indicated therein whether the Permission to start bulk production will have to wait full validation or it can go on in parallel.

53. Expression of Interest (EOI) Tenders:

53.1 EOI tenders are floated for short listing firms who are willing and qualified for: -

- i. Registration of Vendors for Supply of particular Stores or certain categories of Stores.

- ii. Development of new items or Indigenization of Imported stores

53.2 The qualification / eligibility criteria required and the format of submission of such Data would be indicated in the Section IX - "Qualification Criteria" in the SBD.

53.3 Objectives and scope of requirement would be indicated in the Section VI - "List of Requirements" in the SBD. Indicative quantity required yearly and its future requirements would also be indicated.

53.4 In case of EOI for Development of new Items or for Indigenization, prospective firms would be given opportunity to inspect the Machine / Item at the place of installation at the place, dates and Time mentioned in SIT.

53.5 In case EOI is for registration of vendors, Registration Fees and validity period of registration would be detailed in the SIT.

53.6 Short List of Suppliers: The suppliers shall be evaluated for short listing, inter-alia, based on their past experience of supplying goods in similar context, financial strength, technical capabilities etc. Each supplier will be assigned scores based on weightages assigned to each of the criteria mentioned in the Section IX - "Qualification Criteria" in the SBD.

53.7 If stipulated in the SIT, the Firm's capacity and Capability may be assessed by a nominated Committee or by a third party nominated by BRBNMPL.

53.8 All suppliers who secure the minimum required marks (normally 50% unless otherwise specified in the Section IX) would be short listed. Section IX may alternatively specify minimum qualifying requirement for each of the criteria i.e. minimum years of experience, minimum number of assignments executed, minimum turnover etc. Under such circumstances, all suppliers who meet the minimum requirement, as specified, will be short listed.

53.9 In case of EOI for registration of vendors, registration letters would be issued to the short listed tenderers.

53.10 In case of EOI for development / indigenization, these shortlisted tenderers would only be allowed to participate in the subsequent development/ indigenization tenders.

54. Tenders for Disposal of Scrap

54.1 Introduction: The tender is for Sale of Scrap material lying at various locations. Details of scrap for sale including Description, Present Condition, Lot Size and its Location would be given in the Section VI - "List of Requirements".

54.2 "As Is; Where Is; Whatever Is" Basis of This Sale:

54.2.1 This sale of Scrap is strictly on "As is; Where is; Whatever is" basis. Tenderer must satisfy himself on all matters with regard to quality, quantity, nature of stores etc., before tendering as no complaint or representation of any kind shall be entertained after the safe contract is concluded.

54.2.2 The description of lot in the particulars of sale has been given for the purpose of identification thereof only and the use of such description shall not constitute the sale thereof to be sale by description and no sale shall be invalid by reason of any defect or deviation or variation in any lot or on account of any lot not being exactly described and the purchaser shall not be entitled to claim any damage or compensation whatsoever on account of such fault, error in description, weight or the like.

54.2.3 All quantities of scrap whether by weight or measurement mentioned in the Tender notice are only approximate and should the quantity, on actual weight or measurement basis as the case may be and whenever delivered on

such basis, works out less than the advertised and for projected quantity, the BRBNMPL shall not under any circumstances be liable to make good any such deficiency

54.2.4 BRBNMPL reserves right to increase or decrease the quantity of any item or items or terminate the contract at any stage by giving one week's notice. No claim whatsoever shall lie against the BRBNMPL on account of such termination of the contract or variation in the quantity.

54.2.5 BRBNMPL shall have the right to remove certain items which it feels were not intended for sale but were inadvertently made a part of the scrap material or of the lot offered for sale lying at the premises or were joined or attached to the material offered for sale.

54.2.6 Tenderers desirous of purchasing and participating in the tender must visit the site before submitting the offer, after taking due permission from the concerned Stock Holders. The Tenderers submitting the offers shall be deemed to have visited the site and acquainted themselves thoroughly with materials intended for sale in all respect.

54.2.7 Any person giving offer shall be deemed to have made himself fully conversant with the Terms and Conditions of the Tender Sale, as well as the location and condition of the materials being sold and shall be deemed to have agreed to all the stated terms and conditions herein under.

54.3 Submission of Offer

54.3.1 Unless specified otherwise in the SIT, tenders shall hold good for acceptance for a minimum period of 90 days (ninety days) from the date of opening of the tenders. The offers of the tenderers shall be irrevocable.

54.3.2 The BRBNMPL reserves right to reject any offer without assigning any reason there for.

54.3.3 Unless otherwise stated in the SIT, the amount of EMD in such tenders would be 5% of the value of the tender. The Earnest Money shall be forfeited if the tenderer unilaterally withdraws amends, impairs or derogates from his offer in any respect within the period of validity of his offer.

54.3.4 If the offer of the tenderer is not accepted by the BRBNMPL, the Earnest Money deposit made by the tenderer shall be refunded to him. No interest shall be payable on such refunds. The EMD deposited by the successful tenderer shall remain with the BRBNMPL till payment of the security deposit (SD) money, as stipulated in relevant Clause, has been made. It may be adjusted as part of the total SD money at the discretion of the BRBNMPL.

54.3.5 Duties, taxes and other levies of local bodies, whatever in force, shall be payable extra by the purchaser as per rules applicable to BRBNMPL. Current and valid PAN and Goods and Services Tax Identification Number (GSTIN), wherever applicable, must be provided in the Bid of the Tenderer.

54.3.6 All arrangement for lifting and transportation of scrap material, including manpower, crane, transport vehicle and trolley etc., if required shall be made by the purchaser concerned only and the BRBNMPL shall not provide or help in providing any such arrangements and the rate quoted by the purchaser must include such and all incidental charges.

54.3.7 Registered dealers who are exempted from payment of Goods and Services Tax must give reference to Goods and Services Tax laws which provides such exemption or submit any certificate as issued by the Goods and Services tax authorities and shall be required to submit necessary form duly completed in all respect to BRBNMPL or its representatives before obtaining delivery order, duly signed by the partner of the firm or the person authorized to do so.

54.3.8 Evaluation of tenders for Disposal of scrap will be done on similar basis as Tenders for Procurement of Goods, except that the selection of the bidders shall be on the basis of the highest responsive Bidder (H1). In case full quantity is not offered to be taken by the Highest Bidder, parallel contracts would be placed.

54.4 Notification of Acceptance and Award of Contract:

54.4.1 The successful tenderer, herein after referred to as purchasers, shall have to submit security deposit (SD) @ 10% of the total sale value of the contract

within 5 working days of issue of the sale contract (excluding the date of issue of sale contract). The SD shall be deposited in the form of account payee demand draft drawn on any scheduled commercial bank in India in favour of Bharatiya Reserve Bank Note Mudran Private Limited or through online transfer or through other electronic mode of payment as mentioned in clause 3 of NIT in connection with EMD.

54.4.2 The purchaser has to pay balance payment within 20 days from the date of notification of acceptance, which is to be issued by BRBNMPL or his authorized representative, in the form of account payee demand draft drawn on any scheduled commercial bank in India in favour of Bharatiya Reserve Bank Note Mudran Private Limited or through online transfer or through other electronic mode of payment. In case of any, default to deposit balance payment, BRBNMPL reserves right to terminate the contract and forfeit the security deposit.

54.5 Disposal Tenders for Security and Sensitive Machinery and Items:

54.5.1 Non-Misuse Declaration: The bidder is required to give an undertaking that he or his employees or legal heirs will ensure that such items purchased from BRBNMPL, will be utilized only for scrap recovery and will not be misused for any other purpose. He will also ensure that this undertaking is honoured and it got underwritten from further down the line scrap processors / re-purchasers, if any. In case his firm changes hands, it will be his responsibility to ensure that the new owners honour and underwrite this undertaking.

54.5.2 If stipulated in SIT delivery would be given only in dismantled / cut-up condition.

55. Development and Indigenization Tenders:

55.1 Already developed firms or firms who have already received development orders for the item (with whatever results) would not be considered in such tenders.

55.2 If specified in SIT the contract documents may be issued free of cost, and submission of earnest money deposit and security deposit may be relaxed.

55.3 If specified in SIT, The Tenderers may quote separately for

- i. Price / rate for bulk supply of item in development / indigenization supplies and
- ii. Separately, cost of development including cost of pre-production samples. Firms would be paid only for the number of samples specified in the Tender. If he has to manufacture more samples due to failure of earlier one, he would not be paid for it.

55.4 L1 would be determined on the basis of rate of item quoted including reference to total cost of the development cost (including the cost of prototype) plus the notional total cost of quantities that will be required over next three years, wherever applicable.

55.5 Development contracts may, as far as feasible, be concluded with two or more contractors in parallel.

55.6 The ratio of splitting of the supply order between various development agencies / firms in cases of parallel development, including criteria thereof, would be specified in the SIT.

55.7 However, in case the requirement is meagre and complex technology is involved, or quantity of the equipment / spares is limited/small/uneconomic if distributed between two vendors, the entire order could be placed upon the L1 vendor only.

55.8 If specified in SIT, Advance and Intermediate Payment to Suppliers may be allowed.

55.9 Quantity for Development Commitment
In Next three years, after the newly developed firm is able to successfully complete Development orders with $\pm 5\%$ tolerances, 20% of annual quantity requirement may be reserved for Newly Developed firms.

55.10 Period of Development Commitment
A newly developed firm would be granted this facility till only three years after completing the initial Development order. However this facility is not a bar to the firm from competing with already established firms for quantities larger than 20% provided their prices and performance so warrant. Thereafter they would have to compete on equal terms with other already developed firms.

(To be signed & stamped and submitted along with Techno-commercial Bid Part -I)

Part II: Additional General Instructions Applicable to Specific Types of Tenders:

1. Compliance of Security Norms:
 - a) Bharatiya Reserve Bank Note Mudran Pvt. Limited, Bengaluru is a security organization. Hence the bidder shall have to abide by the prevailing security Norms. Any of the bidder's employee/works man/labour deployed at site found by the Company as having doubtful integrity, shall be removed from the premises at the risk and cost.
 - b) The bidder shall provide security provisions to check infiltration, and safeguard of the works till the complete work is handed over. Nothing, extra shall be paid to the bidder by the BRBNMPL on this account.
2. Safety & Security Measures:
 - a) The contractor should scrupulously conform to the safety and security norms and stipulations while working in the security area. The contractor should maintain site clearance during the progress of the work and also after the completion of the work.
 - b) The Contractor will be required to take –Workmen's Compensation Insurance' policy to all of his workmen engaged for the said job and copy of the same to be submitted.
 - c) It shall be the sole responsibility of the contractor to ensure safety to all his workers. The contractor shall take all the precaution during execution of work against any hazards, personnel injury or any damage to the property. The contractor shall provide adequate safety gadgets to the workmen as per norms.
 - d) In respect of all labour, directly or indirectly employed on the works for the performance and execution of the contractor's work under the contract, the contractor shall at his own expense arrange for all the safety provisions as listed in (i) safety code forming part of the contract documents (ii) Indian Standards Regulations, Rules and orders made there under and such other acts as applicable.
 - e) Precautions as stated in the safety clause are the minimum necessary and shall not preclude the Contractor taking additional safety precautions as may be warranted for the particular type of work or situations. Also mere observance of these precautions shall not absolve the contractor of his liability in case of loss or damage to property or injury to any person including the contractor's labour, the BRBNMPL representatives or any member of the public or resulting in the death of any of these.
 - f) Protective gear such as safety Masks/Helmets, Ear Muffler, Goggles, Gloves, Safety Belt, Safety Helmet, Rubber Shoes, etc. shall be provided by the contractor at his own cost to all his manpower at site. BRBNMPL shall have the right to stop any person not wearing such protective gear from working on the site.
 - g) The contractor has to ensure that all equipment tools, brought on to the premises will be in safe conditions have recently been checked and that all personnel using the equipment and tools have been trained in their safe use.
 - h) In case the contractor fails to make arrangements and provide necessary facilities as aforesaid, the BRBNMPL shall be entitled to do so and recover the costs thereof from the contractor. The decision of the BRBNMPL in this regard shall be final and binding on the contractor.
 - i) The contractor shall obtain valid license under the Contract Labour (R & A) Act 1970 and the Contract Labour (Regulation and abolition) Central Rules 1971 and under any other applicable rules before the commencement of the work and continue to have a valid license until the completion of the work.
 - j) Any untoward incident arising out of improper supervision or inadequate safety measures will be the sole responsibility of the contractor. The Contractor shall conform to all the Labour Laws and shall remain solely responsible for the obligation under the relevant statutory provisions.
 - k) BRBNMPL is a security organization and hence the contractor has to abide by the security rules of the Company. The contractor has to ensure the character and antecedent of the persons deployed. The contractor must be in a position to produce such documents whenever he is asked to do so. Details shall be furnished as per format when called for. The contractor has to issue printed photo identity card to its workers duly authenticated by the designated security officer of the Company. The Contractor shall not allow any visitor to the site without the prior written approval of BRBNMPL.
3. The contractor shall make their own arrangement for providing working lunch/dinner to their employees.

4. Short closure of the Work order: Further in the event of any situation arising out of or caused by any act which is beyond the control of BRBNMPL, which results in stoppage of production, or in event of any policy decision made in the interest of the company which may necessitate the short closure of the Work order, the company by giving a notice of reasonable time to supplier, can terminate the Work order without prejudice to the rights of the parties accrued to the date of termination.
5. Penalties: In case the Tenderer fails to execute the work as per the Terms and Conditions and instructions, The Management reserves the rights to impose Liquidated damages as mentioned below:
 - a) In case the Tenderer not carried out the work as per the Terms and Conditions of the work order, not complied with the statutory requirement and its obligations, abandons/discontinue the contract within the validity of the contract period, the BRBNMPL Management reserves the rights to get the remaining work/uncompleted work done through any other agencies and the loss or extra expenditure suffered in such event shall be debited to Tenderers' account in addition to forfeiting the Security Deposit.
 - b) In case of default or breach of Contract Terms & Conditions, the Security Deposit is liable for forfeiture.
 - c) Un-satisfactory performance of the Contract may also lead to black listing of the Tenderer.
6. BRBNMPL's representative reserves the right to execute any delayed services through third parties and deduct from CONTRACTOR the cost of these services together with 10% of this cost for the damages, without any consent of CONTRACTOR, who shall be notified in writing of the measures taken in every case, after giving due notice and Contractor continues to fail to carryout rectifications/execution of services.
7. The Contractor should take utmost care to ensure that no damage to the property of BRBNMPL takes place due to any act of workmen while carrying out the work under the contract.
8. Any damages / breakdowns arising out of negligence, improper handling or improper maintenance will be viewed seriously. In such case the entire expenditure incurred for rectifying or replacing the damaged items will be borne by the contractor. The amount determined by BRBNMPL shall be final and binding. The contractor shall indemnify to this effect. The payment or deduction of such damages shall not relieve CONTRACTOR from his obligations to complete the services or from any of his other obligations and liabilities under this Contract.
9. The period of failure to carry out and all matters of delay, damages, unsatisfactory performance of the services mentioned in several clauses above shall be as determined and judged by the BRBNMPL whose decision shall be final and binding on the CONTRACTOR.
10. All the proposed staff / personnel shall possess high standard of Integrity, have no affiliation with any political parties or trade unions. This has to be followed during the entire contract period.
11. Contractor shall in its dealing with the personnel for the time being employed on or in connection with the Agreement have due regard to all recognized festivals. Contractor shall also observe all relevant local customs and such other conditions and instructions as may be issued to Contractor from time to time by BRBNMPL.
12. Contractor shall at all times take all reasonable precautions to prevent any unlawful, riotous or disorderly conduct by or amongst its employees and for the preservation of peace and protection of persons and property in the neighbourhood of the site against the same.
13. Contractor shall within twenty-four (24) hours of any occurrence of any accident at or about the site or in connection with the execution of the services or any injury, loss or damage to any personnel or to property of Contractor, BRBNMPL or of a third party, report such occurrence to the competent authority whenever such a report is required by law.
14. BRBNMPL will have privity of the contract with the contractor only and will give instructions to the contractor and will have nothing to do or to concern with the conditions of employment of the workers engaged by and/or working for Contractor. However, BRBNMPL shall be at liberty to object to and require Contractor to remove forthwith from the site any person employed by Contractor in or about execution or performance of services who in the opinion of BRBNMPL has committed a misconduct

or whose employment is otherwise considered to be undesirable. Contractor without the written permission of BRBNMPL shall not again employ such person upon services at any circumstances.

15. BRBNMPL will not, in any manner, be responsible for any act, omission or commission of the workers engaged by the contractor and no claim in this respect will be raised against BRBNMPL
16. The contractor shall make their own arrangement for providing working lunch/dinner to their employees.
17. Contractor shall be responsible for the engagement, employment, transport, working and living conditions of personnel and in respect of all matters connected therewith.
18. It shall be sole responsibility of the contractor to ensure safety to all his workers.
19. BRBNMPL will not accept any responsibility for any loss or damage to any property or personal belonging effect to Contractor's employee.
20. The CONTRACTOR shall keep BRBNMPL, its servants or agents indemnified against claims, actions or proceedings brought or instituted against BRBNMPL, its servants or agents by any of his employees or any other third party employed by the Contractor in connection with relating to, or arising out of the performance of the services under the Contract.
21. All compensation or other sums of money payable by the Contractor to the employer under the terms of this contract will be deducted from the earnest Money deposit/Security Deposit or any other process or recovery of such dues.
22. The calculations made by the tenderer should be based upon probable quantities of several items of work, which are furnished for the tenderer's convenience in the schedule of probable quantities, but it must be clearly understood that the contract is not a lump sum contract.
23. Inspection by BRBNMPL – All materials and workmanship shall be subject to inspection, examination, and test by the BRBNMPL at any and all times during the period of contract. It is responsibility of the CONTRACTOR to intimate on regular basis the progress of work / receipt of material and shall furnish promptly without additional charge all reasonable facilities, labour and materials necessary for the safe and convenient inspection and test that may be required by the BRBNMPL.

(To be signed & stamped and submitted along with Techno-commercial Bid Part –I)

भाग / Section III: निविदाकर्ताओं के लिए विशेष अनुदेश / Special Instructions to Tenderers (SIT)

The following Special Instructions to Tenderers will apply for this purchase. These special instructions will modify/ substitute/ supplement the corresponding General Instructions to Tenderers (GIT) incorporated in Section II. The corresponding GIT clause numbers have also been indicated in the text below:

In case of any conflict between the provision in the GIT and that in the SIT, the provision contained in the SIT shall prevail.

(Clauses of GIT listed below include a possibility for variation in their provisions through SIT. There could be other clauses in SIT as deemed fit).

SI. No.	GIT Clause No.	Topic	SIT Provision
1	1, 2, 3, 4, 5, 6, 7	PREAMBLE-Introduction, Language of Tender, Eligible Tenderers, Eligible Goods and Services (Origin of Goods), Tendering Expense, TENDER DOCUMENTS, Amendments to Tender Documents	No Change
2	8	Pre bid Conference	Not Applicable
3	9	Time Limit for receiving request for clarification of Tender Documents	No Change
4	10, 11, 12, 13, 14, 15	Documents Comprising the Tender, Tender Currencies, Tender Prices, Indian Agent, PVC Clause & Formula, Alternative tenders	No Change
5	16, 17	Documents Establishing Tenderer's Eligibility and Qualifications Documents establishing Good's Conformity to Tender document	No Change
6	18	EMD	No EMD
7	19	Tender Validity	120 days from date of opening of tender.
8	20	Number of Copies of Tenders to be submitted	One
9	21, 22 23, 24, 25	Submission of Tenders, Late Tender, Alteration and Withdrawal of Tender, Opening of tenders, Basic Principle	No Change
10	35. 2	Additional Factors for Evaluation of Offers	Supplement with the following: Prospective bidders should meet our tender conditions and items being supplied should be strictly as per given specification without counter conditions. Tender will be finalised on overall L1 basis Tender is non-splitable. Price bid evaluation will be subject to purchase preference as per Government guidelines
11	43	Parallel Contracts	Not Applicable
12	50. 1, 50. 3	Tender For rate Contracts	Not applicable

13	51. 1, 51. 2	PQB Tenders	Not Applicable
14	52. 1, 52. 3, 52. 5	Tenders involving Purchaser's & Pre - Production Samples	Not applicable
15	53. 4, 53. 5, 53. 7	EOI Tenders	Not applicable
16	54. 3. 1, 54. 5. 2	Tenders for Disposal of Scrap	Not applicable
17	55. 2, 55. 3, 55. 7, 55. 8	Development/Indigenization Tenders	Not applicable
18	Clarification of Bidders:	For any clarification bidder may contact this office on any working day during working hours before submission of tender paper. Contractor is advised to visit the site with prior information to understand the actual scope of work and prevailing site conditions. Authorization paper must be displayed for any person visiting on behalf of contractor. Once tender is submitted, it will be implied that the contractor has fully understood the detail specifications, site condition and scopes of work. After quoting ignorance regarding these will not be entertained.	
19	Sub-contract	Sub-contracting in any form before and after placement of the work order will not be allowed. In case the contractor is found engaging sub-contractor, the contract is liable for termination forthwith and forfeit the Security Deposit	
20	Clarification of Bids	During evaluation and comparison of bids, purchaser may, at its discretion ask the bidder for clarification of its bid. The clarification should be received within 7 days from the bidder from the date of receipt of such request. The request for clarification shall be in writing and no change in prices or substance of the bid shall be sought, offered or permitted. No post bid clarification at the initiative of the bidder shall be entertained.	
21	Discrepancy in Prices	a) If in the price structure quoted by a tenderer, there is discrepancy between the unit price and the total price (which is obtained by multiplying the unit price and the quantity), the unit price shall prevail and the total price shall be corrected accordingly, unless client feels that the tenderer has made a mistake in placing the decimal point in the unit price, in which case the total price as quoted shall prevail over the unit price and the unit price shall be corrected accordingly. b) If there is an error in a total price, which has been worked out through addition and/or subtraction of subtotals, the subtotals shall prevail and the total shall be corrected, and c) If, as per the judgment of client, there is any such arithmetical discrepancy in a tender, the same will be suitably conveyed to the tenderer by registered/speed post, if the tenderer does not agree to the observation of the client, the tender is liable for rejection.	

(To be signed & stamped and submitted along with Techno-commercial Bid Part –I)

भाग / Section IV: संविदा की सामान्य शर्तें /
General Conditions of Contract (GCC)
 (For complete details refer our website
www.brbnmpl.co.in under downloads)

Part I: General Conditions of Contract
applicable to all types of Tenders

1. Definitions; Interpretation and Abbreviations: In the contract, unless the context otherwise requires:

1.1 Definitions and Interpretation:

- (i) "Contract" means the letter or memorandum communicating to the Contractor the acceptance of this tender and includes "Intimation of Award" of his tender; "Contract" includes Bid Invitation, Instructions to Tenderers, Tender, Acceptance of Tender, General Conditions of Contract, Schedule of Requirements, particulars and the other conditions specified in the acceptance of tender and includes a repeat order which has been accepted or acted upon by the Contractor and a formal agreement, if executed;
- (ii) "Contractor" or "Supplier" means the individual or the firm supplying the goods and services. The term includes his employees, successors, authorized dealers/representatives, stockists and distributors. Other homologous terms are: Vendor, Firm, Manufacturer, OEM etc.;
- (iii) "Drawing" means the drawing or drawings specified in or annexed to the Specifications;
- (iv) "Government" means the Central Government or a State Government as the case may be;
- (v) The "Inspecting Officer" means the person, or organisation specified in the contract for the purpose of inspection of stores of work under the contract and includes his / their authorised representative;
- (vi) "Purchase Officer" means the officer signing the acceptance of tender and includes any officer who has authority to execute the relevant contract on behalf of the Purchaser;
- (vii) The "Purchaser" means BRBNMPL - the organization purchasing goods and services as incorporated in the documents;
- (viii) "Signed" includes stamped, except in the case of an acceptance of tender or any amendment thereof;
- (ix) "Test" means such test as is prescribed by the particulars or considered necessary by the Inspecting Officer

whether performed or made by the Inspecting Officer or any agency acting under the direction of the Inspecting Officer;

- (x) The delivery of the stores shall be deemed to take place on delivery of the stores in accordance with the terms of the contract, after approval by the Inspecting Officer if so provided in the contract:
 - a. The consignee at his premises; or
 - b. Where so provided, the interim consignee at his premises; or
 - c. A carrier or other person named in the contract for the purpose of transmission to the consignee; or
 - d. The consignee at the destination station in case of contract stipulating for delivery of stores at destination station.
- (xi) "Writing" or "Written" includes matter either in whole or in part, in manuscript, typewritten, lithographed, cyclostyled, photographed or printed under or over signature or seal, as the case may be.
- (xii) Words in the singular include the plural and vice-versa.
- (xiii) Words importing the masculine gender shall be taken to include the feminine gender and words importing persons shall include any company or association or body of individuals, whether incorporated or not.
- (xiv) The heading of these conditions shall not affect the interpretation or construction thereof.
- (xv) Terms and expression not herein defined shall have the meanings assigned to them in the Indian Sale of Goods Act, 1930 (as amended) or the Indian Contract Act, 1872 (as amended) or the General Clauses Act, 1897 (as amended) as the case may be.
- (xvi) PARTIES: The parties to the contract are the "Contractor" and the "Purchaser", as defined above;
- (xvii) "Tender" means quotation / bid received from a firm / supplier.
- (xviii) "Goods" means the articles, material, commodities, livestock, furniture, fixtures, raw material, spares, instruments, machinery, equipment, industrial plant etc. which the supplier is required to supply to BRBNMPL under the contract. Other homologous terms are: Stores, Materials etc.
- (xix) "Services" means services allied and incidental to the supply of goods, such as transportation, installation, commissioning, provision of technical assistance, training, after sales service, maintenance service and other such obligations of the supplier covered under

- the contract.
- (xx) "Earnest Money Deposit" (EMD) means monetary guarantee to be furnished by a Tenderer along with its tender.
- (xxi) "Performance Security" means monetary guarantee to be furnished by the successful Tenderer for due performance of the contract placed on it. Performance Security is also known as Security Deposit or Performance Bank Guarantee.
- (xxii) "Consignee" means the person to whom the goods are required to be delivered as specified in the Contract. If the goods are required to be delivered to a person as an interim consignee for the purpose of dispatch to another person as provided in the Contract then that "another" person is the consignee, also known as ultimate consignee.
- (xxiii) "Specification" or "Technical Specification" means the drawing/document/standard that prescribes the requirement to which product or service has to conform.
- (xxiv) "Inspection" means activities such as measuring, examining, testing, analysing, gauging one or more characteristics of the product or service and comparing the same with the specified requirement to determine conformity.
- (xxv) "Day" means calendar day.

1.2 Abbreviations:

"AAEC"	means "Appreciable Adverse Effect on Competition" as per Competition Act
"BG"	means Bank Guarantee
"BL or B/L"	means Bill of Lading
"CD"	means Custom Duty
"CIF"	means Cost, Insurance and Freight Included
"CMD"	means Chairman and Managing Director
"CPSU"	means Central Public Sector Undertaking
"DDO"	means Direct Demanding Officer in Rate Contracts
"DGS&D"	means Directorate General of Supplies and Disposals
"DP"	means Delivery Period
"ECS"	means Electronic clearing system
"EMD"	means Earnest money deposit
"EOI"	means Expression of Interest (Tendering System)
"ERV"	means Exchange rate variations
"FAS"	means Free alongside shipment

"FOB"	means Freight on Board
"FOR"	means Free on Rail
"GCC"	means General Conditions of Contract
"GIT"	means General Instructions to Tenderers
"GST"	means Goods and Services Tax
"H1, H2 etc."	means First Highest, Second Highest Offers etc. in Disposal Tenders
Incoterms	means International Commercial Terms, 2000 (of ICC)
"L1, L2 etc."	means First or second Lowest Offer etc.
"LC"	means Letter of Credit
"LD or L/D"	means Liquidated Damages
"LSI"	means Large Scale Industry
"NIT"	means Notice Inviting Tenders.
"NSIC"	means National small industries corporation
"PQB"	means Pre-qualification bidding
"PSU"	means Public Sector Undertaking
"PVC"	means Price variation clause
"RC"	means Rate contract
"RR or R/R"	means Railway Receipt
"SBD" or "TD"	means Standard Bid Document / Tender Document
"SCC"	means Special Conditions of Contract
"SIT"	means Special Instructions to Tenderers
"BRBNM PL"	means Bharatiya Reserve Bank Note Mudran Private Limited
"SSI"	means Small Scale Industry

2. Application

2.1 The General Conditions of Contract incorporated in this section shall be applicable for this purchase to the extent the same are not superseded by the Special Conditions of Contract (SCC) prescribed under Section V of this document.

2.2 General Conditions of the contract shall not be changed from one tender to other.

2.3 Other Laws and Conditions that will govern the Contract:

Besides GCC and SCC following conditions and Laws will also be applicable and would be considered as part of the contract:

- Indian Contracts Act, 1872
- Sale of Goods Act, 1930
- Arbitration and Conciliation Act, 1996 read with the Arbitration and

- iv. Conciliation (Amendment) Act, 2015
- v. Competition Act, 2002 as amended by Competition (Amendment Act), 2007
- vi. Contractor's Tender Submissions including Revised Offer during Negotiations if any
- vii. Conditions in other parts of the Tender Documents
- viii. Correspondence including counter-offers if any; between the Contactor and BRBNMPL during the Tender Finalization
- ix. Notification of award and Contract Documents
- ix. Subsequent Amendments to the Contract

3. Use of contract documents and information

3.1 The supplier shall not, without BRBNMPL's prior written consent, disclose the contract or any provision thereof including any specification, drawing, sample or any information furnished by or on behalf of BRBNMPL in connection therewith, to any person other than the person(s) employed by the supplier in the performance of the contract emanating from this tender document. Further, any such disclosure to any such employed person shall be made in confidence and only so far as necessary for the purposes of such performance for this contract.

3.2 During the process of procurement of Security or Sensitive Machinery and Items, Tender Documents and the specifications / drawings of such items would be issued only to Vendors having security clearance within the validity of such clearance and he shall maintain absolute secrecy and strictly control the number of copies and access to the documents and copies thereof, in addition to safeguards mentioned in sub-para above.

3.3 Further, the supplier shall not, without BRBNMPL's prior written consent, make use of any document or information mentioned in GCC sub-clause 3.1 above except for the sole purpose of performing this contract.

3.4 Except the contract issued to the supplier, each and every other document mentioned in GCC sub-clause 3.1 above shall remain the property of BRBNMPL and, if advised by BRBNMPL, all copies of all such documents shall be returned to BRBNMPL on completion of the supplier's performance and obligations under this contract.

4. Patent Rights

4.1 The supplier shall, at all times, indemnify BRBNMPL, free of cost, against all claims

which may arise in respect of goods & services to be provided by the supplier under the contract for infringement of any right protected by patent, registration of designs or trademarks. In the event of any such claim in respect of alleged breach of patent, registered designs, trademarks etc. being made against BRBNMPL, BRBNMPL shall notify the supplier of the same and the supplier shall, at his own expenses take care of the same for settlement without any liability to BRBNMPL.

5. Country of Origin

5.1 All goods and services to be supplied and provided for the contract shall have the origin in India or in the countries with which the Government of India has trade relations.

5.2 The word "origin" incorporated in this clause means the place from where the goods are mined, cultivated, grown, manufactured, produced or processed or from where the services are arranged.

6. Performance Bond / Security

6.1 Within twenty-one days after the issue of notification of award by BRBNMPL, the supplier shall furnish performance security to BRBNMPL for an amount equal to ten per cent of the total value of the contract, valid up to sixty days after the date of completion of all contractual obligations by the supplier, including the warranty obligations.

6.2 The Performance security shall be denominated in Indian Rupees or in the currency of the contract and shall be in one of the following forms:

- a. Account Payee Demand Draft drawn on any scheduled commercial bank in India, in favour of Bharatiya Reserve Bank Note Mudran Private Limited as indicated in the clause 3 of NIT in reference to EMD.
- b. Bank Guarantee issued/confirmed by any scheduled commercial bank in India, in the prescribed form as provided in section XV of this document.

6.3 In the event of any loss due to supplier's failure to fulfil its obligations in terms of the contract, the amount of the performance security shall be payable to BRBNMPL to compensate BRBNMPL for the same.

6.4 In the event of any amendment issued to the contract, the supplier shall, within twenty-one days of issue of the amendment, furnish the corresponding amendment to the Performance Security (as necessary), rendering the same valid in all respects in terms of the contract, as amended.

6.5 Subject to GCC sub-clause 6.3 above, BRBNMPL will release the performance security without any interest to the supplier on completion of the supplier's all contractual obligations including the warranty obligations.

7. Technical Specifications and Standards

7.1 The Goods & Services to be provided by the supplier under this contract shall conform to the technical specifications and quality control parameters mentioned in 'Technical Specification' and 'Quality Control Requirements' under Sections VII and VIII of this document.

8. Packing and Marking

8.1 The packing for the goods to be provided by the supplier should be strong and durable enough to withstand, without limitation, the entire journey during transit including transshipment (if any), rough handling, open storage etc. without any damage, deterioration etc. As and if necessary, the size, weights and volumes of the packing cases shall also take into consideration, the remoteness of the final destination of the goods and availability or otherwise of transport and handling facilities at all points during transit up to final destination as per the contract.

8.2 The quality of packing, the manner of marking within & outside the packages and provision of accompanying documentation shall strictly comply with the requirements as provided in Technical Specifications and Quality Control Requirements under Sections VII and VIII and in SCC under Section V. in case the packing requirements are amended due to issue of any amendment to the contract, the same shall also be taken care of by the supplier accordingly.

8.3 Packing instructions:

Unless otherwise mentioned in the Technical Specification and Quality Control Requirements under Sections VII and VIII and in SCC under Section V, the supplier shall make separate packages for each consignee (in case there is more than one consignee mentioned in the contract) and mark each package on three sides with the following with indelible paint of proper quality:

- a) contract number and date
- b) brief description of goods including quantity
- c) packing list reference number
- d) country of origin of goods
- e) consignee's name and full address and

f) supplier's name and address

9. Inspection and Quality Control

9.1 BRBNMPL and / or its nominated representative(s) will, without any extra cost to BRBNMPL, inspect and/or test the ordered goods and the related services to confirm their conformity to the contract specifications and other quality control details incorporated in the contract. BRBNMPL shall inform the supplier in advance, in writing, BRBNMPL's programme for such inspection and, also the identity of the officials to be deputed for this purpose.

9.2 The Technical Specification and Quality Control Requirements incorporated in the contract shall specify what inspections and tests are to be carried out and, also, where and how they are to be conducted. If such inspections and tests are conducted in the premises of the supplier or its subcontractor(s), all reasonable facilities and assistance, including access to relevant drawings, design details and production data, shall be furnished by the supplier to BRBNMPL's inspector at no charge to BRBNMPL.

9.3 If during such inspections and tests the contracted goods fail to conform to the required specifications and standards, BRBNMPL's inspector may reject them and the supplier shall either replace the rejected goods or make all alterations necessary to meet the specifications and standards, as required, free of cost to BRBNMPL and resubmit the same to BRBNMPL's inspector for conducting the inspections and tests again.

9.4 In case the contract stipulates pre-despatch inspection of the ordered goods at suppliers' premises, the supplier shall put up the goods for such inspection to BRBNMPL's inspector well ahead of the contractual delivery period, so that BRBNMPL's inspector is able to complete the inspection within the contractual delivery period.

9.5 If the supplier tenders the goods to BRBNMPL's inspector for inspection at the last moment without providing reasonable time to the inspector for completing the inspection within the contractual delivery period, the inspector may carry out the inspection and complete the formality beyond the contractual delivery period at the risk and expense of the supplier. The fact that the goods have been inspected after the contractual delivery period will not have the effect of keeping the contract alive

and this will be without any prejudice to the legal rights and remedies available to BRBNMPL under the terms & conditions of the contract.

9.6 BRBNMPL's contractual right to inspect, test and, if necessary, reject the goods after the goods' arrival at the final destination shall have no bearing of the fact that the goods have previously been inspected and cleared by BRBNMPL's inspector during pre-despatch inspection mentioned above.

9.7 Goods accepted by BRBNMPL and/or its inspector at initial inspection and in final inspection in terms of the contract shall in no way dilute BRBNMPL's right to reject the same later, if found deficient in terms of the warranty clause of the contract, as incorporated under GCC Clause.

10. Terms of Delivery

10.1 Goods shall be delivered by the supplier in accordance with the terms of delivery specified in the contract.

11. Transportation of Goods

11.1 The supplier shall not arrange part-shipments and / or transhipments without the express / prior written consent of BRBNMPL.

11.2 Instructions for transportation of domestic goods including goods already imported by the supplier under its own arrangement: In case no instruction is provided in this regard in the SCC, the supplier will arrange transportation of the ordered goods as per its own procedure.

11.3 Shipping Arrangement for Foreign Contracts: In the case of FOB/FAS contracts, shipping arrangements shall be made by the Ministry of Shipping & Transport (Chartering Wing), New Delhi, INDIA, in accordance with details given in SBD Section XVIII. The Contractor shall give adequate, notice to the Forwarding Agents/Nominees about the readiness of the cargo from time to time and at least six weeks' notice in advance of the required position for finalising the shipping arrangements. In the case of CFR contracts, the Contractor shall arrange shipment in accordance with the requirements of the Ministry of Shipping & Transport, New Delhi, INDIA, indicated in the same SBD section (as applicable).

12. Insurance:

12.1 Unless otherwise instructed in the SCC, the supplier shall make arrangements for insuring the goods against loss or damage incidental to manufacture or acquisition, transportation, storage and delivery in the following manner.

12.2 In case of supply of domestic goods on CIF/FOR destination basis, the supplier shall be responsible till the entire stores contracted for arrive in good condition at destination. The transit risk in this respect shall be covered by the Supplier by getting the stores duly insured. The insurance cover shall be obtained by the Supplier in its own name and not in the name of BRBNMPL or its Consignee.

12.3 In the case of FOB and CFR offers for import of Goods, insurance shall be arranged by the Purchaser. However, the supplier must give sufficient notice to the Purchaser prior to the date of shipment, so that the Insurance Cover for the shipment can be activated. The Supplier must co-ordinate so as to ensure that the Shipment sails only with Insurance cover in place.

12.4 In case of Import of Goods, even in case where the insurance is paid by the Purchaser, and loss or damage shall be made good by the Contractor free of cost, without waiting for the settlement of insurance claim. The payment after settlement of insurance claim shall be reimbursed by the Purchaser to the Contractor. It will be entirely the responsibility of the Contractor to make good loss/damage without waiting for settlement of insurance claim so that machine is commissioned within the time specified in the contract.

13. Spare parts

13.1 If specified in the List of Requirements and in the resultant contract, the supplier shall supply / provide any or all of the following materials, information etc. pertaining to spare parts manufactured and / or supplied by the supplier:

- a) The spare parts as selected by BRBNMPL to be purchased from the supplier, subject to the condition that such purchase of the spare parts shall not relieve the supplier of any contractual obligation including warranty obligations; and
- b) In case the production of the spare parts is discontinued:
 - i. sufficient advance notice to BRBNMPL before such discontinuation to provide adequate time to BRBNMPL to purchase the required spare parts etc., and
 - ii. immediately following such discontinuation, providing BRBNMPL, free of cost, the designs, drawings, layouts and specifications of the spare parts, as and if requested by BRBNMPL.

13.2 Supplier shall carry sufficient inventories to assure ex-stock supply of consumable spares for the goods so that the same are supplied to BRBNMPL promptly on receipt of order from BRBNMPL.

14. Incidental services

14.1 Subject to the stipulation, if any, in the SCC (Section V) and the Technical Specification (Section VII), the supplier shall be required to perform any or all of the following services:

- a) Providing required jigs and tools for assembly, start-up and maintenance of the goods
- b) Supplying required number of operation & maintenance manual for the goods
- c) Installation and commissioning of the goods
- d) Training of BRBNMPL's operators for operating and maintaining the goods
- e) Providing after sales service during the tenure of the contract
- f) Providing maintenance service after expiry of the warranty period of the goods if so incorporated in the contract

14.2 Prices to be paid to the supplier by BRBNMPL for any of the required incidental services, if not already included in the contract price during the placement of the contract, shall be settled and decided in advance by BRBNMPL and the supplier. However, such prices shall not exceed the contemporary rates charged by the supplier to other customers for similar services.

15. Distribution of Despatch Documents for Clearance / Receipt of Goods

15.1 The supplier shall send all the relevant despatch documents well in time to BRBNMPL to enable BRBNMPL to clear or receive (as the case may be) the goods in terms of the contract. Unless otherwise specified in the SCC, the usual documents involved and the drill to be followed in general for this purpose are as follows:

15.2 For Domestic Goods, including goods already imported by the supplier under its own arrangement, within 24 hours of despatch, the supplier shall notify BRBNMPL, consignee, and others concerned if mentioned in the contract, the complete details of despatch and also supply the following documents to them by registered post / speed post (or as instructed in the contract):

- (a) Supplier's Invoice indicating, inter alia description and specification of the goods, quantity, unit price, total value;
- (b) Packing list;
- (c) Insurance certificate;

- (d) Railway receipt / Consignment note;
- (e) Manufacturer's guarantee certificate and in-house inspection certificate;
- (f) Inspection certificate issued by BRBNMPL's inspector
- (g) Expected date of arrival of goods at destination and
- (h) Any other document(s), as and if specifically mentioned in the contract.

15.3 For Imported Goods, within 3 days of dispatch, the supplier will Notify BRBNMPL, consignee and other concerned if mentioned in the contract, the complete details of dispatch and also supply the following documents to them by Courier (or as instructed in the Contract), besides advance intimation by Fax / email:

- (a) Clean on Board Airway Bill/Bill of Lading (B/L)
- (b) Original Invoice
- (c) Packing List
- (d) Certificate of Origin from Seller's Chamber of Commerce
- (e) Certificate of Quality and current manufacture from OEM
- (f) Dangerous Cargo Certificate, if any.
- (g) Insurance Policy of 110% if CIP/CIF contract.
- (h) Performance Bond / Warranty Certificate

16. Warranty

16.1 The supplier warrants that the goods supplied under the contract is new, unused and incorporate all recent improvements in design and materials unless prescribed otherwise by BRBNMPL in the contract. The supplier further warrants that the goods supplied under the contract shall have no defect arising from design, materials (except when the design adopted and/ or the material used are as per BRBNMPL's specifications) or workmanship or from any act or omission of the supplier, that may develop under normal use of the supplied goods under the conditions prevailing in India.

16.2 This warranty shall remain valid for twelve months after the goods or any portion thereof as the case may be, have been delivered to the final destination and installed and commissioned at the final destination and accepted by BRBNMPL in terms of the contract or for fifteen months from the date of despatch from the supplier's premises for domestic goods (including goods already imported by the supplier under its own arrangement) or for eighteen months after the date of shipment from the port of loading in the source country for

imported goods offered from abroad, whichever is earlier, unless specified otherwise in the SCC.

16.3 In case of any claim arising out of this warranty, BRBNMPL shall promptly notify the same in writing to the supplier.

16.4 Upon receipt of such notice, the supplier shall, with all reasonable speed (or within the period, if specified in the SCC), repair or replace the defective goods or parts thereof, free of cost, at the ultimate destination. The supplier shall take over the replaced parts / goods after providing their replacements and no claim, whatsoever shall lie on BRBNMPL for such replaced parts/ goods thereafter.

16.5 In the event of any rectification of a defect or replacement of any defective goods during the warranty period, the warranty for the rectified / replaced goods shall be extended to a further period of twelve months from the date such rectified / replaced goods starts functioning to the satisfaction of BRBNMPL.

16.6 If the supplier, having been notified, fails to rectify / replace the defect(s) within a reasonable period (or within the period, if specified in the SCC), BRBNMPL may proceed to take such remedial action(s) as deemed fit by BRBNMPL, at the risk and expense of the supplier and without prejudice to other contractual rights and remedies, which BRBNMPL may have against the supplier.

17. Assignment

17.1 The Supplier shall not assign, either in whole or in part, its contractual duties, responsibilities and obligations to perform the contract, except with BRBNMPL's prior written permission.

18. Sub Contracts

18.1 The Supplier shall notify BRBNMPL in writing of all sub contracts awarded under the contract if not already specified in its tender. Such notification, in its original tender or later, shall not relieve the Supplier from any of its liability or obligation under the terms and conditions of the contract.

18.2 Sub contract shall be only for bought out items and sub-assemblies.

18.3 Sub contracts shall also comply with the provisions of GCC Clause 5 ("Country of Origin").

19. Modification of contract

19.1 Once a contract has been concluded, the terms and conditions thereof will generally not be varied. However, if necessary, BRBNMPL may, by a written order given to the supplier at any time during the currency of the contract,

amend the contract by making alterations and modifications within the general scope of contract in any one or more of the following:

- (a) Specifications, drawings, designs etc. where goods to be supplied under the contract are to be specially manufactured for BRBNMPL,
- (b) mode of packing,
- (c) incidental services to be provided by the supplier
- (d) mode of despatch,
- (e) place of delivery, and
- (f) any other area(s) of the contract, as felt necessary by BRBNMPL depending on the merits of the case.

19.2 In the event of any such modification / alteration causing increase or decrease in the cost of goods and services to be supplied and provided, or in the time required by the supplier to perform any obligation under the contract, an equitable adjustment shall be made in the contract price and/ or contract delivery schedule, as the case may be, and the contract amended accordingly. If the supplier doesn't agree to the adjustment made by BRBNMPL, the supplier shall convey its views to BRBNMPL within twenty one days from the date of the supplier's receipt of BRBNMPL's amendment / modification of the contract.

19.3 Option Clause: By a suitable provision in the SCC, the Purchaser may reserve the right to increase the ordered quantity by 25% at any time, till final delivery date of the contract, by giving reasonable notice even though the quantity ordered initially has been supplied in full before the last date of Delivery Period.

20. Prices

20.1 Prices to be charged by the supplier for supply of goods and provision of services in terms of the contract shall not vary from the corresponding prices quoted by the supplier in its tender or during negotiations, if any, and incorporated in the contract except for any price adjustment authorized in the SCC.

21. Taxes and Duties

21.1 Supplier shall be entirely responsible for all taxes, duties, fees, levies etc. incurred until delivery of the contracted goods to BRBNMPL.

21.2 Further instruction, if any, shall be as provided in the SCC.

22. Terms and Mode of Payment: Unless specified otherwise in SCC, the terms of payments would be as follows:

- 22.1** Unless otherwise specified in SCC, usual payment term is 100% on receipt and acceptance of goods by the consignee (Stores section) and on production of all required documents by the supplier.
- 22.2 For Domestic Goods:** Unless otherwise specified in the SCC, payments to suppliers are usually made by account payee cheque or through ECS only.
- 22.2.1** Where the terms of delivery is FOR dispatching Station, the payment terms, depending on the value and nature of the goods, mode of transportation etc. maybe 60% to 90% (as specified in SIT) on proof of dispatch and other related documents and balance on receipt at site and acceptance by the consignee (Stores section).
- 22.2.2** Where the terms of delivery is delivery at site / FOR destination, usual payment term is 100% on receipt and acceptance of goods by the consignee (Stores section) and on production of all required documents by the supplier.
- 22.2.3** Where goods to be supplied also need installation and commissioning by the supplier, the payment terms are generally as under:
- (a) For a contract with terms of delivery as FOR dispatching station
 - i. 60% on proof of dispatch along with other specified documents
 - ii. 30% on receipt of the goods at site by the consignee (Stores section) and balance
 - iii. 10% on successful installation and commissioning and final acceptance by the consignee (User department)
 - (b) For a contract with terms of delivery as Delivery at site/FOR destination
 - i. 90% on receipt and acceptance of goods by the consignee (Stores section) at destination and on production of all required documents by the supplier
 - ii. 10% on successful installation and commissioning and final acceptance by the consignee (User department)
- 22.3 For Imported Goods:** Unless otherwise specified in SCC, payments are made through an irrevocable Letter of Credit (LC).
- (a) Cases where Installation, Erection and Commissioning (if applicable) **are not the responsibility of the Supplier** - 90% net FOB/FAS/ CFR/CIF/CIP price is to be paid against invoice, shipping documents, inspection certificate (wherever applicable), manufacturers' test certificate, etc. and balance 10% on receipt of goods and after its suitability is ascertained by the consignee (User department).
 - (b) Cases where Installation, Erection and Commissioning are the responsibility of the Supplier - 80% to 90% net FOB/FAS/CFR/CIF/ CIP price (as specified in the SCC) will be paid against invoice, inspection certificate (where applicable), shipping documents etc. and balance within 21-30 days of successful installation and commissioning at the consignee's premises and final acceptance by the consignee (User department).
- 22.4** Unless specified otherwise in the SCC, the following general conditions will apply for payment to the supplier.
- 22.5** The payment shall be made in the currency / currencies authorized in the contract.
- 22.6** The supplier shall send its claim for payment in writing as per Section XIX - "Proforma for Bill for Payments", when contractually due, along with relevant documents etc., duly signed with date, as specified in SCC and in a manner as also specified therein.
- 22.7** While claiming payment, the supplier is also to certify in the bill that the payment being claimed is strictly in terms of the contract and all the obligations on the part of the supplier for claiming that payment has been fulfilled as required under the contract.
- 22.8** The important documents which the supplier is to furnish while claiming payment are:
- a) Original Invoice
 - b) Packing List
 - c) Certificate of country of origin of the goods from seller's Chamber of Commerce.
 - d) Certificate of pre-dispatch inspection by BRBNMPL's representative / nominee
 - e) Manufacturer's test certificate
 - f) Performance / Warrantee Bond
 - g) Certificate of insurance
 - h) Clean on Bill of lading / Airway bill / Rail receipt or any other dispatch document, issued by a government agency (like postal department) or an agency duly authorized by the concerned ministry / department
 - i) Consignee's Certificate confirming receipt and acceptance of goods
 - j) Dangerous Cargo Certificate, if any, in case of imported goods.
 - k) Any other document specified.
- 22.9** While claiming reimbursement of duties, taxes Goods and Services Tax, Customs duty and any other similar duties and taxes from BRBNMPL, as and if permitted under the contract, the supplier shall

also certify that, in case it gets any refund out of such taxes and duties from the concerned authorities at a later date, it (the supplier) shall refund to BRBNMPL. The supplier shall also refund the applicable amount to BRBNMPL immediately on receiving the same from the concerned authorities.

22.10 In case where the supplier is not in a position to submit its bill for the balance payment for want of receipted copies of Inspection Note from the consignee and the consignee has not complained about the non-receipt, shortage, or defects in the supplies made, balance amount will be paid by the paying authority without consignee's receipt certificate after three months from the date of the preceding part payment for the goods in question, subject to the following conditions:

- (a) The supplier will make good any defect or deficiency that the consignee (s) may report within six months from the date of despatch of goods.
- (b) Delay in supplies, if any, has been regularized.
- (c) The contract price where it is subject to variation has been finalized.
- (d) The supplier furnishes the following undertakings:
 "I/We, _____ certify that It We have not received back the Inspection Note duly receipted by the consignee or any communication from BRBNMPL or the consignee about non-receipt, shortage or defects in the goods supplied. I / We agree to make good any defect or deficiency that the consignee may report within three months from the date of receipt of this balance payment or six months from the date of dispatch whichever is later.

23. Delay in the supplier's performance

23.1 The time for and the date specified in the contract or as extended for the delivery of the stores shall be deemed to be the essence of the contract and the supplier shall deliver the goods and perform the services under the contract within the time schedule specified by BRBNMPL in the List of Requirements and as incorporated in the contract.

23.2 Subject to the provision under GCC clause 28, any unexcused delay by the supplier in maintaining its contractual obligations towards delivery of goods and performance of services shall render the supplier liable to any or all of the following sanctions besides any administrative action:

- a) Imposition of liquidated damages,

- b) Forfeiture of its performance security and
- c) Termination of the contract for default.

23.3 If at any time during the currency of the contract, the supplier encounters conditions hindering timely delivery of the goods and performance of services, the supplier shall promptly inform BRBNMPL in writing about the same and its likely duration and make a request to BRBNMPL for extension of the delivery schedule accordingly. On receiving the supplier's communication, BRBNMPL shall examine the situation as soon as possible and, at its discretion, may agree to extend the delivery schedule, with or without liquidated damages for completion of supplier's contractual obligations by issuing an amendment to the contract.

23.4 When the period of delivery is extended due to unexcused delay by the supplier, the amendment letter extending the delivery period shall, inter alia contain the following conditions:

- a) BRBNMPL shall recover from the supplier, under the provisions of the clause 24 of the General Conditions of Contract, liquidated damages on the goods and services, which the Supplier has failed to deliver within the delivery period stipulated in the contract
- b) That no increase in price on account of any ground, whatsoever, including any stipulation in the contract for increase in price on any other ground and, also including statutory increase in or fresh imposition of customs duty, Goods and Services Tax or on account of any other duties and taxes which may be levied in respect of the goods and services specified in the contract, which takes place after the date of delivery stipulated in the contract shall be admissible on such of the said goods and services as are delivered and performed after the date of the delivery stipulated in the contract.
- c) But nevertheless, BRBNMPL shall be entitled to the benefit of any decrease in price on account of reduction in or remission of customs duty, Goods and Services Tax or any other duty or tax or levy or on account of any other grounds, which takes place after the expiry of the date of delivery stipulated in the contract.

23.5 The supplier shall not despatch the goods after expiry of the delivery period. The supplier is required to apply to BRBNMPL for extension of delivery period and obtain the same before despatch. In case the supplier despatches the goods without obtaining an extension, it would

be doing so at its own risk and no claim for payment for such supply and / or any other expense related to such supply shall lie against BRBNMPL.

24. Liquidated damages

24.1 Subject to GCC clause 28, if the supplier fails to deliver any or all of the goods or fails to perform the services within the time frame(s) incorporated in the contract, BRBNMPL shall, without prejudice to other rights and remedies available to BRBNMPL under the contract, deduct from the contract price, as liquidated damages, a sum equivalent to the 0.5% percent (or any other percentage if prescribed in the SCC) of the delivered price of the delayed goods and / or services for each week of delay or part thereof until actual delivery or performance, subject to a maximum deduction of the 10% (or any other percentage if prescribed in the SCC) of the delayed 'goods' or 'services' contract price(s). During the above mentioned delayed period of supply and / or performance, the conditions incorporated under GCC sub-clause 23.4 above shall also apply.

25. Custody and Return of BRBNMPL's Materials / Equipment / Documents loaned to Contractor

25.1 Whenever stores are required to be issued to the firm/contractor for fabrication or prototypes or sub-assemblies are issued for guidance in fabrication, these would be issued against appropriate Bank Guarantee as specified in SCC. In addition to the Bank Guarantee, appropriate insurance may be asked if specified in the SCC.

25.2 All drawings and samples issued to the contractor in connection with the contract must be returned by him. Final payment will be withheld if this is not done, besides any other sanction deemed fit by BRBNMPL.

26. Termination for default

26.1 BRBNMPL, without prejudice to any other contractual rights and remedies available to it (BRBNMPL), may, by written notice of default sent to the supplier, terminate the contract in whole or in part, if the supplier fails to deliver any or all of the goods and/or services or fails to perform any other contractual obligation(s) within the time period specified in the contract, or within any extension thereof granted by BRBNMPL pursuant to GCC sub-clauses 23.3 and 23.4.

26.2 In the event of BRBNMPL terminates the contract in whole or in part, pursuant to

GCC sub-clause 26.1 above, BRBNMPL may procure goods and / or services similar to those cancelled, with such terms and conditions and in such manner as it deems fit at the "Risk and Cost" of the supplier and the supplier shall be liable to BRBNMPL for the extra expenditure, if any, incurred by BRBNMPL for arranging such procurement.

26.3 Unless otherwise instructed by BRBNMPL, the supplier shall continue to perform the contract to the extent not terminated.

27. Termination for insolvency

27.1 In the event the supplier becomes bankrupt or otherwise insolvent or loses substantially the technical or financial capability (based on which he was selected for award of contract) or liquidation proceedings are commenced against it by a third party or by own volition, BRBNMPL reserves the right to terminate the contract, at any time, by serving written notice to the supplier, without any adverse consequence to BRBNMPL and without being liable to pay any compensation, whatsoever, to the supplier, subject to further condition that such termination will not prejudice or affect any rights of action or remedies which have accrued or will accrue prior to termination or thereafter to BRBNMPL.

27.2 Upon such termination, BRBNMPL shall be deemed to be the owner of the stores/materials manufactured by the supplier and retain first right and lien over the stores/materials including the raw material purchased by the supplier for performance of the contract and require the stores/materials to be delivered under the contract, which is terminated on account of bankruptcy or insolvency or likely bankruptcy or insolvency of the supplier and such stores in possession of the supplier shall be earmarked and be delivered to BRBNMPL before the start of the bankruptcy or insolvency process.

27.3 In the event the supplier is aware or apprehends that it is likely to go into liquidation whether on account of liquidation proceedings commenced by a third party or by way of voluntary liquidation, then the supplier shall forthwith inform BRBNMPL as soon as it is aware that a third party has issued notice that it intends to commence liquidation proceedings or well before it files for liquidation.

27.4 Escrow Arrangement

The Supplier shall deposit with a third party escrow agent mutually agreed to by the parties, a copy of Software and its source code and object code for safe keeping with instructions for it to be released forthwith to BRBNMPL, in the event the Supplier fails to make the source code/object code accessible to BRBNMPL whenever required and/or in the event the Supplier is likely to go into liquidation or goes into liquidation.

In the event, the Supplier apprehends that it is likely to go into liquidation whether on account of liquidation proceedings commenced by a third party or in the event it anticipates filing for bankruptcy, then the Supplier shall inform BRBNMPL in advance and engage with it to determine the sale and possession of BRBNMPL's software and its source code. In the event Supplier fails to do so, the third party escrow agent shall be instructed under the Escrow Agreement to release the Software and its source code to BRBNMPL as noted above.

For the purpose of this Clause, the term 'Software' shall collectively mean, the full and final version of the Software to be delivered to BRBNMPL in source code and object code forms, together with any and all improvements, corrections, modifications, updates, enhancements or other changes, whether or not included in the full and final version including all System Documentation and User Documentation.

The term 'System Documentation' shall mean any and all documentation used in the development and updating of the Software, including but not limited to, customer requirements and specifications design or development specifications, test and error reports, and related correspondence and memoranda. And the term 'User Documentation' shall mean the end-user instruction manual that usually accompanies the Software instructing end users in the use of the Software in both printed and electronic form.

28. Force Majeure

28.1 In the event of any unforeseen event directly interfering with the supply of stores arising during the currency of the contract, such as war, hostilities, acts of the public enemy, civil commotion, sabotage, fires, floods, explosions, epidemics, quarantine restrictions, strikes, lockouts, or acts of God, the Contractor shall, within a week from the commencement thereof, notify the same in writing to the Purchaser with reasonable evidence thereof. Unless otherwise directed by BRBNMPL in writing, the supplier shall continue to perform its obligations under the contract

as far as reasonably practical, and shall seek all reasonable alternative means for performance not prevented by the Force Majeure event. If the force majeure condition(s) mentioned above be in force for a period of 90 days or more at any time, either party shall have the option to terminate the contract on expiry of 90 days of commencement of such force majeure by giving 14 days' notice to the other party in writing. In case of such termination, no damages shall be claimed by either party against the other, save and except those which had occurred under any other clause of this contract prior to such termination.

28.2 Notwithstanding the provisions contained in GCC clauses 23, 24 and 26, the supplier shall not be liable for imposition of any such sanction so long the delay and / or failure of the supplier in fulfilling its obligations under the contract is the result of an event of Force Majeure.

28.3 In case due to a Force Majeure event BRBNMPL is unable to fulfil its contractual commitment and responsibility, BRBNMPL will notify the supplier accordingly and subsequent actions taken on similar lines described in above sub-paragraphs.

29. Termination for convenience

29.1 BRBNMPL reserves the right to terminate the contract, in whole or in part for its (BRBNMPL's) convenience, by serving written notice on the supplier at any time during the currency of the contract. The notice shall specify that the termination is for the convenience of BRBNMPL. The notice shall also indicate inter-alia, the extent to which the supplier's performance under the contract is terminated, and the date with effect from which such termination will become effective.

29.2 The goods and services which are complete and ready in terms of the contract for delivery and performance within thirty days after the supplier's receipt of the notice of termination shall be accepted by BRBNMPL following the contract terms, conditions and prices. For the remaining goods and services, BRBNMPL may decide:

- a. to get any portion of the balance completed and delivered at the contract terms, conditions and prices; and / or
- b. to cancel the remaining portion of the goods and services and compensate the supplier by paying an agreed amount for the cost incurred by the supplier towards

the remaining portion of the goods and services.

30. Governing language

30.1 The contract shall be written in Hindi or English language following the provision as contained in GIT clause 2. All correspondence and other documents pertaining to the contract, which the parties exchange, shall also be written accordingly in that language.

31. Notices

31.1 Notice, if any, relating to the contract given by one party to the other, shall be sent in writing or by cable or telex or facsimile and confirmed in writing, the procedure will also provide the sender of the notice, the proof of receipt of the notice by the receiver. The addresses of the parties for exchanging such notices will be the addresses as incorporated in the contract.

31.2 The effective date of a notice shall be either the date when delivered to the recipient or the effective date specifically mentioned in the notice, whichever is later.

32. Code of Ethics

BRBNMPL as well as Bidders, Suppliers, Contractors, and Consultants under BRBNMPL contracts shall observe the highest standard of ethics during the procurement or execution of such contracts. In pursuit of this policy, for the purposes of this provision, the terms set forth below are defined as follows:

- (a) "Corrupt practice" means the offering, giving, receiving, or soliciting, directly or indirectly, of anything of value to influence the action of a public official in the procurement process or in contract execution;
- (b) "Fraudulent practice" means a misrepresentation or omission of facts in order to influence a procurement process or the execution of a contract;
- (c) "Collusive practice" means a scheme or arrangement between two or more Bidders, with or without the knowledge of the Purchaser, designed to establish bid prices at artificial, non-competitive levels; and
- (d) "Coercive practice" means harming or threatening to harm, directly or indirectly, persons or their property to influence their participation in the procurement process or affect the execution of a contract.
- (e) A particular violation of ethics may span more than one of above mentioned unethical practices.

32.1 The following policies will be adopted in order to maintain the standards of ethics during procurement:

- (a) A proposal for award will be rejected if it is determined that the Bidder recommended for award has, directly or through an agent, engaged in corrupt, fraudulent, collusive or coercive practices in competing for the Contract in question.
- (b) A contract will be cancelled if it is determined at any time that BRBNMPL representatives / officials have directly or indirectly, engaged in corrupt, fraudulent, collusive or coercive practices during the procurement or the execution of that contract
- (c) In case any individual staff is found responsible, suitable disciplinary proceedings should be initiated against such staff under the applicable government conduct rules. The existing provisions under the Indian law including the instructions of Central Vigilance Commission should be followed in this regard.
- (d) Firms or individuals shall be banned / blacklisted after following due process, including declaring them ineligible, either indefinitely or for a stated period of time, to be awarded a BRBNMPL contract, if it at any time determines that they have, directly or through an agent, engaged in corrupt, fraudulent, collusive or coercive practices in competing for, or in executing, a BRBNMPL contract.
- (e) Bidders have to sign an Integrity Pact in tenders meeting the criteria of threshold value / nature of procurement. Integrity Pact format shall be included in the Bid Document as Section XX. Each page of such Integrity pact proforma would be duly signed by Purchaser's competent signatory. All pages of the Integrity Pact will have to be duly signed by the same signatory who is duly authorized to sign the bid and to make binding commitments on behalf of his company and to be submitted along with the technical bid. Any bid not accompanied by Integrity Pact duly signed by the bidder shall be considered to be a non-responsive bid and shall be rejected straightway.

33. Resolution of disputes

33.1 If dispute or difference of any kind shall arise between BRBNMPL and the supplier in connection with or relating to the contract, the parties shall make every effort to resolve the same amicably by mutual consultations. If the parties fail to resolve their dispute or difference by such

mutual consultation within twenty one days of its occurrence, then, unless otherwise provided in the SCC, either BRBNMPL or the supplier may seek recourse to settlement of disputes through arbitration as per The Arbitration and conciliation Act 1996 as per following clause.

33.2 Arbitration Clause: If both parties fail to reach such amicable settlement, then either party (the Purchaser or Seller) may within 21 days of such failure give a written notice to the other party requiring that all matters in dispute or difference be arbitrated upon. Such written notice shall specify the matters which are in difference or of difference of which such written notice has been given and no other matter shall be referred to the arbitration in accordance with the conciliation and arbitration rules of International Chamber of Commerce {ICC}/United National Commission on International Trade Law (UNCITRL) by three arbitrators appointed in accordance with the procedure set out in clause below. The arbitration proceeding shall be held in Bangalore/Mysore/Kolkata and shall be conducted in English language. All documentation to be reviewed by the arbitrators and / or submitted by the parties shall be written or translated into English. Venue of arbitration shall be Bangalore/Mysore/Kolkata. The arbitrator or arbitrators appointed under this article shall have the power to extend time to make the award with the consent of the parties. Pending reference to arbitration the parties shall make all endeavours to complete the contract/work in all respects and all disputes, if any, will finally be settled in the arbitration.

34. Applicable Law

34.1 The contract shall be interpreted in accordance with the laws of India.

34.2 Irrespective of the place of delivery, or the place of performance or the place of Payments under the contract, the contract shall be deemed to have been made at the place from which the notification of acceptance of the tender has been issued.

35. Secrecy

35.1 The Contractor shall take all reasonable steps necessary to ensure that all persons employed in any work in connection with the contract, have full knowledge of the Official Secrets Act and any regulations framed thereunder.

35.2. Any information obtained in the course of the execution of the contract by the Contractor, his servants or agents or any person so employed, as to any matter whatsoever, which would or might be directly or indirectly, of use to any enemy of India, must be treated secret and shall not at any time be communicated to any person.

35.3. Any breach of the aforesaid conditions shall entitle the Purchaser to cancel the contract and to purchase or authorise the purchase of the stores at the risk and cost of the Contractor, In the event of such cancellation, the stores or parts manufactured in the execution of the contract shall be taken by the Purchaser at such price as he considers fair and reasonable and the decision of the Purchaser as to such price shall be final and binding on the Contractor.

Part II: Additional General Conditions of Contract for specific Types of Tenders in addition / modification to clauses mentioned above:

36. Disposal / Sale of Scrap by Tender

36.1 During the currency of contract, no variation in price or rate shall be admissible.

36.2 Payment and Default

36.2.1 Payment may be made in the form of cash or Account Payee Demand Draft drawn on any scheduled commercial bank in India in favour of Bharatiya Reserve Bank Note Mudran Private Limited or through Online Transfer or through other Electronic Mode of Payment as mentioned in the NIT.

36.2.2 No interest will be paid to the purchaser for the amounts paid or deposited with the BRBNMPL and subsequently found refundable to the purchaser under any of the conditions of the contract.

36.2.3 If the purchaser fails to deposit sale value for a sold lot within the allowed period as per relevant clause BRBNMPL may forfeit the security deposit. Requests for an extension of this period, made by the purchaser may be considered by the BRBNMPL and may at its discretion, on the merits of the case, allow further time not excluding 50 days from the date of the contract. Interest shall be leviable on such amount at a rate 2% per annum higher than the PLR of State Bank of India, from the date of expiry of the payment date to actual date of payment (actual date of payment inclusive).

- 36.2.4** The lot or lots in respect of which forfeiture has been made, shall be deemed to have been abandoned by the purchaser to all intents and purposes and may be re-sold or otherwise disposed of at the discretion of the BRBNMPL without reference to the purchaser concerned and without incurring any liability on part of BRBNMPL whatsoever in respect there under.
- 36.2.5** In case extension is granted by BRBNMPL and due to late payment of sale amount the delivery cannot be completed by the purchaser, in accordance with the relevant clause of Special Conditions of Tender sale, then ground rent shall also be leviable as per relevant clause of Special Conditions of Tender sale.
- 36.2.6** On production of proof of having made payment, nominated authority shall issue a delivery order authorizing the purchaser to take delivery of the Scrap Materials.
- 36.3 Deliveries, Delays and Breach of Contact**
- 36.3.1** The Title of goods or material sold shall not be deemed to have been passed to the Purchaser / Bidder until and unless the full and final payment has been made by the purchaser, in accordance with the contract to the BRBNMPL and the authorized Officer has issued the Delivery Order in favour of the purchaser. The materials sold may be removed from the premises only on production of the cash receipt for the payment and a delivery order from the Officer authorized by the BRBNMPL.
- 36.3.2** Unless specified otherwise in SIT, delivery period for lifting of material shall be within 60 days from the date of finalization of contract agreement.
- 36.3.3** The work of delivery will be supervised by Stock Holder or his authorized representative, representative of accounts Department and Security Staff duly authorized by BRBNMPL for the propose of delivery. Delivery will be allowed during working hours.
- 36.3.4** No delivery of or materials sold shall be given on Sundays, Gazetted holidays and other shall holidays observed by BRBNMPL. The delivery of the goods or material shall be effected from the premises concerned only during its normal working hours. In order to complete the delivery within the working hours all loading must cease half an hour before the normal closing time of the concerned premises. The decision of the BRBNMPL with regard to the working hour shall be final and binding on the purchaser. Purchaser will not be allowed to lift the Scrap Material from more than one location at a time.
- 36.3.5** The purchased stores will be carried away by the purchaser at his risk and no claims against the BRBNMPL will be entertained for shortage in weight which may be discovered after the materials have left the premises wherefrom delivery is taken. If required the purchaser shall provide his own bags, cases or other receptacles for the removal of the scrap.
- 36.3.6** The BRBNMPL shall not be responsible for any accident that may occur to purchaser's labours/servants for any reasons whatsoever. The purchaser will himself have to ensure the safety of his workers and shall be liable to pay claims, whatsoever if any. BRBNMPL will not carry any responsibility of such payments. The purchaser will be responsible to supply personal protection equipment to his labour/servant and staff and no additional charges are admissible for the same.
- 36.3.7** The materials sold, shall be removed by the purchaser within the period specified in relevant clause of Special Condition of Sale.
- 36.3.8** If due to any default on the part of the BRBNMPL, the purchaser is unable to remove the materials sold within the specified period, the BRBNMPL may extend the period therefore and in such an event purchaser will be entitled to take delivery of the goods or the materials sold within such extended Delivery period.
- 36.3.9** If contractor fails to lift sold scrap within the specified period, penalty shall be levied at the rate of 0.5% per day of the value of un-removed Scrap. Moreover the material shall remain at the purchaser's risk until removal thereof. Further BRBNMPL will be entitled to charge the ground rent as stated in relevant Para of SCC, for the area in which the materials sold are kept or stored - which would be recovered by the BRBNMPL from the Purchaser before removal of the material and in the event of default in payment thereof, the BRBNMPL at may its discretion shall be entitled to order the re-sale of such materials and forfeit the Security deposit or sale amount or both, paid by the purchaser.
- 36.3.10** If the purchaser makes slow progress with his contract and the BRBNMPL is of opinion that he may fail to fulfil the contract within the time specified in the conditions of sale, it will be lawful for the

BRBNMPL to cancel the whole contract or such portion thereof as may not have been completed and the BRBNMPL shall be at liberty to dispose of the goods in any manner at the risk and expense of the purchaser.

36.3.11 The purchaser will have to comply with the provisions of the Contract Labour (Regulations and Abolition Act 1970 and Central Rules 1971 and obtain license from the Assistant Labour Commissioner or the competent authorities empowered to issue such license. Any failure on the part of the purchaser in this regard will be at his risk and consequences. He shall comply with Workman's Compensation Act 1923, Payment of Wages Act 1936, and Minimum Wages Act 1948 and all the other related statutory and legal provisions and obligations, the purchaser

shall also indemnify the BRBNMPL against any claim / liabilities that may occur to the contractor's labours and servants due to any reasons whatsoever.

36.3.12 If the purchaser makes default in complying with any of the condition of the contract, the sale of lot or lots in respect of which such default is made may be cancelled and such lot or lots may be put up again for sale and in such an event if a lower price is offered and accepted for such lot or lots then the purchaser shall be liable to pay the difference in price thereof together with all expenses occasioned by such resale in default to the BRBNMPL provided further that the purchaser in default shall not be entitled to claim any profit which may arise from such resale.

भाग /Section V: संविदा की विशेष शर्तें / Special Conditions of Contract (SCC)

The following Special Conditions of Contract (SCC) will apply for this purchase. The corresponding clauses of General Conditions of Contract (GCC) relating to the SCC stipulations have also been incorporated below. These Special Conditions will modify / substitute / supplement the corresponding (GCC) clauses.

Whenever there is any conflict between the provision in the GGC and that in the SCC, the provision contained in the SCC shall prevail.

(Clauses of GCC listed below include a possibility for variation in their provisions through SCC. There could be other clauses in SCC as deemed fit).

Sl. No	GCC Clause No.	Topic	SCC Provision
1.	6	Performance Bond / Security Deposit	Performance Bond/ Security shall be 3% on the contract value.
2.	8.2	Packing and Marking	No change
3.	11.2	Transportation of Domestic Goods	No change
4	12.2	Insurance	No change
5	14.1	Incidental Services	No change
6	15	Distribution of Dispatch Documents for clearance / Receipt of Goods	No change
7	16.2, 16.4	Warrantee Clause	Applicable
8	19, 19.3	Option Clause	No change
9	20.1	Price Adjustment Clause	No Change
10	21.2	Taxes and Duties	No Change
11	22, 22.1, 22.2, 22.3, 22.4, 22.6,	Terms and Mode of Payments	The minimum value of interim bill / progressive running account (R/A) bill shall not be less than ₹ 15 lakhs (Rupees Fifteen Lakhs)
12	24.1	Quantum of LD	No Change
13	25.1	Bank Guarantee and Insurance for Material loaned to Contractor	No change
14	33.1	Resolution of Disputes	No change
15	36, 36.3.2, 36.3.9	Disposal / Sale of Scrap by Tender	Not applicable

Note: Please read the GCC carefully before submitting the offer.

1. Statutory requirements: The Contractor should comply with all statutory provisions as applicable such as but not limited to:
 - a. The contractor shall have to observe/ fulfil and comply with all the statutory requirements and obligation as per the provisions of law/Rules i.e. the Factories Act 1948, Karnataka Factories Rule 1969, Employee's Compensation Act 1923, Employers Liability Act 1938, Contract Labour R & A Act 1970 and Central Rules 1971, Industrial Dispute Act 1947, Maternity Benefit Act 1961, Minimum Wages Act 1948, Payment of Wages Act 1936, Employee's Provident Funds & Misc. Provisions and Schemes 1952, and Employee's State Insurance Act 1948, Payment of Bonus Act 1965, Payment of Gratuity Act 1972, Karnataka Industrial (National and Festival) Act 1963, etc., including any enactment made by the Governments or modification thereof or any other law/s relating thereto and rules framed there under from time to time.
 - b. Provisions of the Factories Act, Workman Compensation Act, Employers Liability Act, Contract Labour Act, Industrial Dispute Act, Minimum Wages Act, Payment of Wages Act, EPF and ESI Act including any modification thereof or any other law relating thereto and rules framed there under from time to time.

- c. The contractor has to obtain insurance coverage to all his employees under 'Workmen Compensation Policy' if the labourer out of ESIC coverage during the full tenure of the contract to address the liability under Workmen's Compensation Act 1923. The same has to be submitted before commencement of work. The sum insured per labour is to be calculated as per extant rule in this regard. The BRBNMPL, as a principal employer, shall enforce the provisions of these Acts.

Contractor shall at all times during the continuance of this Agreement conform in all respects to and carry out all obligations imposed on it by the provisions and requirements of the Employees Provident Fund (Miscellaneous Provision) Act, 1952, Payment of Gratuity Act, 1972, Employment State Insurance Act, 1948, Maternity Benefit Act, 1961, Minimum Wages Act 1948, prescribed by Ministry of labour & employment, office of the Chief labour Commissioner. Equal Remuneration Act, 1976, Payment of Wages Act, 1936, Payment of Bonus Act, 1965, Contract Labour (Regulation and Abolition) Act, 1971 and any applicable law in the country where any of the services are performed or regulations issued including without limitation all laws, regulations and requirements of Government of India.

The Contractor must have a valid Provident Fund code & ESI code and the same shall be intimated along with the tender. Copy of Registration Certificates issued under EPF and MP Act, 1952, Karnataka Shops and Establishments Act and ESI Act, 1948 along with originals for verification.

- d. The Labourers to be engaged/ deployed should not be below 18 years of age. They should be in sound health and free from any contagious diseases.
- e. It shall be the sole responsibility of the contractor to ensure safety to all his workers.
- f. Any untoward incident arising out of improper supervision or inadequate safety measures will be the sole responsibility of the contractor. The Contractor shall conform to all the Labour Laws and shall remain solely responsible for the obligation under the relevant statutory provisions.
- g. BRBNMPL will not accept any responsibility for any loss or damage to any property or personal belonging effect to Contractor's employee.
- h. The Contractor shall keep BRBNMPL, its servants or agents indemnified against claims, actions or proceedings brought or instituted against BRBNMPL, its servants or agents by any of his employees or any other third party employed by the Contractor in connection with relating to, or arising out of the performance of the services under the Contract
- i. Contractor shall indemnify BRBNMPL against any liability for any accident, death or injury to BRBNMPL's servants or agents or against any loss of or damage to any property belonging to BRBNMPL, its servants or agents which shall arise out of the performance of the services under this Agreement and against all costs, claims, demands and damages involved therewith.
- j. Statutory Deductions: Statutory deductions shall be made at source as per rule

2. Tender Evaluation:

- i) **The evaluation shall be based on overall L1 basis considering the Total Cost including GST.** However, BRBNMPL does not pledge itself to accept the lowest or any tender and reserves to itself the right of accepting the whole or any part of the tender or portion of the quantity tender or cancel the tender without assigning any reason what so ever.
- ii) BRBNMPL shall evaluate the bids to determine whether they are complete, whether any computational errors have been made, whether required sureties have been furnished, whether the documents have been properly signed and whether the bids are generally in order.
- iii) Quoted price should be in words and figures. Any discrepancy between words and figures, the price in words shall prevail. Insertions, postscripts, additions and alterations shall not be recognized, unless authenticated by the tenderer's signature. In case of discrepancy between unit price and total price/cost, the unit rate will be considered for evaluation.
- iv) All decisions by BRBNMPL on the evaluation of bids will be final and binding on the Bidders and is not subject to any scrutiny
- v) Any effort by a bidder to influence BRBNMPL personnel or representatives on matters relative to the bid under study in the process of examination, clarification, evaluation

and comparison of bids, and in decisions concerning award of contract may result in rejection of his bid

3. The successful tenderer must note that all performance of the job shall be strictly in accordance with the requirements and fulfilments of the local/public authorities, statutory approvals and to the requirements of BRBNMPL and no deviation on any account will be permitted.

BRBNMPL's representative reserves the right to execute any delayed services through third parties and deduct from contractor the cost of these services together with 10% of this cost for the damages, without any consent of contractor, who shall be notified in writing of the measures taken in every case, after giving due notice and Contractor continues to fail to carryout rectifications/execution of services.

Any damages / breakdowns arising out of negligence, improper handling or improper maintenance will be viewed seriously. In such case the entire expenditure incurred for rectifying or replacing the damaged items will be borne by the contractor. The amount determined by BRBNMPL shall be final and binding. The contractor shall indemnify to this effect.

The payment or deduction of such damages shall not relieve contractor from his obligations to complete the services or from any of his other obligations and liabilities under this Contract.

The period of failure to carry out and all matters of delay, damages, unsatisfactory performance of the services mentioned in several clauses above shall be as determined and judged by the BRBNMPL whose decision shall be final and binding on the Contractor.

4. Superintendence – Contractor shall provide all necessary superintendence as necessary for the proper fulfilling of Contractor's obligations under this Contract.
5. BRBNMPL shall have the right to check and make remarks on any or all procedures proposed to be adopted by Contractor for the performance of services. Contractor shall submit such work procedure for BRBNMPL's review and approval.
6. Responsibility of the contractor
 - a. The contractor should comply with all security procedures adopted by us and they should furnish the list of people deployed for this contract for verification to our Security Manager. Gate passes will be issued to the personnel deployed & it should be renewed periodically.
 - b. Supervision: The Contractor or his supervisor should be present at the work spot and supervise during shifts in all working days. The Contractor should take and observe all the required formalities like deployment of his labourers, maintaining of attendance as directed by the Authorised persons of BRBNMPL. Any untoward incident arising out of improper supervision or inadequate safety measures will be the sole responsibility of the Contractor and shall confirm to all the labour Laws and shall remain solely responsible for the obligation under the relevant statutory provisions.
 - c. The Contractor/Agency shall indemnify the Company from any claims/liability due to any breach of the statutory requirements from him/them. The Company as a principle Employer shall enforce the provisions of the Acts.
 - d. Adequacy of Contractor's Staff: It is essential that the service activities are to be performed with utmost diligence and expediency so as to maintain the highest standards of Maintenance. To achieve this, Contractor shall maintain adequate level of staff of good technical competence at site at all times.
 - e. Failure of Contractor to comply with the instructions of BRBNMPL may be grounds for determination by BRBNMPL that Contractor is not proceeding with the performance of services with due diligence to ensure fulfilment of contractual requirements.
7. Conditions of Performance: the contractor should confirm and assure that:
 - a. Contractor has the requisite skilled and qualified personnel to perform the services.
 - b. Contractor has inspected the premises and is familiar with the conditions related to performance of the services.
 - c. Contractor shall at all times ensure that the supply of know-how, Manpower, Materials, Equipment, Tools and Tackles shall be adequate to satisfactorily undertake the scope of services without delay.
 - d. Contractor shall at all times ensure that the services are being carried out in the most expeditious efficient manner consistent with the best interests of BRBNMPL,

and in good and professional manner and in accordance with sound industry practice.

- e. Contractor shall perform and provide the services in accordance with provisions of this Contract and shall exercise all reasonable skill, care diligence and judgment in performance of the services.

Contractor shall discuss as per the Contract, the general basis for execution of services, Contractor shall provide procedures for BRBNMPL approval which shall be based upon good engineering practice in order to maintain the services/equipment at a high level of efficiency and to provide safe working conditions. If any question arises between Contractor and BRBNMPL regarding particular work procedure followed or proposed to be followed by Contractor, Contractor must justify to BRBNMPL the soundness of such procedure and shall obtain BRBNMPL's written approval before the same may be affected. Provision or otherwise of such approval shall not relieve Contractor of any of its obligations under this Contract.

BRBNMPL shall have the right to check and make remarks on any or all procedures proposed to be adopted by Contractor for the performance of services. Contractor shall submit such work procedure for BRBNMPL's review and approval.

8. Force Majeure Clause:

BRBNMPL shall in addition to its power under other clauses to determine Purchase orders have power to terminate its liability there under at any time by giving a notice of reasonable time in writing to the supplier of the company's desire to do so and upon the expiration of the notice the P.O /W.O shall be determined without prejudice to the rights of the parties accrued to the date of determination.

Further in the event of any situation arising out of or caused by any act which is beyond the control of BRBNMPL, which results in stoppage of production, or in event of any policy decision made in the interest of the company which may necessitate the short closure of the Purchase order, the company by giving a notice of reasonable time to supplier, can terminate the purchase order without prejudice to the rights of the parties accrued to the date of termination

9. Conflict of Interest:

- a. Contractor shall conduct its operations in a lawful manner consistent with good international practices and standards for such type of services.
- b. Neither Contractor nor any of its subsidiaries or affiliates shall in connection with the services enter into a contract, give an undertaking, bid, enter into a Joint Venture Partnership, have any relations with a Third Party or any other arrangement to perform any services, to supply goods or equipment which may be to BRBNMPL's detriment.
- c. Any treasures, antiques, valuable etc. found during excavation belong to the BRBNMPL & same shall be handed over without causing any damage to them.
- d. The Contractor must ensure that at no point of time should any system be rendered non-functional.
- e. Communication and Document distribution pertain to respective specialized works shall be made during execution of work to meet the requirement of the BRBNMPL.
- f. Details of the service infrastructure in terms of the service staff strength and their qualifications, details of warehousing facilities for spares and the value of spares stocked shall be submitted.

भाग / Section VI – आवश्यकताओं की सूची / List of Requirements

Tender Document for Construction of Compound Wall, Pathway and Security Building & Refurbishment of Existing Signage Tower at BRBNMPL, Bengaluru

निविदा सं. 008/CO/OT/2021-22 दिनांक December 31, 2021

Tender No: 008/CO/OT/2021-22 dated December 31, 2021

Sl. No.	Brief Description of Goods / Services	Unit	Quantity	Amount of Earnest Money
01	Construction of Compound Wall, Pathway and Security Building & Refurbishment of Existing Signage Tower at BRBNMPL, Bengaluru <u>(NON-SPLITABLE)</u> As per Scope of work mentioned at List of Requirement – Section-VI	As per BOQ	As per BOQ	Nil Note: bidder is required to submit declaration for bid security as per proforma at Annexure-J

- The work shall be carried out the following address:
Bharatiya Reserve Bank Note Mudran (P) Limited,
Corporate Office
No. 3 & 4, 1st Stage, 1st Phase,
BTM Layout, Bannerghatta Road,
Bengaluru – 560029
GSTN No. : 229AAACB8111E1Z1
- Pre-Bid Visit: The BIDDER must obtain for himself on his own responsibility and at his own expenses, all the information which may be necessary for the purpose of making a tender and for entering into a contract and must examine the drawings and must inspect the site of the work and acquaint himself with all scope of work, volume of work, local conditions, means of access to the work, nature of the work and all matters appertaining thereof.
- Each of the tender documents should be signed by the person or persons submitting the tender in token of his/their acquainted himself/themselves with the General Conditions of Contract, Specifications, Special Conditions, etc. as laid down. Any tender with any of the documents not signed may be rejected.
- The tender submitted on behalf of a firm shall be signed by all the partners of the firm or by a partner who has the necessary authority on behalf of the firm to enter into the proposed contract. Otherwise the tender may be rejected.
- Contractor's Responsibility: The contractor shall provide everything necessary for the proper execution of the works according to the intent and meaning of the schedule of quantities and specifications taken together whether the same may or may not be particularly shown or described therein provided that the same can reasonably be inferred there from. If that contractor finds any discrepancy in the schedule of quantities and specifications, he shall immediately and in writing refer the same to BRBNMPL who shall decide which is to be followed.
- Co – ordinations with Other Agencies: BRBNMPL reserves the right to use premises and any portions of the site for the execution of any work not included in this contract which it may desire to have carried out by other persons, and the contractor shall allow all reasonable facilities for the execution of such work but shall not be required to provide any plant or material for the execution of such work except by special arrangement with BRBNMPL.
- Non – Compliance Of Site Instruction: If the contractor after receipt of written notice from BRBNMPL requiring compliance within 7 days fails to comply with such instructions, BRBNMPL may employ and pay other contractor to execute any such work whatever that may be necessary to give effect thereto, and all cost incurred in connection therewith shall be recoverable from the contractor by BRBNMPL as a debt or may be deducted from any payment due to the contractor.

9. Co – ordinations with Other Agencies: BRBNMPL reserves the right to use premises and any portions of the site for the execution of any work not included in this contract which it may desire to have carried out by other persons, and the contractor shall allow all reasonable facilities for the execution of such work but shall not be required to provide any plant or material for the execution of such work except by special arrangement with BRBNMPL.
10. Alteration in quantity or work, specification, addition of work / deletion of work: BRBNMPL shall have power to make any alterations / additions to or substitutions for the original specifications and instructions that may appear to him to be necessary during the maintenance work. For that purpose or if for any other reason it shall in its opinion be desirable, it shall have power to order the contractor to do any or all of the following:
 - a. Increase or decrease the quantity of any work included in the contract.
 - b. Delete any such work.
 - c. Change the character or quantity or kind of any such work.
 - d. Change the names, levels, liners, positions and dimensions of any part of the work.
 - e. Execute additional work of any kind necessary for the completion of the work
 - f. Change in any specified sequence, method of timing of the work.
 - g. The contractor shall be bound to carry out the work in accordance with any instructions in these connections which may be given to him in writing signed by the BRBNMPL and shall not on any way vitiate or invalidate the contract.
 - h. Quoted rates shall be firm and binding and inclusive of all taxes & charges.
 - i. Statutory deduction of taxes shall be made at the source.
 - j. Successful Bidder has to arrange all the required materials, labors, transportation etc., at his own cost.
 - k. The Successful Bidder has to strictly follow the safety norms during his work & also take care for BRBNMPL property.
 - l. The Successful Bidder should understand the scope of work before quoting and inspect the site accordingly.

(To be signed & stamped and submitted along with Techno-commercial Bid Part –I)

भाग / Section VII – तकनीकी विनिर्दिष्टियां / Technical Specifications and Scope of Work:

1. Preamble:

Bharatiya Reserve Bank Note Mudran (P) Limited (BRBNMPL) is a wholly owned Subsidiary of Reserve Bank of India is engaged in sovereign function of Design and printing of Bank Notes. It has corporate office at Bengaluru and has two printing presses at Mysore, Karnataka and Salboni, West Bengal.

Corporate Office, BRBNMPL, Bengaluru invites tenders from eligible vendors for the work of “Construction of Compound Wall, Pathway and Security Building & Refurbishment of Existing Signage Tower at BRBNMPL, Bengaluru”. The work has to be executed as mentioned in the BOQ as per the IS, CPWD and KPWD specifications (whichever applicable) and to the satisfaction of the officials from BRBNMPL. The general character and the scope of the works shall be as illustrated and defined in the Drawings, Specifications, Schedule of Quantities, and other Contract Documents.

2. Scope of Work:

The general character and the scope of the works shall be as illustrated and defined in the Drawings, Specifications, Schedule of Quantities, and other Contract Documents. The defined scope of work shall be as mentioned below.

The job involves carefully dismantling the existing compound wall and handing over the salvaged materials, excavation, foundation, back filling, leveling & proper consolidation, centering and shuttering, flooring, masonry, RCC, fabrication, finishing works, etc. complete.

As BRBNMPL is a security organization, the dismantling of the existing compound wall shall be taken up in stages corresponding to the progress of work.

3. General:

- i. The work shall broadly include construction of all the civil, structural & finishing works related to buildings and foundations which includes earth work, plain & reinforced cement concrete, reinforcement, scaffolding, formwork, masonry work, floor finishing, skirting, plastering, painting, roof finishes, etc. as well as supply of all materials, consumables, labour, tools and plants, transportation and storage, sample testing etc.; all complete as per BOQ, specifications and drawings.
- ii. The materials, design and workmanship shall satisfy the relevant Indian Standard, KPWD/CPWD specification, most specifications and the Specifications contained herein and codes referred to. Where the Specifications stipulate requirements in addition to those contained in the standard codes and specifications, these additional requirements shall be approved by the Engineer – in – charge. In case of any ambiguity, sound engineering practices shall prevail and the decision of engineer in charge in such matters shall be final.
- iii. The detailed specifications given hereinafter are for the items of works described in the schedule of quantities attached herein, and shall be guidance for proper execution of work to the required standards. It may also be noted that the specifications are of generalized nature and these shall be read in conjunction with the description of item in schedule of quantities and drawings. The work also includes all minor details of construction which are obviously and fairly intended and which may not have been referred to in these documents but are essential for the entire occupation in accordance with standard Engineering practice.
- iv. Unless specifically otherwise mentioned, all the applicable codes and standards published by the Indian Standard Institution and all other standards which may be published by them before the date of receipt of tenders, shall govern in all respects of design, workmanship, quality and properties of materials and methods of testing, methods of measurements etc. Wherever any reference to any Indian Standard Specifications occurs in the documents relating to this contract, the same shall be inclusive of all amendments issued thereto or revision thereof, if any, up to the date of receipt of tenders.
- v. Wherever any reference to any Indian Standard Specification occurs in the documents relating to this contract the same shall be inclusive of all amendments

issued thereto or revisions thereof, if any, up to the date of receipt of tenders. In case there is no I.S.I. specification for the particular work, such work shall be carried out in accordance with the instructions in all respects, and requirements of the Engineer-in-Charge. The work shall be carried out in a manner complying in all respects with the requirements of relevant bye-laws of the Municipal Committee/Municipal Corporation/Development Authority under the jurisdiction of which the work is to be executed or as directed by the Engineer-in-Charge and, unless otherwise mentioned, nothing extra shall be paid on this account.

- vi. The contractor shall take instructions from the Engineer-in-charge regarding collection and stacking of materials in any place. Unserviceable materials shall be stacked such that it does not hamper the day-to-day movement of people/office staff/ visitors etc.
 - vii. BRBNMPL is ISO 9001 – 2015 AND ISO 14001: 2015 certified company. The contractor in all respects shall organize his work, systems, environment, process control documentation, tools, plant, inspection, measuring and testing equipment's etc. as per instructions of Engineer.
 - viii. The contractor shall also comply with applicable legislation and regulations with regards to Health, safety and environmental aspects for minimizing risk arising from occupational health, safety hazards, controlling pollution and wastage.
 - ix. BRBNMPL may depute their representative for checking and supervision of important stages of work. The contractor shall be required to provide all facilities for inspection of works at no extra cost to BRBNMPL. Any defect in quality of work or deviations from drawings / specifications pointed out during such inspection shall be made good by the contractor in the same way as if pointed out by the Engineer, without any cost implication to BRBNMPL.
 - x. All works shall be taken over by BRBNMPL in part or in full when it has been completed in all respects and /or can be put to use satisfactorily. The complete work under the contract shall be taken over only after completion of all punch points, pending work, rework wherever required, site clearing and reconciliation of materials.
 - xi. The guarantee period shall start only after the complete work under the contract has been taken over by BRBNMPL.
 - xii. The Rates quoted shall include necessary Staging, Scaffolding for all heights & levels. No Additional rates shall be entertained for Staging and Scaffolding.
All works shall comply with relevant IS codes and KPWD/CPWD standards and specifications.
4. Drawings, Instructions and Measurements: The contractor shall strictly adhere to the working drawings or detail drawings and written instructions of the BRBNMPL / Architect. No working drawing or detail drawing shall be scaled. Figured dimensions alone shall be followed. Measurements shall be recorded of the actual work done. However, the quantum of work over and above that indicated in the working or detail drawings shall not be recorded. The mode of measurement shall be generally in accordance with IS - 1200 Method of Measurement for Building and Civil Engineering Works unless otherwise specified.
5. Additional conditions for cement, steel brought by the contractor:
- i. All the materials required for construction of work shall be arranged by the contractor at his own cost. The samples of material to be procured shall be got approved by the Engineer-in-charge and material as per approved samples shall only be procured.
 - ii. The contractor shall submit periodically as well as on completion of work, an account of all materials brought by him in a manner as directed by Engineer-in-charge. The contractor shall also furnish monthly account of materials; a separate register shall be maintained on site for recording daily item wise receipt and consumption of Cement, Steel used by him, also item wise consumption of other materials used. This register shall be signed daily by the contractor or his representative and representative of Engineer-in-charge.
 - iii. In each case, certificate for its quality and quantity shall be produced by the contractor at his own cost and the test results of samples shall be supplied to the Department. The material not confirming to the required standard shall be removed at once from the site of the work by the Contractor at his own cost.

- iv. Testing of all construction material shall be carried out as per required frequency and specifications and the charges for testing shall be borne by the contractor
 - v. All the testing charges for mix design etc. if necessary on construction work shall be borne by the contractor.
 - vi. The contractor shall construct shed / sheds as per direction of the Engineer-in-charge of the work for storing the materials brought at site. The material shall be taken out for use in the presence of the departmental representative only.
 - vii. The contractor shall make his own arrangement for the safe custody of the materials which are brought for construction of work.
 - viii. The contractor shall not transfer any material once brought at work site without prior written permission from Engineer-in-charge and for bonafied reasons only
 - ix. In case the materials brought by the contractor become surplus owing to the change in the design of the work, the materials should be taken back by the contractor at his own cost after prior permission of the Engineer-in-charge.
 - x. The charge for conveyance of materials from the place of delivery to the site of work and the actual sport on work site shall be entirely borne by the contractor. No claims on his account shall be entertained.
 - xi. The contractor shall furnish the account of cement, steel, asphalt brought by him at each time before placing orders for further supply. Also the same should submit on completion of the work, final account of the materials used by him to the Department. This account will be scrutinized by the Engineer-in-charge
 - xii. All empty cement bags or empty asphalt drums shall be the property of contractor and the same shall be removed immediately after completion of work.
6. Civil and Structural Works:
- i. Setting out of works:
The Contractor shall set out of the works and shall be responsible for the true and perfect setting out of the same and for the correctness of the positions, levels, dimensions and alignment of all parts thereof. If at any time error in this respect shall appear during the progress of the works or even after the completion of the works; the Contractors shall, if so required, at his own expense rectify such error to the satisfaction of the Engineer in Charge/BRBNMPL. The rate of site clearance is deemed to be included in the rate of earth work for which no extra will be paid.
 - ii. Excavation:
 - a) The excavation in foundation shall be carried out in true line and level and shall have the width and depth as shown in the drawings or as directed. The bottom of the excavated area shall be levelled both longitudinally and transversely as directed by removing and watering as required. The excavated earth of the selected type shall be used in filling the trenches and plinth or levelling the ground in layers including ramming and watering etc.
 - b) The earth to be used for filling shall be free from salts, organic or other foreign matter. All clods of earth shall be broken. As soon as the work in foundation has been completed and measured the site of foundation shall be cleared of all debris, brick bats: mortar dropping etc., and filled with earth in layers not exceeding 20 cms. Each layer shall be adequately watered, rammed and consolidated before the succeeding layer is laid. The finished level of filling shall be kept to shape intended to be given to floor.
 - iii. Shuttering:
 - a) The timber used in shuttering shall not be so dry as to absorb water from concrete and swell or bulge nor so green or wet as to shrink after erection. The timber shall be properly sawn and planed on the sides and surface coming in contact with concrete. The shuttering shall be supported on battens and beams and props of vertical bellies properly cross braced together so as to make the centering rigid.
 - b) The form work shall be sufficiently strong and shall have camber, so that it assumes correct shape after deposition of the concrete and shall be able to resist forces caused by vibration of live load of men working over it and other incidental loads associated with it. The shuttering shall have smooth and even surface and its joints shall not permit leakage of cement grout.
 - c) If at any stage of work during or after placing concrete in the structure, the form work sags or bulges out beyond the required shape of the structure, the concrete shall be removed and work redone with fresh concrete and adequately rigid form

work. The complete form work shall be got inspected by and got approved from the Engineer-in-charge, before the reinforcement bars are placed in position.

iv. Reinforcement Works:

- a) The work shall consist of furnishing and placing reinforcement to the shape and dimensions shown as on the drawings or as directed. Steel shall be clean and free from rust and loose mill scale at the time of fixing in position and subsequent concreting. Reinforcing steel shall conform accurately to the dimensions given in the bar bending schedules shown on relevant drawings. Bars shall be bent cold to specified shape and dimensions or as directed using a proper bar bender, operated by hand or power to attain proper radius of bends. Unless otherwise specified a „U“ type hook at the end of each bar shall invariably be provided to main reinforcement. The hooks shall be suitably encased to prevent any splitting of the concrete.
- b) All the reinforcement bars shall be accurately placed in exact position shown on the drawings and shall be securely held in position during placing of concrete by annealed binding wire not less than 1 mm. in size and by using stay blocks or metal chair spacers, metal hangers, supporting wires or other approved devices at sufficiently close intervals. Bars shall not be allowed to sag between supports nor displaced during concreting or any other operations of the work. Reinforcement after being placed in position shall be maintained in a clean condition until completely embedded in concrete. To prevent reinforcement from corrosion, concrete cover shall be provided.

v. Concrete works;

- a) The Proportion of cement, sand and coarse aggregate shall be as mentioned in the BOQ for specific work enumerated and shall be measured by volume. The minimum quantity of cement used in cement concrete of specific grade has to be maintained strictly as per IS code. The concrete shall be mixed in a mechanical mixer at the site of work. Hand mixing may however be allowed for smaller quantity of work if approved by the Engineer-in-charge. The concrete shall be handled from the place of mixing to the final position in not more than 15 minutes by the method as directed and shall be placed into its final position, compacted and finished within 30 minutes of mixing with water i.e. before the setting commences. Workability of the concrete shall be controlled by maintaining a water-cement-ratio that is bound to give a concrete mix which is just sufficiently wet to be placed and compacted without difficulty with the means available. The degree of consistency which shall depend upon the nature of the work and methods of vibration of concrete, shall be determined by regular slumps tests in accordance with IS Code.
- b) Contractor shall give the Engineer-in-charge due notice before placing any concrete in the forms to permit him to inspect and accept the false work and forms as to their strength, alignment, and general fitness but such inspection shall not relieve the contractor of his responsibility for the safety of men, machinery, materials and for results obtained. No concrete shall be placed in any part of the structure until the approval of the Engineer-in-charge has been obtained.
- c) Concreting shall proceed continuously over the area between construction joints. Fresh concrete shall not be placed against concrete which has been in position for more than 30 minutes unless a proper construction joints is formed. Concrete shall be compacted in its final position within 30 minutes of its discharge from the mixer.
- d) Concrete shall not be dropped into place from a height exceeding 2 meters. When trunking or chutes are used they shall be kept close and used in such a way as to avoid segregation. When concreting has to be resumed on a surface which has hardened, it shall be roughened, swept clean, thoroughly wetted and covered with a 13 mm. thick layer of mortar composed of cement and sand in the same ratio as in the concrete mix itself.
- e) All concrete shall be compacted to produce a dense homogeneous mass with the assistance of vibrators, unless otherwise permitted by the Engineer-in-charge for exceptional cases, such as concreting under water, where vibrators cannot be used. Sufficient vibrators in serviceable condition shall be kept at site so that spare equipment is always available in the event of breakdowns.

- f) Immediately after compaction, concrete shall be protected from weather, including rain, running water, shocks, vibration, traffic, rapid temperature changes, frost and drying out process. It shall be covered with wet sacking, hessian or other similar absorbent material approved soon after the initial set and shall be kept continuously wet for a period of not less than 14 days from the date of placement. Masonry work over foundation concrete may be started after 48 hours of its laying but curing of concrete shall be continued for a minimum period of 14 days.
 - g) Samples from fresh concrete shall be taken as per IS Code provisions and cubes shall be made, cured and tested at 7 days or 28 days as per requirements in accordance with IS code. A random sampling procedure shall be adopted to ensure that each concrete batch shall have a reasonable chance of being tested i.e. the sampling should be spread over the entire period of concreting and cover all mixing units.
 - h) No additional cost shall be paid for Continuous De- Watering for all foundation works
 - i) The RMC shall be obtained from the approved RMC plant from outside for RMC works based on the approved design mix for which necessary certificate should be furnished. Regarding minimum cement content relevant IS specifications shall prevail. Only Ordinary Portland cement shall be used for RMC Works.
 - j) Clearance for site mix (with approved weigh batched designed concrete mix) under special circumstances to be taken from EIC.
 - k) Rate quoted for RMC/Site Mix Concrete shall be for all floors and at all levels and no additional charges are payable towards lift.
 - l) Use of admixture, its type, dosage and conditions of its use shall be as per design mix and no extra cost is admissible in this regard.
 - m) Design Mix with trial cubes strength shall be got approved from consultants well in advance before commencement of RCC works.
- vi. Formwork:
- a) Providing and removing centering, shuttering, strutting, propping etc, and removal of form work for compound wall, foundations, footings ,rafts, pedestals for mass concrete including cost of all materials, labour complete as per specifications.
 - b) Providing and erecting Formwork for RCC Compound Wall / at all levels and places with plywood lining, of all shapes and sizes, at all levels & heights, providing grooves of various shapes and sizes including scaffolding, releasing & removing the formwork, etc; complete as per specifications
 - c) Providing, fabricating and erecting form faced formwork at all levels and places wherever needed / specified as per drawing including striking / deshuttering with necessary safety precautions.
 - d) Material :12mm thick Marine grade or film faced plywood of high density (34 Kg) of make Green Ply/Virgo/Archid Ply/Somany / equivalent should be used and shall be repeated upto a maximum of 10 repetitions. (5 repetitions on each side) with surface treatments that provide a nearly impervious and smooth surface. Mixing different brands or surface treatments should be avoided to avert variations in colour caused by amount of water absorption.
 - e) Shuttering Oil for all Slabs, Beams, Shear walls, Columns, Chajjas etc shall be of Rebbol -E from M/s. Fosroc, Sika Form Oil from M/s. Sika & Dr. Fixit De-shuttering Oil from M/s. Dr.Fixit / equivalent of reputed make
 - f) Form Liners: Form Liners in concrete works upto 600mm in height for elevation with white band shall be of foam liner made out of fiber glass fixed to the form work. Texture finish of fiber glass shall be as per architects requirement. The Form Liner to be match with the Existing Building.
 - g) Accuracy: Form faced formwork should be designed, constructed and maintained in accordance with detailed specifications, recommendations of ACI 347-04 and additional requirements out lined. Form faced concrete requires care in design to minimize deflection, deformations, pillowing, offsets and mortar leakage. Specified clearances between reinforcement and formwork should be maintained.

- h) Form face should be designed as a stable envelop to contain the fresh concrete, extra walers, additional ties and bracings to be provided to satisfy the deflection requirements and also to maintain alignment during vibrating of concrete.
 - i) Form joints: Leakage should be minimized for uniform colour and texture are critical. Leakage shall be minimized by providing lining forms with separate materials and staggering the joints using pressure sensitive compressible gaskets / tapes or sealant with in form interfacing joints. Care should be taken to prevent displacement of tape / gaskets during concrete operations. A mock up panel to be done to verify the effectiveness of taped joints.
 - j) Form Release agents : Material applied to the form sheathing to prevent the bonding of concrete to the sheathing, to keep the formwork clean and assist in the successful production of high quality architectural surfaces.
 - k) For Uniformity of appearance, the same release agent should be used for all architectural concrete surfaces.
 - l) Chemically active release agents shall be used. Fatty acids chemically react with basic materials in concrete and produce soap. Soap is better lubricant than oil for removal of entrapped air in fresh concrete.
 - m) Providing of Grooves of Various Sizes in Exposed Concrete works 20x12mm , 12mmx12mm & 50mm x 12mm made of PVC.
- vii. Concrete Block Works:
- a) Hollow or solid concrete blocks shall conform to IS 2185 and shall be regular in size and shape and of the specified strength.
 - b) Blocks shall be properly cured before being brought to Site and shall have a texture such that plaster and/or render will readily adhere to it.
 - c) The Contractor shall supply samples for the approval of the Engineer and all blocks supplied shall conform strictly to the approved samples.
 - d) Half or three quarter size blocks may be used wherever required to make up lengths of walls but broken blocks shall not be used.
 - e) Pre-cast concrete screen or special blocks or 'jalli' work for decorative purposes shall be as specified on the drawings or as directed by the Engineer. Sample blocks shall be submitted to the Engineer for approval and blocks supplied shall strictly conform to the approved samples.
 - f) Mortar shall be prepared in accordance with IS 2250. Mixes for cement mortar shall be as specified for the respective items of work. Cement shall be ordinary Portland cement as described in Specification 2.2.
 - g) Sand shall be natural sand in accordance with IS 383, passing a 4.75mm size IS sieve, and shall be free from clay, shale, loam, alkali, organic and other deleterious matter and shall be of sound, hard, clean and durable particles. Sand shall be approved by the Engineer and, if so directed, shall be thoroughly washed until it is free of any contamination.
 - h) Gauge boxes for sand shall be of such dimensions that one complete 50Kg bag of cement forms one unit.
 - i) For the preparation of cement mortar the ingredients shall first be thoroughly mixed dry. Water shall then be added and the mixing continued until a uniform mix of the required consistency is achieved.
 - j) Cement mortar shall preferably be machine mixed, though hand mixing in troughs may be allowed with the approval of the Engineer. Mortar so mixed shall be used within 25 (twenty five) minutes of mixing. Mortar left unused within the specified period shall be rejected and disposed of by Contractor to satisfaction of the Engineer. Re-tempering of mortar shall not be permitted.
 - k) The Contractor shall arrange at his own cost for tests on mortar samples, if so directed by the Engineer.
 - l) Workmanship:
 - 1. Block work shall be plumb, square and properly bonded with broken joints. The thickness of the courses shall be uniform with courses horizontal. All connected work shall be carried out at one level and no portion of the work shall be left more than one course lower than the adjacent work.
 - 2. Blocks shall be laid so that all joints are well filled with mortar. Joined shall not be less than 6mm and not more than 8mm thick. Face joints shall be raked to a minimum depth of 10mm by raking tools during the progress of work when the mortar is still green so as to provide a proper key for pointing,

plastering or rendering. When pointing, plastering or rendering is not required joints shall be struck flush.

3. For pointed block work or block work without plaster or render approved, smooth textured concrete blocks shall be used.
4. Faces of block work shall be cleaned daily and all mortar droppings cleaned off and removed. Top surfaces of each course shall be thoroughly cleaned before other courses are laid. If mortar in lower courses has begun to set joints shall be raked out to a depth of 12mm before laying is continued.
5. Where blocks are to be used for load bearing walls the uppermost course of blocks supporting slabs or other structural members shall be solid or treated as directed by the Engineer.
6. Miscellaneous inserts in block work, e.g. sleeves, wall ties, anchors, conduits, structural steel, steel lintels and the like shall be installed by the Contractor and these items shall be deemed to be included in the quoted rates for block work. The supply of such inserts by the Contractor will be paid separately in accordance with the relevant items of the Bill of Quantities.
7. Openings, arches, chases, pockets and the like shall be provided as shown on the drawings to receive windows, louvers, doors frames and the like.
8. Wall ties and flashings shall be built into block work in accordance with the drawings and Specifications. It shall be clearly understood that the rates quoted by the Contractor shall be deemed to include for leaving openings, Forming arches, cutting chases pockets and the like in block work for various trades.

viii. Waterproofing:

Providing and laying integral cement based waterproofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc., consisting of following application:

- a) Preparing the Surface: The surface of the slab should be roughened by scrapping when the slab concrete is still green, however, the surface need not be hacked. In case the slab is already cast and surface fairly finished, the same shall be cleaned neatly of all mortar droppings, loose materials etc. with brooms/cloth.
- b) Providing and Laying of Slurry under Base Coat:
 1. The consistency of the slurry should be such as to cover the desired area by using 0.488 kg of blended cement per sqm of area.
 2. On deciding the correct quantity of water required per sqm. area the required quantity of slurry should be prepared which can be applied over the desired surface within half an hour of mixing with 0.488 kg. of grey cement + 0.253 kg. water proofing compound as per manufacturer specifications + x litres of water per sqm. area and the required quantity of slurry thus prepared should only be used for first application.
 3. The first layer shall be applied with painting brushes over the specified and dampened area carefully including the corners, holes on the surfaces and joints of pipes in concrete etc. and the application should continue at least upto 150 mm height of fixtures of pipes from the surface. The surface on application shall be air cured for 4 hours.
 4. The quantity of water required to prepare the slurry with 2.75 kg. of blended cement to be painted over an area of 1 sqm. shall be calculated exactly as described above. Depending upon the area of surface that has to be covered, the required quantity of slurry should be prepared using 2.75 kg. blended cement + water per sqm. area to be covered, taking particular care to see that only that much quantity of slurry shall be prepared which can be used within half an hour of preparation i.e. before the initial setting time of cement.
 5. The prepared slurry shall be applied over the dampened surface with brushes very carefully, including the joints between the floor slab and the parapet wall, holes on the surfaces, joints of pipes, masonry/concrete etc.
 6. The application of the slurry should continue upto a height of 300 mm on the parapet wall and also the groove. The slurry should also be applied upto a height of 150 mm over pipe projections etc.

- c) Laying Base Coat 20 mm thick: Immediately after the application of slurry and when the application is still green, 20 mm thick cement plaster as base coat with cement mortar 1:5 (1 blended cement : 5 coarse sand) shall be evenly applied over the concrete surface taking particular care to see that all the corners and joints are properly packed and the application of the base coat shall be continued upto a height of 300 mm over the parapet wall.
- d) Laying Brick Bat Coba:
1. Brick bat of size 25 mm to 115 mm out of well burnt bricks shall be used for the purpose of brick bat coba. The brick bats shall be properly dampened for six hours before laying. Brick bats shall be laid to required slope/gradient over the base coat of mortar leaving 15-25 mm gap between two bats. Cement mortar 1:5 (1 blended cement: 5 coarse sand) shall be poured over the brick bats and joints filled properly. Under no circumstances dry brick bats should be laid over the base coat.
 2. The haunches/gola at the junction of parapet wall and the roof shall be formed only with brick bat coba.
 3. In case the brick bat coba is laid on the base coat immediately on initial set there will be no necessity of applying cement slurry over the base coat before laying the brick bat coba. However, if the brick bat coba is to be laid on the subsequent day, cement slurry prepared as described below and shall be applied over the top surface of the base coat, then only the brick bat coba shall be laid.
 4. The quantity of water required to prepare the slurry with 2.75 kg. of blended cement to be painted over an area of 1 sqm. shall be calculated exactly as described above. Depending upon the area of surface that has to be covered, the required quantity of slurry should be prepared using 2.75 kg. blended cement + water per sqm. area to be covered, taking particular care to see that only that much quantity of slurry shall be prepared which can be used within half an hour of preparation i.e. before the initial setting time of cement.
 5. The prepared slurry shall be applied over the dampened surface with brushes very carefully, including the joints between the floor slab and the parapet wall, holes on the surfaces, joints of pipes, masonry/concrete etc.
 6. The application of the slurry should continue upto a height of 300 mm on the parapet wall and also the groove. The slurry should also be applied upto a height of 150 mm over pipe projections etc.
- e) Application of Slurry over Brick Bat Coba: After two days of curing of brick bat coba cement slurry prepared as mentioned in above paragraph and shall be applied on the surface of brick bat coba. The application of slurry shall be the same as described in clause laying of slurry in base coat which should cover the haunches/gola, and the remaining small portion of parapet wall and also inside the groove as shown in the figure.
- f) Laying Finishing Layer (Protective Coat):
1. Immediately on applying the cement slurry over the surface of the brick bat coba and when the slurry applied is still green. The fibre glass cloth shall be of approved brand and shall be thin, flexible uniformly bonded mat composed of chemically resistant borosilicate glass fibre distributed in random open porous structure bonded together with a thermosetting resin.
 2. The cloth shall be spread evenly on the surface without any kink & pressed to see that no air spaces exist. The fibre glass cloth shall be taken up to a height of 300 mm on parapet walls & tucked in the groove specially prepared at that height. 20 mm thick layer of cement plaster, without leaving any joints shall be applied with cement mortar 1:4 (1 blended cement: 4 coarse sand) over the entire fibre glass cloth including the haunches/gola and the small portion on the parapet wall. The groove in the parapet wall over the haunches shall also be filled neatly packing the mortar firmly in the groove.
 3. The surface of the finishing layer (protective coat) shall be neatly finished with cement slurry prepared as per clause providing slurry for base coat. The finished surface shall be allowed to dry for a while and then pattern of 300 mm x 300 mm groove, 8 mm deep shall be made over the entire surface.

- g) Curing and Testing the Treatment: The entire surface thus treated shall be flooded with water by making kiarries with weak cement mortar, for a minimum period of two weeks.
- ix. Fabrication:
 - a) The fabrication of structures with steel tubes shall generally conform to IS 806. The general provisions in Section V of IS 800 are also applicable to the fabrication of structures using steel tubes. Where welding is adopted, reference to appropriate provision of IS 820 and IS 816 shall be made.
 - b) The component parts of the structure shall be assembled in such a manner that they are neither twisted nor otherwise damaged and be so prepared that the specified cambers, if any, are maintained.
 - c) Straightening: All materials before being assembled, shall be straightened unless required to be of a curvilinear form and shall be free from twists.
 - d) Bolting: Washers shall be specially shaped where necessary or other means used, to give the nuts and the heads of the bolts a satisfactory proper bearing. In all cases where the full bearing area of the bolt is to be developed, the threaded portion of the bolt shall not be within the thickness of the parts bolted together, and washers of appropriate thickness shall be provided to allow the nut to be completely tightened.
 - e) Cut edges: Edges should be dressed to a neat and workmanlike finish and be free from distortion where parts are to be in contact, metal to metal. For tube to tube connections the cutting of individual members shall be done with Profile Cutting Machines only.
 - f) Caps and bases for columns: The ends of all tubes for columns, transmitting loads through the ends, should be true and square to the axis of the tube and should be provided with a cap or base accurately fitted to the end of the tube and screwed, welded or shrunk on. The cap or base plate should be true and square to the axis of the column.
 - g) Connections:
 - 1. Connections in structures using steel tubes shall be provided by welding, riveting or bolting. Wherever possible, connections between tubes shall be made directly, tube to tube without gusset plates and other attachments. Ends of tubes may be flattened as specified or otherwise formed to provide for welded, riveted or bolted connections.
 - 2. Eccentricity of members: Tubes meeting at a point, shall wherever practicable, having their gravity axes, meeting at a point so as to avoid eccentricity.
 - 3. Eccentricity of connections: Wherever practicable, the center of resistance of the connection shall lie on the line of action of the load, so as to avoid eccentricity moment of connection.
 - 4. Tolerances: The tolerances as mentioned in (IS 1161-1979) shall apply.
 - 5. Sealing of tubes: When the end of a tube is not automatically sealed by the virtue of its connection by welding to another member, the end shall be properly and completely sealed. Before sealing, the inside of the tube should be dry and free from loose scale.
 - 6. Flattened ends: In tubular construction, the ends of tubes may be flattened or otherwise formed to provide for welded, riveted or bolted connections provided that the methods adopted for such flattening do not injure the material. The change of section shall be gradual
 - 7. Welded connections: A weld connecting two tubes end to end, shall be full penetration butt weld. The effective throat thickness of the weld shall be taken as the thickness of the thinner part joined.
A weld connecting the end of one tube (branch tube) to the surface of another tube (main tube) with their axes at an angle of not less than 30 degrees shall be of the following types:
 - a) A butt weld throughout
 - b) A fillet weld throughout, and
 - c) A fillet-butt weld, the weld being a fillet weld in one part and a butt weld in another with a continuous change from one form to the other in the intervening portions.

Type (a) may be used whatever the ratio of the diameters of the tubes joined, provided complete penetration is secured either by the use of backing material, or by depositing a sealing run of metal on the back of the joint, or by some special method of welding. When type (a) is not employed, type (b) should be used where the diameter of the branch tube is less than 1/3rd of the diameter of the main tube, and type (c) should be used where the diameter of the branch tube is equal to or greater than 1/3rd of the diameter of the main tube.

8. Angle between tubes: A weld connecting the end of one tube to the surface of another, with the axes of the tubes intersecting at an angle of less than 30 degrees, shall be permitted only if adequate efficiency of the junction has been demonstrated.

x. Cement Concrete Flooring (IPS) / Granolithic Flooring;

- a) The flooring shall be of specified thickness and shall consist of 1:2:4 concrete base as specified and 12mm thick granolithic wearing coat. The granolithic flooring shall be laid in alternate panels. The size of panels shall be as decided by the architects.
- b) The sand shall be screened and thoroughly washed to remove all dust and silt.
- c) The coarse aggregate shall be of approved quality, well graded and shall not exceed 10 mm size. The coarse aggregate shall be also washed thoroughly to remove all dust and dirt.
- d) The surface to be paved shall be thoroughly hacked, cleaned of all mortar, loose materials etc. and washed to remove the mud and dirt from the surface. Unless and until the surface is approved by the Engineer-In-charge the paving shall not be started.
- e) The surface to be paved shall then be wetted for at least 24 hours before the paving is taken in hand. Before placing the concrete for flooring neat cement slurry shall be thoroughly brushed into the prepared surface of the base concrete just ahead of the finish.
- f) The 1:2:4 concrete base shall be of graded course aggregate of maximum size 10 mm and course sand and cement. The ingredients shall be thoroughly mixed with sufficient water to obtain the required plasticity.
- g) The prepared 1:2:4 concrete shall be laid immediately after mixing on the fresh grouted base. The concrete shall be spread evenly and leveled carefully. Low places shall be filled, humps removed and the whole surface again leveled. The layer shall be compacted by ramming and trowel led and allowed to set.
- h) One part of cement in dry state shall be mixed with 1.5 parts by volume of well graded/crushed granite chips of 6 mm maximum size. The ingredients shall be then mixed with sufficient water as for ordinary concrete.
- i) The wearing coat shall be laid 12mm thick over 1:2:4 cement concrete base immediately after it has set compacted and leveled with a steel trowel. Just sufficient toweling shall be made to give a level surface. The surface should not be over trowel led, as excessive toweling will bring the cement to the surface, which shall be strictly avoided. When the initial set takes place, further compaction by steel toweling shall be done and final brushing shall be made before the topping becomes too hard.
- j) The paving shall be cured for at least 7 days and it shall be protected during this period with hessian or other suitable material / means which will not stain the surface.
- k) The laying and finishing shall conform to I.S. 2571.
- l) The paving shall be laid in alternate bays of size as specified by the Engineer-in-charge. The formwork required for setting the bays shall not be paid extra.

xi. Specification For Marble / Granite / Antique Finish Flooring, Treads, Risers, Sills, Cladding, Dado:

a) Dressing of Slabs:

1. Every stone shall be cut to the required size and shape, fine dressed on all sides to the full depth so that a straight edge laid along the side of the stone is full in contact with it. The top surface shall also be fine dressed to remove all waviness. The top surface of slabs shall be machine polished and exposed edges machine cut, or as specified in the item and as directed by the Engineer-in-charge. All visible angles and edges of the slabs shall be

true, square or as required, and free from chippings and the surface shall be true and plane.

2. The thickness of the slabs shall be specified in the description of item. The minimum size of stone to be used for various items shall be as mentioned in the schedule of quantities/drawings of this tender. Marble stones of approved smaller sizes other than mentioned in the schedule of quantities, if required for bands, borders, flooring etc. shall be provided and laid as directed by the Engineer-in-charge.
3. Any opening of required size and shape at any desired place in flooring, bands, borders etc. shall be made in such a way that marble bounded by number of marble stones/slabs. No broken or defaced stone shall be permitted in the work.

b) Bedding/Backing Mortar:

1. The bedding/backing shall be of cement mortar/lime mortar of mix and thickness as specified in the description of the item.
2. Mixing: The mixing of mortar shall be done in mechanical mixer or hand mixing as specified/as directed by the Engineer-in-Charge.
3. Mixing in Mechanical Mixer: Cement and sand in the specified proportion shall be mixed dry thoroughly in a mixer. Water shall then be added gradually and wet mixing continued for at least one minute. Care shall be taken not to add more water than that which shall bring the mortar to the consistency of stiff paste.
4. Only the quantity of mortar, which can be used within 30 minutes of its mixing shall be prepared at a time.
5. Mixer shall be cleaned with water each time, before suspending the work.
6. Hand Mixing: If approved by Engineer-in-Charge, hand mixing shall be allowed. The measured quantity of sand shall be leveled on clean masonry platform and cement bags emptied on top. In hand mixing, the quantity of cement shall be increased by 5% over the approved constant, with no extra cost to the Department. The cement and sand shall be thoroughly mixed dry by being turned over and over, backwards and forwards, several times till the mixture gives an uniform colour. The quantity or dry mix which can be used within 30 minutes shall then be mixed on masonry through with just sufficient quantity of water to bring the mortar to the consistency of stiff paste.
7. Mortar shall be used as soon as possible after mixing and before it has begun to set, and in any case within 30 minutes after the water is added to the dry mixture. Mortar unused for more than 30 minutes shall be rejected and removed from the site of work immediately

c) Laying:

Before laying the cement mortar bedding/backing, the concrete/brick, floor/wall surfaces shall be thoroughly hacked, cleaned of all mortar scales, concrete lumps etc., brushed, washed with water to remove mud, dirt etc. from the surface and shall be thoroughly wetted. Until and unless the surface is approved by the Engineer-in-Charge, the flooring shall not be started. A bedding of cement mortar of 20 mm. average thickness with the minimum thickness at any place under the slab not less than 13mm. shall be laid evenly and to the required slopes as directed / specified. The marble slabs shall be thoroughly washed and cleaned and then be laid on the bedding/ backing with cement floating at the rate of 4.39 kg./sqcm. All slabs shall be truly and evenly set in a thick cement slurry or paste like consistency applied to the sides and bottom and over the prepared base. The slabs shall then be tamped down with a wooden mallet until they are exactly in true plane and line with adjacent slabs. All slabs shall be extended upto the unplastered surface of masonry walls/RCC columns/RCC walls. The slabs shall be close jointed in matching cement slurry and the cement slurry coming out through the thin joints shall be immediately wiped clean. The grains of marble stone shall be matched as shown in drawing or as directed by the Engineer-in-Charge. All slabs shall be so laid as to have continuous lines from various rooms to the corridors. No change of lines shall be permitted at junction between rooms and corridor, if the same flooring is specified in both the places.

- d) Dado & Cladding:
Only machine cut and machine polished marble stone will be used. Brass cramps and brass pins of approved quality, size and make shall be provided. The brass pins shall be provided at the meeting of two marble slabs both ways horizontally and vertically. The brass cramps shall be provided at the places approved by the Engineer-in-Charge. Marble to be used shall be of approved size, colour, type of veins and laid as specified in schedule of quantities or to the pattern shown in drawings or as directed by the Engineer-in-Charge. Laying of marble stone shall be similar as stated above as far as applicable.
- e) Polishing & Finishing:
- xii. Flooring, Dado / Skirting / Facia:
The tiles shall be of approved make and shall generally conform to the approved standards. They shall be flat and true to shape, free from cracks, crazing spots, chipped edges and corners.
- a) Surface preparation for flooring –
1. Sub grade concrete or RCC slab or side brick / block wall / or plastered surfaces on which tiles are to be laid shall be cleaned, wetted and mopped.
 2. Mortar and bedding: Cement mortar for bedding shall be prepared of mix 1:4 or as specified in the schedule of items, to a consistent paste and shall conform to the specification for materials, preparations etc. as specified under cement mortar. The amount of water added while preparing mortar shall be the minimum necessary to give sufficient plasticity for laying. Care shall be taken in preparation of the mortar to ensure that there are no hard lumps that would interfere with even bedding of the tiles. Before spreading the mortar bed the base shall be cleaned off all dirt, scum or laitance and loose materials and well wetted without forming any pools of water on the surface. The mortar of specified proportion and thickness shall then be evenly and smoothly spread over the base by use of screed battens to proper level or slope.
 3. Once the mix is prepared, no further water be added and the same shall be used within one hour of adding water. Apply on an average 20 mm thick bedding of mortar over an area of 1 Sqm. at a time over surface of the area for laying tiles, in proper level and allowed to harden sufficiently to offer a fairly good cushion for the tiles to set
- b) Laying of Tiles:
1. The tiling work shall be done as per the pattern shown in the drawing or as directed by the Engineer-in-Charge. As a general practice laying of tiles shall be commenced from the centre of the area and advanced towards the walls. Cut tiles, if any, shall be laid along wall with necessary border / pattern as shown / directed by the Engineer-in-Charge. Tiling work shall be completed by pressing tiles firmly into place along the wall / floor. A white cement slurry to the back of the tile to be applied to ensure proper and full bedding. The tiles shall be laid on the bedding mortar when it is still plastic but has become sufficiently stiff to offer a fairly firm cushion for the tiles. Tiles, which are fixed on the flooring adjoining the wall, shall be so arranged that the surface on the round edge tiles shall correspond to the skirting or dado. Press gently the tile with wooden mallet for even adherence at the back of the tile. Do not use an iron hammer or some heavy material to press the tile.
 2. The edges of the tiles shall be smeared with neat white cement slurry and fixed in this grout one after the other, each tile being well pressed and gently tapped with a wooden mallet till it is properly bedded and in level with the adjoining tiles. There shall be no hollows in bed or joints. The joints shall be kept as close as possible and in straight line. Unless otherwise specified, joint-less tiling shall be done butting the tiles with each other. If joint is specified, the same shall be as specified by the Engineer-in-charge. The joint shall be grouted with white / matching colour cement slurry. After fixing the tiles, finally in an even plane or slope, the flooring shall be covered with wet sand and allowed undisturbed for 14 days.
- c) Dado & Skirting / Facia:

1. The fixing of tiles on wall surfaces shall be done only after completing fixing of the tiles on the floor. Following procedure shall be followed:
 2. The back of tiles shall be cleaned off and covered with layer of cement paste or approved adhesive like BAL-ENDURA or equivalent with proper troweling as per manufacturer's recommendations.
 3. The edges of the tiles shall be smeared with cement paste or adhesive and fixed on the wall one after the other, each tile being well pressed and gently tapped with a wooden mallet till it is properly fixed in level with the adjoining tiles. There shall be no hollows on the back or in joints. Unless otherwise specified, joint-less tiling shall be done butting the tiles with each other. If joint is specified by the Engineer-in-charge, the joint shall be grouted with approved white / matching colour cement slurry cement or adhesive. The joints shall be kept in straight line or as per the approved pattern.
 4. While fixing tiles in dado / skirting work, care shall be taken to break the joints vertically. The top line shall be touched up neatly with the rest of the plaster above. If doors, windows, sanitary fittings or other openings are located within the dado area, the corners, sills, jambs etc. shall be provided with true right angles without any specials. The contractor will not be entitled to any extra claims on this account for cutting of tiles if required.
 5. The fixing shall be done from bottom of wall to upward without any hollows in the bed of joints. Each tile shall be as close as possible to one adjoining. All tiles faces shall be in one vertical plane.
- d) Grouting of Joints:
1. The joints, if specified, shall be cleaned off and all dust and loose particles removed. Joints shall then be filled with approved adhesive like BAL-ENDURA or equivalent grouts. After finishing the grouting process, after 15 minute, wipe off excess grout with a damp sponge and polish the tiles with a soft & dry cloth for a clean surface. The Finished work shall not sound hollow when tapped with a wooden mallet.
- xiii. Painting Works:
- a) The surfaces painting shall be cleaned of all rust, scale, dirt and other foreign matter sticking to it with wire brushes, steel wool, scrapers, sand paper etc. This surface shall then be wiped finally with mineral turpentine which shall also remove grease and perspiration of hand marks. The surface shall then be allowed to dry.
 - b) After the preparation of the surface, the priming coat shall be applied immediately. The brushing operations are to be adjusted to the spreading capacity advised by the manufacturer of the particular primer. The paint shall be applied evenly and smoothly by means of crossing and laying off. No hair marks from the brush or clogging at pain puddles in the corner of panels angles of molding etc. shall be left on the work
 - c) The materials required for work of painting work shall be obtained directly from approved manufactures or approved dealer and brought to the site in maker's drums; kegs. etc. with seal unbroken. All materials not in actual use shall be kept properly protected, lids of containers shall be kept closed and surface of paint in open or partially open containers covered with a thin layer of turpentine to prevent formation of skin. The materials which have become state or flat due to improper and long storage shall not be used. The paint shall be stirred thoroughly in its container before pouring into small containers. While applying also, the paint shall be continuously stirred in smaller container. No left over paint shall be put back into stock tins. When not in use the containers shall be kept properly closed.
 - d) The surface to be painted shall be thoroughly cleaned and dusted. All rust, dirt and grease shall be thoroughly removed before painting is started. No painting on exterior or other exposed part of the work shall be carried out in wet, damp or otherwise unfavorable weather and all the surfaces shall be thoroughly dry before painting work is started.
 - e) Brushing operations are to be adjusted to the spreading capacity advised by the manufacture of particular paint. Each coat shall be allowed to dry completely and lightly rubbed with very fine grade of sandpaper and loose particles brushed off before next coat is applied.

- xiv. Concertina Coil / Barbed Wire Fencing Works:
The Concertina Coil / Barbed Wire Fencing Works shall be carried out as per the instructions / drawings.
The code of practice shall correspond to IS 278:2009.

7. Maintenance of Records & Documentation:

It shall be the sole responsibility of the contractor to maintain all the necessary records and documentation pertaining to the project works. Some of the important documents re listed below:

i. Site order Book:

The contractor shall himself engage an authorized all time site engineer/supervisor / agent on the work capable of managing and guiding the work and understanding the specifications and contract conditions. A qualified and experienced person shall be provided by the contractor as his agent for technical matters. Site engineer can also be designated as an agent of the contractor. Agent will take orders as will be given by the Engineer in charge or his representative and shall be responsible for carrying them out. This agent shall not be changed without prior intimation of the Engineer in charge and his representative on the work site. The Engineer-in-charge have the unquestionable right to ask for changes in the quality and strength of supervisory staff of contractor and to order removal from work of any of such staff. The contractor shall comply with such order and effect replacements of the satisfaction of the Engineer-in-charge.

A Site order book shall be maintained on site and it shall be the property of BRBNMPL and the contractor shall promptly sign orders given therein by the Engineer in charge or his representative and his superior officer, and comply with them. The compliance shall be reported by contractor to the Engineer in charge in good time so that it can be checked. The contractor will be allowed to copy out the instruction therein from time to time.

ii. Daily / Weekly /Monthly Progress Reports

iii. Material Register

iv. Quality / Test Certificates / Batch / MSDS / Design Mix / MTC etc.

v. Hindrance Register :

In order to have a record of hindrances in the progress of work which may result in delays and consequent claims for extension of time, a Hindrance Register shall be maintained at the construction site. The details of the hindrances with time period shall be recorded by the BRBNMPL Officer therein as and when these occur and all recordings shall be signed jointly by the BRBNMPL Officer and the contractor's representative. While considering the contractor's request for extension of time for completion of work, this register shall be referred to. BRBNMPL shall maintain such register and same should be in the custody of the BRBNMPL. Genuine and acceptable hindrances to their work recorded in this register will only be considered for extension of time.

8. Utility Services:

BRBNMPL shall provide connection for water and power at one point. It shall be the responsibility of the contractor to draw them. Water / electricity shall be provided free of cost.

9. Clean Up of Site Work:

During execution, the contractor shall without any additional payment, at all times keep the working and storage areas used by him, free from accumulation of waste materials or rubbish. Before completion of all works and handing over of the site, he shall remove or dispose of in a satisfactory manner all excess materials, temporary structures, waste and debris and leave the premises in a condition satisfactory to BRBNMPL.

Note: Prior to the preparation and submission of this tender, the contractor shall make visits to the site and carry out all the necessary inspections and investigations in order to obtain all information and to make his own assessment of the conditions and constraints at site, including means of access to it. The contractor shall make himself aware of all the features of the site and working conditions and space and shall, in general, be responsible for obtaining all the necessary and requisite information needed for him to prepare and submit the tender.

List of Preferred Make of Materials

Sl. No.	Particulars	Make
01	Cement	ACC, L&T (Ultratech), Rajasree, Zuari, Coromandel, Birla Super, Dalmia, Penna or equivalent
02	Reinforcement Steel	Bhuwalka, Tata, Tisco, Sail, Vizag or equivalent
03	Structural Steel	Tisco, Iisco, Sail, Vizag or equivalent
04	Tubular Steel	Tata, Gujarat Steel, Zenith, Apollo or equivalent
05	Aluminum Extrusions	Jindal, Hindalco, Bhorka or equivalent
06	Vitrified Tiles	Kajaria, Somany, Nitco, Johnson or equivalent
07	Cement Tiles	Eurocon, Ultra Tile, Basanth Baton or equivalent
08	Glass (Sheet)	Atul, Saint Gobain, Pilkington, Asahi or equivalent
09	Glass (Float)	Modiglass, Saint Gobain, Atul Tuf, Pilkington or equivalent
10	Polysulphide Sealant	Tuffseal, Pedilite, Choksey, Fosroc or equivalent
11	Silicone Sealant	Ge Silicones, Dow Corning, Rodosil, Anabond or equivalent
12	Ready Mix Paints	Asian Paints, Goodlass Nerolac, Berger, Jhenson & Nickelson or equivalent
13	Cement Paints	Super Snowcem, Sandtex Matt, Berger Paints or equivalent
14	Industrial Paints	Goodlass Nerolac, Berger, Asian, Shalimar or equivalent

भाग /Section VIII: गुणता नियंत्रण आवश्यकताएँ /निविदाकर्ता द्वारा घोषणा/ Quality Control Requirements/Declaration by the tenderer

Tender Document for Construction of Compound Wall, Pathway and Security Building & Refurbishment of Existing Signage Tower at BRBNMPL, Bengaluru

निविदा सं. 008/CO/OT/2021-22 दिनांक December 31, 2021

Tender No: 008/CO/OT/2021-22 dated December 31, 2021

[Supplier/Bidders shall fill the following format and submit along with bid]

1. It is confirmed that I/We shall carry out the works as per Technical specification and tender conditions. Necessary MSDS and test certificates for desired materials shall be submitted along with bills.
2. I /we, also confirm that No material without conforming to the Specifications in the Contract will be used for the Works without prior written approval and instruction of the BRBNMPL Officers in charge.

भाग / Section IX: योग्यता / अर्हता के मापदंड / Qualification / Eligibility Criteria

Part-I: Technical Bid Criteria

1. The bidder should be currently in similar business and in sound financial condition.
2. Financial Soundness:
 - i. The average annual turnover of the company should be more than ₹ 15.83 Lakhs in the last three years ending 31/03/2021.
 - ii. The Net Worth of the firm should be positive and should not have eroded by more than 30% year on year in the last 3 years ending 31/03/2021.

Documents to be submitted in support of the above criteria.

- i. Audited / Chartered Accountant Certified P & L Account and Balance sheet for the FY 2018-19, FY 2019-20 and FY 2020-21 & IT returns as applicable.
 - ii. CA certified turnover as per the format enclosed at Annexure A – Proforma for financial certificate.
3. Experience & Past Performance:

Minimum Qualification: The bidder should have executed similar works ending last date of the previous month in which the tender is floated

Minimum value of similar works during last 7 years ending last day of the month previous to the one in which tenders are invited as per either of the following:

Three similarly completed works each costing not less than the amount of value of 40% of estimated value **(i.e., ₹ 21.10 lakhs)**

OR

Two similarly completed works each costing not less than the amount of value of 50% of estimated value **(i.e., ₹ 26.38 lakhs)**

OR

One similarly completed works each costing not less than the amount of value of 80% of estimated value **(i.e., ₹ 42.20 lakhs)**

Relaxation of norms with regard to prior turnover and prior experience for all Class I and Class II Local Suppliers (Under Make In India), MSEs and Start-ups [whether MSEs or otherwise] subject to meeting of quality and technical specifications.

Note: Similar type of work means construction / modification / restoration / civil works, etc., Sub Contracted works will not be considered.

Documentary proof (copies of PO's executed and Work completion certificate) for the above qualifying criterion should be submitted along duly signed by authorized signatory of your company.

4. General Criteria:
 - a. Proof of Registration with GST, and PAN.
 - b. The declaration having not blacklisted by BRBNMPL / Government of India / Public Sector Undertakings and Confidentiality Statement, shall be signed and submitted as part of Technical Bid.
 - c. The Contractor should have GST, PAN, ESI, PF Account numbers, labour license and proof of the same is to be attached with the tender during its submission.

All the above certificates / documents shall be duly signed with seal by the Authorized person of the firm.

Bidder to furnish stipulated documents in support of fulfilment of qualifying criteria. Non-submission or incomplete submission of documents may lead to rejection of offer.

5. Bidder shall submit the following declarations / undertakings along with tender application.
 - a. The signatory is competent and legally authorized to submit the tender and / or to enter into legally binding contract.
 - b. Undertaking that the bidder is accepting all the terms and conditions of this tender and abides by it without any counter conditions
 - c. Undertaking that the information given in the documents is correct and the Bidder is aware that any information provided is found to be false at a later stage BRBNMPL reserves the right to reject / disqualify the Bidder at any stage of the tendering process without assigning any reason.

भाग / Section X: निविदा प्रारूप / Tender Form

Date:

To,
The General Manager,
Corporate Office,
BRBNMPL,
Bengaluru 29

Ref: Your Tender Enquiry No: निविदा सं. 008/CO/OT/2021-22 दिनांक December 31, 2021 /
Tender No: 008/CO/OT/2021-22 dated December 31, 2021 for the work of Tender
Document for Construction of Compound Wall, Pathway and Security Building &
Refurbishment of Existing Signage Tower at BRBNMPL, Bengaluru

We, the undersigned have examined the above mentioned tender enquiry document, including amendment No. -----, dated _____ (if any), the receipt of which is hereby confirmed. We now offer to supply and deliver '**Construction of Compound Wall, Pathway and Security Building & Refurbishment of Existing Signage Tower at BRBNMPL, Bengaluru**' in conformity with your above referred document for the sum of as mentioned in financial bid attached herewith and made part of this tender.

If our tender is accepted, we undertake to supply the goods and perform the services as mentioned above, in accordance with the delivery schedule specified in the List of Requirements.

We further confirm that, if our tender is accepted, we shall provide you with a performance security of required amount in an acceptable form in terms of GCC clause 6, read with modification, if any, in Section V — "Special Conditions of Contract", for due performance of the contract.

We agree to keep our tender valid for acceptance for a period upto as required in the GIT clause 19, read with modification, if any in Section-III — "Special Instructions to Tenderers" or for subsequently extended period, if any, agreed to by us. We also accordingly confirm to abide by this tender upto the aforesaid period and this tender may be accepted any time before the expiry of the aforesaid period. We further confirm that, until a formal contract is executed, this tender read with your written acceptance thereof within the aforesaid period shall constitute a binding contract between us.

We further understand that you are not bound to accept the lowest or any tender you may receive against your above-referred tender enquiry.

Dated this _____ day of _____
For & on behalf of

(Signature with date)
(Name and designation)

Duly authorized to sign tender for and on behalf of

Thanking you.
Yours faithfully,

Seal

Signature with date Name:

अनुभाग / Section XI: कीमत अनुसूची / Price Schedule

**Proforma of Price Bid cum for Construction of Compound Wall, Pathway and Security Building & Refurbishment of Existing Signage Tower at BRBNMPL, Bengaluru
(NON-SPLITABLE)**

प्रेषक/ From:

सेवा में / To

महाप्रबंधक / The General Manager,

बीआरबीएनएमपीएल / BRBNMPL,

बैंगलूरु / Bengaluru – 560029

प्रिय महोदय / Dear Sir,

SUB: Tender Notice for Construction of Compound Wall, Pathway and Security Building & Refurbishment of Existing Signage Tower at BRBNMPL, Bengaluru

संदर्भ / REF: आपकी निविदा इनक्वाइरी सं। / Your Tender Enquiry No: 008/CO/OT/2021-22 dated December 31, 2021

We received your tender enquiry cited and we are pleased to submit the following as our price bid for your kind consideration.

Item wise Price bid:

Bill of quantities and scope of work:

Sl No.	Description of item	Unit	Qty	Rate (₹)	Amount (₹)
1	Earthwork in excavation of foundation of structures as per drawing & technical specification including setting out, construction of shoring & bracing ,De-Watering, removal of stumps & other deleterious matter, dressing of sides & bottom, backfilling the excavated earth to the extent required & utilising the remaining earth locally for the work in all types of soil / soft rock / ordinary rock by Mechanical means (depth upto 3 m) with all lead and lifts, loading and unloading charges, transportation cost, all other incidental charges etc. including bailing out water where required, cost of all materials and labour, HOM of machineries and equipment's etc., complete for successful completion of work as per specifications as directed by the Engineer-in-Charge	cum	177.00		
2	Carefully dismantling of the existing compound wall (masonry / concrete / steel struts, grill, railings / gates / sheeting /	LS	1.00		

	etc.) and handing over the salvageable materials to BRBNMPL				
3	Providing and Laying in position plain cement concrete of mix M10 - 75mm thick of mix 1:3:6 with OPC Cement @ 220kgs, with 20mm and downsize grade granite metal coarse aggregate @ 0.84 cum and fine aggregates @ 0.56 cum, machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted , in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	28.00		
4	Providing and Laying in position reinforced Cement Concrete of Design Mix M25 with OPC cement @ 340kg with 20mm & downsize graded granite metal coarse aggregates @ 0.70 cum and fine aggregates @ 0.47 cum, with super plasticisers @ 3 Litres confirming to IS 9103 - 1999 reaffirmed - 2008, machine mixed, concrete laid in layers not exceeding 15cm thick, vibrated for all works in foundation for Footings, Pedestals, Retaining walls, walls (any thickness) including attached pilasters, column pillars, post, struts, buttresses, bed blocks, anchor blocks, plinths beams, grade slabs etc., including cost of all materials, Labours, HOM of Machinery, curing, complete but excluding cost of steel & fabrication charges)	cum	27.00		
5	Providing and Laying in position reinforced Cement Concrete of Design Mix M25 with OPC cement @ 340kg with 20mm & downsize graded granite metal coarse aggregates @ 0.70 cum and fine aggregates @ 0.47 cum, with super plasticisers @ 3 Litres confirming to IS 9103 - 1999 reaffirmed - 2008 , machine mixed, concrete laid in layers not exceeding 15cm thick, vibrated for all works in ground floor level for roof slabs, Chajja Slabs, Chajja Beams, staircases, lintels and beams, retaining walls, return walls, walls (any thickness) including attached pilasters, columns, lintels, Chajjas, pillars,posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, Labours, HOM of Machinery, curing, complete but excluding cost of steel & fabrication charges)	cum	67.00		
6	Providing and removing centering, shuttering, strutting, propping etc, and removal of form work for FOUNDATIONS, FOOTINGS,RAFTS, PEDESTALS for mass concrete including cost of all materials, labour complete as per specifications	sqm	72.00		
7	Form Work				

a	Providing and erecting Formwork for RCC Compound Wall with plywood lining, of all shapes and sizes, at all levels & heights, providing grooves of various shapes and sizes including scaffolding, releasing & removing the formwork, etc; complete as per specifications.	sqm	850.00		
b	Extra rate for providing form finished exposed concrete using 12mm thick marine plywood or Equivalent Plywood shuttering to the Required Pattern NOTE:- The areas for the shuttering works to be executed for exposed concrete shall be clearly identified / defined by the Architects for which those areas only will be executed by the contractor and only those areas shall be measured and paid.	sqm	685.00		
c	Providing and removing necessary centering, shuttering, strutting, propping etc, and removal of formwork for sides and soffits of BEAMS, beam haunchings, cantilever girders, bressumers, LINTELS, CHAJJA BEAMS not exceeding one meter in depth including cost of all materials, labour complete as per specifications.	sqm	7.00		
d	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, ROOFS, LANDINGS, BALCONIES, CHAJJA SLABS and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications.	sqm	6.00		
8	Providing Thermo-mechanically treated (T.M.T) Bars Fe-500 grade steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire of approved quality and anchoring to the adjoining members wherever necessary complete for successful completion of work as per design (laps, hooks and wastage shall not be measured and paid) including cost of materials, labour, HOM of machinery with all leads & lifts, loading and unloading charges, transportation cost and conveyance and all other incidental charges complete for successful completion of work as per specifications and as directed by the Engineer-in-charge.	MT	12.00		

9	Providing straightening, fabricating and fixing in position structural steel work using MS rolled sections like flats, plates, angles, checkered plates, etc; including cutting, welding to the required shape and size and embedding or welding it on side of the Vertical RCC Compound Wall and fixing the Flats on to the side plates of size 50mm x 10mm Flats @ 1.2m c/c and MS Plates with all necessary arrangements to fix the the Barbed wire / concertina coil for fencing, etc complete, as per the detailed drgs, including staging, scaffolding at all levels and heights and painting with two coats of approved brand and colour of synthetic enamel paint over a coat of primer and Anodic Coating through the process of hot dip spray galvanising 100- 150 microns at 450 degree temperature which shall include the dipping process, De-Greasing and removing of corrosion with 7 tank process etc. compete as per detailed specifications.. Only standard weights as per IS code shall be considered for measurement and payment.	MT	1.00		
10	Providing and Fixing galvanized steel concertina coil fencing of 450 mm dia including drawing through the fencing posts or fixing to the clips provided or binding to the posts with binding wires of required strength including stretching the coil tight.	RMT	180.00		
11	Providing and Fixing GI two strand barbed wire - 12 gauge wire for fencing including drawing through holes in the fencing posts or fixing to the clips provided or binding to the posts with binding wires of required strength including stretching the wires tight.	RMT	1,260.00		
12	Providing precast M20 RCC coping of top width 170 mm and 40 mm high including providing drip mould, fixing in position in CM 1:4, etc complete as per drawing. If the sectional area is changed, rate will be revised proportionately.	RMT	130.00		
13	Supplying, Fabricating and Fixing MS Opening gate made out of MS Flats, MS angles, tubular box sections as per detailed drawing including cutting, bending, fabricating, welding and fixing in position with necessary hold fasts. pivots, hinges, heavy duty rollers, and locking arrangements, aldrops, etc complete as per drawing including two coats of synthetic enamel paint over a coat of primer. (Assume 60kg/Sqm)	sqm	17.00		

14	Providing, fabricating and fixing sliding folding gate of approved make made out of tubular section, MS Flats, MS Plates, angles etc assembled with bottom roller with bearing ,supporting nylon guide roller etc including cutting, bending, fabricating, welding and fixing in position with necessary hold fasts. pivots, hinges, heavy duty rollers, and locking arrangements, aldrops, etc complete as per drawing including two coats of synthetic enamel paint over a coat of primer. (Assume 60kg/Sqm)	sqm	12.00		
15	Supply and fixing of Sliding Gate of approved make made out of hollow tubular section, flats etc all as per drawing assembled with bottom track and guide made of ISMC MS rods, roller, bearing, supporting nylon guide roller etc for manual operations with required length of M.S.Rack & Pinion & operated with push button switch with all necessary MS supports, etc. including two coats of synthetic enamel paint over a coat of primer.. (Assume 60kg/Sqm)	sqm	25.00		
16	Motorising the Sliding Gate: Supplying, installation, testing & commissioning Sliding gate motar using Single phase 220v motar 50Hz of 400 watts self locking and reversible electro mechanical geared motar housed in water proof alum: die cast body having disengaging mechanism for manual operation with Inbuilt control unit. End Limits switches are fitted at the gate ends to limit the gate movements. make: Beninca (Made in Italy) / or equivalent, 1000kg, Specification: Input power : 230V AC, ThrustL 1000N, Opening / closing speed: 10 mtr/min, protection level: IP44, Duty Cycle: 40%. The Italian make gear rack is welded on gate to its full length. Motar stand of suitable height is fabricated out of 50x5mm MS angle to mount the motar assembly, The Rate to include for providing remote transitter, safety photocell sensor, Industrial push button.	sqm	2.00		
17	Providing and injecting chemical emulsion for Preconstructional Anti-Termite Treatment, creating continuous chemical barrier under and around the column pits, walls, trenches, basement excavation, top surface of the plinth filling, junction of wall and floor, along the external perimeter of building, expansion joints, over the top surface of consolidated earth on which apron is to be laid, surrounding of pipes and conduits, with chloropyriphos emulsifiable concentrates of 20% concentration, including cost of chemical, diluting in water to one per cent concentration, including cost of all	sqm	6.00		

	materials, labour, HOM of machinery, with all leads and lifts, loading and unloading charges, transportation cost and conveyance and all other incidental charges etc complete for successful completion of work as per specifications and as directed by Engineering in charge. (Plinth area of the building at ground floor only shall be measured)The contractor to furnish necessary certificate for 10 year warranty.				
18	Providing and construction Solid Cement Concrete Block masonry in cement mortar 1:6 using factory made, load bearing, approved quality, as per IS 2185 (Part 1), density of blocks not less than 1800kg/cum, ith a minimum crushing strength of 35 Kgs/sqcm , set to level plumb including setting in position, providing scaffolding, curing, raking out joints wherever necessary etc., complete with all leads and all as per specification and direction of engineer-in -charge For Construction of Steps and as directed by architects.	cum	0.10		
19	Providing and constructing granite / trap/basalt size stone masonry in FOUNDATION with cement mortar 1:6, edges of stones hammer dressed in courses not less than 20 cms high, bond stones at 2m apart in each course including the cost of all materials, labour, curing, HOM of equipment's and machineries, with all leads and lifts loading and unloading charges, transportation cost and conveyance all other incidental charges etc. complete for successful completion of work as per specifications and as directed by the Engineer-in-charge.	cum	5.00		
20	Providing and fixing 10mm thick glass to glass joined clear toughened glass for Glazed Curtain wall fixed over U channels at bottom and top. Rate to include the sealant to be applied for the glass joints and for the channels. All edges of the glass to be polished etc complete as per detailed drawings.	sqm	14.00		
21	Providing and Fixing Single Shutter glass door of 12mm thick plain toughned glass. The Door is fixed by using any approved make hardware fitting like patch fitting, pivot, floor machine, locking arrangements and suitable SS door rails with floral glass etching for 1/3 portion of door area etc complete. The Rate includes cost of all materials, labour, hire of tools & machineries and as per specification.	sqm	2.00		

22	Providing & laying 18mm to 20mm thk Leather finish Black Granite slabs for flooring & Skirting approved size machine cut slabs laid in pattern as directed over a bed mortar 20mm thk in CM 1:4 including cement paste backing, pointing, curing, cleaning and protecting the floor with POP/bubble board,etc, complete (Basic Price Rs. 235/Sqft Excluding GST)	sqm	6.00		
23	Providing & laying 18mm to 20mm thk Leather Finish Black Granite for Staircase, Steps Treads, Risers & Skirting set over a bed of 20 mm thick in CM 1:4, including providing nosing edges chamfered / rounded and edge flamed, 10mmx20mm grooves to be provided in risers Including curing cleaning, protecting with POP/bubble board as directed by the Architects with anti-skid grooves wherever necessary or as directed, etc. complete as shown in the drawing.(Basic Price Rs. 235/Sqft Excluding GST)	sqm	1.00		
24	For Terrace: Providing and applying two coats of Brushbond RFX of acrylic polymer modified cementitious waterproof coating with Food grade certification over prepared surface. Removing all surface laitance and contamination free from loose aggregate or other sharp protrusions with fairly smooth finish by wire brush and grinding method and surface shall be damped with Water for application of Brushbond RFX waterproof coating. Brushbond RFX shall contain a liquid polymer component and a cementitious powder component, which shall be mixed as per manufacturer's instructions and applied over prepared concrete surface strictly maintaining the coverage specified by the manufacturer. The applied material of Brushbond RFX should have a Pull off adhesion of greater than 1N/mm ² as per ASTM-D4541 and static crack accommodation of 1mm according to ASTM-C836. Complete as per the vendors methodology approved by consultants / clients. all detail as per manufacturers specification M/s. Fosroc or Equivalent , Pedilite, BASF.	sqm	6.00		

25	<p>Providing and laying integral cement based waterproofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc., consisting of following application:</p> <p>a)Applying and grouting a slurry coat of neat cement using 2.75 kgs/sqm of cement admixed with proprietary water proofing compound conforming to I.S. 2645 over the RCC slab after clearing the surface before treatment.</p> <p>b)Laying cement concrete using broken brick bats 25mm to 100mm size with 50% of cement mortar 1:5 admixed with proprietary water proofing compound to required slope and treating similarly the adjoining walls upto 300mm height including rounding off junctions of walls and slabs.</p> <p>c)After two days of proper curing, applying a second coat of cement slurry admixed with proprietary water proofing compound</p> <p>d) Finishing the surface with 20mm thick jointless cement mortar of mix 1:4 admixed with proprietary water proofing compound and finally finishing the surface with trowl and neat cement slurry and making of 300x300mm square.</p> <p>e)The whole terrace so finished shall be flooded with water for a minimum period of two weeks for curing and for final test including cost of materials,labour complete as per specifications</p>	sqm	6.00		
26	Removing carefully the existing Stainless steel logo fixed on the Stone cladding tower, repairing the damaged Logo, alphabets & numerals, polishing and refixing it on the newly cladded granite tower, including grouting, grinding, welding, polishing, staging & scaffolding etc complete as per detailed drawing	LS	1.00		
27	Removal of existing granite cladding, coping including mortar, labour, staging, tools & tackles etc., complete as per specifications. The dismantled granite to be handled with care and stacked in the area as per the instructions of the client & debris to be cleared off the site at dumped at a place as acceptable to the concerned government authorities in accordance with their rules and regulations	sqm	20.00		
28	Providing and laying 18 to 20 mm thk Leather Finish Black Granite for Signage wall Cladding (Wet cladding) of approved sizes and pattern with necessary grooves and polishing of all exposed edges etc, required over a backing of cement mortar 1:3, 12 mm thick including pointing with matching colour cement to match the colour of slab etc. complete as per specifications and as directed by the	sqm	20.00		

	architects at all levels. (Basic Price of the granite - Rs 250/Sft including GST)				
29	Providing & fixing 600mm height Stainless Steel logo with Alphabets, Numerical with 25mm depth of SS 304 grade as per design & drawing. The rate to include grouting, grinding, welding, staging, polishing to approved finish as per architect's selection complete etc.	LS	1.00		
30	Earthwork in excavation of foundation of structures as per drawing & technical specification including setting out, construction of shoring & bracing ,De-Watering, removal of stumps & other deleterious matter, dressing of sides & bottom, backfilling the excavated earth to the extent required & utilising the remaining earth locally for the work in all types of soil by Mechanical means (depth upto 3 m) with all lead and lifts, loading and unloading charges, transportation cost and conveyance upto 1.00 KM Lead, all other incidental charges etc including bailing out water where required, cost of all materials and labour, HOM of machineries and equipment's etc., complete for successful completion of work as per specifications as directed by the Engineer-in-Charge.	cum	60.00		
31	Providing and constructing 200mm thick Walls with Solid Cement Concrete Blocks conforming to IS 2185 with a mini-mum crushing strength of 35 Kgs/sqcm in cement mortar 1:4, in superstructure at all levels and heights including all necessary Staging and Scaffolding complete as per specifications. (Size of the Block is 400x200x200mm)	sqm	98.00		
32	Providing 15mm thick cement plaster in single coat with cement mortar 1:3 to concrete surfaces including providing and mixing water proofing compound at one Kg per bag or in the proportion recommended by the manufacturers rounding off corners wherever required, finish as directed, providing and removing scaffolding, including cost of all materials, labour, curing, HOM of equipment and machineries, leads and lifts at all levels, Loading and unloading charges, transportation cost and conveyance , all other incidental charges etc., complete for successful completion of work all as per specifications and as directed by the Engineer-in-charge.	sqm	140.00		
33	Preparation of sub-grade by excavating earth in all soils including hard soils, upto an average 30 cms depth dressing to camber & consolidating with 8/10 ton road roller, including making good undulations, etc. & disposing the surplus earth within	cum	68.00		

	the site upto a maximum lead of 150 metres as directed.				
34	Providing and laying 150mm consolidated thickness of wet mix macadam laid in single layer using 40-63mm stone aggregates and quarry dust mix, mixed in the ratio of 1:1. The rate to include mixing coarse aggregates and quarry dust spreading, levelling watering, rolling and consolidation with 8-10 ton road roller to the required levels, as per detailed drawings, etc. complete.	cum	25.00		
35	Providing and laying 150mm consolidated thickness of wet mix macadam laid in single layer using 40mm and down size stone aggregates and quarry dust mix, mixed in the ratio of 1:1. The rate to include mixing coarse aggregates and quarry dust spreading, levelling watering, rolling and consolidation with 8-10 ton road roller to the required levels, as per detailed drawings, etc. complete.	cum	25.00		
36	Providing & laying square paver blocks (shot blasted) of size 150 x 150 mm, 60mm thk set in 50 mm thick sand bed of "Basant Beton" or appvd make equivalent type of Grey colour as per manufacturer's specification.	sqm	150.00		
37	Providing 50 mm thick RCC precast slab with cement concrete 1:2:4 using coarse graded aggregate 12.5 mm and down size. The work includes necessary casting platform, shuttering, finishing smooth with cement mortar 1:4, on exposed faces, curing, transporting to work site, hoisting and fixing in position and finishing complete excluding cost of reinforcement steel.	sqm	40.00		
38	M.S Grating: Providing straightening, fabricating and fixing in position structural steel work using MS rolled sections like angles, channels, flats, plates including checkered plates, rounds, etc; including cutting, welding for Gratings including painting with two coats of approved brand and color synthetic enamel paint over a coat of primer. Only standard weights as per IS code shall be considered for measurement and payment.	Kgs	1,250.00		
	Total				
	GST @ 18%				
	Grand Total				
	Grand Total in Words -				

NOTE:

1. The rates quoted are with all awareness of the site conditions and after going through the tender documents in details.

2. *We confirm that the quoted price is inclusive of all statutory levies, GST, duties, packing, forwarding, freight, handling, loading, unloading & insurance charges for services offered and is firm.*
3. *We confirm that there would not be any price escalation during the tenure of contract.*
4. *Payment will be made as per the actual work carried out.*
5. *We confirm that we will abide by all the tender terms & conditions of tender, scope of work and we do not have any counter conditions.*
6. *We confirm that tendered item will be supplied as per specifications and tender conditions*
7. *The tender will be decided on the overall lowest L1 basis and after considering purchase preference policy for MSE's as mentioned at Section-III of this tender and then Contract will be awarded accordingly.*

Thanking you,

Yours faithfully,

(.....)
Name & Signature with date

Seal

Firm:

भाग / Section XII: प्रश्नावली / जांच सूची / Questionnaire / Checklist

The Tenderer should furnish specific answers to all the questions/ issues mentioned below. In case a question / issue does not apply to a tenderer, the same should be answered with the remark – not applicable". Wherever necessary and applicable, the tenderer shall enclose certified copy as documentary proof/ evidence to substantiate the corresponding statement.

In case a tenderer furnishes a wrong or evasive answer against any of the under mentioned question / issues, its tender will be liable to be ignored.

Sl No	Item Description	Yes/ No	Deviation /Remarks
01	Brief description of goods and services offered as per tender and scope of work		
02	Name and Address of the Firm		
03	Nature of the Firm: (Proprietorship/Partnership/Ltd. Company/Co-op. Society)		
04	Offer is valid for acceptance up to 120 days after opening of tender		
05	A copy of Permanent Income Tax A/ C No (PAN) card attached (Please attach certified copy of your latest/ current Income Tax clearance certificate issued by the above authority)		
06	A copy of GST Registration Certificate attached		
07	Status: 1. Are you currently registered with the Central Purchase Organization, and/or as a Micro and Small Enterprise (MSE) as defined in MSEs Order 2012 issued by Ministry of Micro, Small and Medium Enterprises (MSME), and/or as a Startup as recognised by Department for Promotion of Industry and Internal Trade (DPIIT) and/or the present BRBNMPL and/or the Directorate of Industries of the concerned State Government for the goods quoted? If so, indicate the date up to which you are registered and whether there is any monetary limit imposed on your registration. 2. Are you currently registered under the Indian Companies Act, 2013 or any other similar Act? Please attach certified copy(s) of your registration status etc. in case your answer(s) to above queries is in affirmative.		
08	Please indicate name & full address of your Banker(s)		
09	Please state whether business dealings with you currently stand suspended/ banned by BRBNMPL/any Ministry / Dept. of Government of India or by any State Govt.		

.....
(Signature with date)

(Full name, designation & address of the person duly authorized sign on behalf of the tenderer)

For and on behalf of

.....

(Name, address and stamp of the tendering firm)

भाग / Section XIV: निर्माता का प्राधिकृति फॉर्म / Manufacturer's Authorization Form

सेवा में / To

महाप्रबंधक / The General Manager,

बीआरबीएनएमपीएल / BRBNMPL,

बैंगलूरु / Bengaluru – 560029

प्रिय महोदय / Dear Sir,

संदर्भ / **REF:** आपकी निविदा इनक्वाइरी सं। / Your Tender Enquiry No: निविदा सं. / 008/CO/OT/2021-22 dated December 31, 2021

We,, who are proven and reputable manufacturers of (name and description of the goods offered in the tender) having factories at hereby authorise Messrs (name and address of the authorized dealer/distributor/representative) to submit a tender, process the same further and enter into a contract with you against your requirement as contained in the above referred tender enquiry documents for the above goods manufactured by us.

We further confirm that no supplier or firm or individual other than Messrs. (name and address of the above authorized dealer/distributor/representative) is authorized to submit a tender, process the same further and enter into a contract with you against your requirement as contained in the above referred tender enquiry documents for the above goods manufactured by us.

We also hereby extend our full warranty, as applicable as per clause 16 of the General Conditions of Contract read with modification, if any, in the Special Conditions of Contract for the goods and services offered for supply by the above firm against this tender document and also undertake to abide by other tender terms and conditions.

Yours faithfully,

.....

.....

[signature with date, name and designation]

for and on behalf of Messrs

(name & address of the manufacturers]

Note: This letter of authorization should be on the letter head of the manufacturing firm and should be signed by a person competent and having the power of attorney to legally bind the manufacturer

भाग /SECTION XV: निष्पादन सुरक्षा के लिए बैंक गारंटी फॉर्म / SECTION XV: Bank Guarantee
Form for Performance Security

_____[Insert Bank 's Name, and Address of Issuing Branch or Office]
Beneficiary (**BHARATIYA RESERVE BANK NOTE MUDRAN PRIVATE LIMITED,**

Date: -----

Performance Guarantee No.

WHEREAS (name and address of the Contractor) (hereinafter called "the Contractor") has undertaken, in pursuance of contract no dated to construction (.....) (description of goods and services) (herein after called "the contract").

AND WHEREAS it has been stipulated by you in the said contract that the Contractor shall furnish you with a bank guarantee by a scheduled commercial bank recognized by you for the sum specified therein as security for compliance with its obligations in accordance with the contract:

AND WHEREAS we have agreed to give the Contractor such a bank guarantee;

NOW THEREFORE we hereby affirm that we are guarantors and responsible to you, on behalf of the Contractor, up to a total of (amount of the guarantee in words and figures), and we undertake to pay you, upon your first written demand declaring the Contractor to be in default under the contract and without cavil or argument, any sum or sums within the limits of (amount of guarantee) as aforesaid, without your needing to prove or to show grounds or reasons for your demand or the sum specified therein.

We hereby waive the necessity of your demanding me said debt from the Contractor before presenting us with the demand. We further agree that no change or addition to or other modification of the terms of the contract to be performed thereunder or of any of the contract documents which may be made between you and the Contractor shall in any way release us from any liability under this guarantee and we hereby waive notice of any such change, addition or modification.

We undertake to pay BRBNMPL up to the above amount upon receipt of its first written demand, without BRBNMPL having to substantiate its demand.

This guarantee will remain in force for a period of sixty days after the after the completion of all contractual obligations and any demand in respect thereof should reach the Bank not later than the above date.

(Signature of the authorized officer of the Bank)

Name and designation of the officer

Seal, name & address of the Bank and address of the Branch

Name and designation of the officer

Seal, name & address of the Bank and address of the Branch

भाग /Section XVI: संविदा फॉर्म/ Contract Form

(Address of BRBNMPL's office issuing the contract)

Contract No dated.....

This is in continuation to this office' Notification of Award No. dated

1. Name & address of the Contractor:
2. BRBNMPL's Tender document No. dated and subsequent Amendment No. dated (if any), issued by BRBNMPL
3. Contractor 's Tender No. dated and subsequent communication(s) No..... dated (If any), exchanged between the contractor and BRBNMPL in connection with this tender
4. In addition to this Contract Form, the following documents etc, which are included in the documents mentioned under paragraphs 2 and 3 above, shall also be deemed to form and be read and construed as part of this contract:
 - a. General Conditions of Contract;
 - b. Special Conditions of Contract;
 - c. List of Requirements;
 - d. Technical Specifications;
 - e. Quality Control Requirements;
 - f. Tender Form furnished by the supplier;
 - g. Price Schedule(s) furnished by the supplier in its tender;
 - h. Manufacturers' Authorisation Form (if applicable for this tender);
 - i. BRBNMPL's Notification of Award

Note: The words and expressions used in this contract shall have the same meanings as are respectively assigned to them in the conditions of contract referred to above. Further, the definitions and abbreviations incorporated under Section - V - 'General Conditions of Contract' of BRBNMPL's Tender document shall also apply to this contract.

5. Some terms, conditions, stipulations etc. out of the above-referred documents are reproduced below for ready reference:
 - a. Brief particulars of the goods and services which shall be supplied / provided by the supplier are as under:

Schedule No.	Brief description of goods / services	Accounting unit	Quantity to be supplied	Unit Price (In Rs.)	Total price
--------------	---------------------------------------	-----------------	-------------------------	---------------------	-------------

Any other additional services (if applicable) and cost thereof:

- i. Total value (in figure) (In words)
- ii. Delivery schedule
- iii. Details of Performance Security
- iv. Quality Control
 - a. Mode(s), stage(s) and place(s) of conducting inspections and tests.
 - b. Designation and address of BRBNMPL's inspecting officer
- v. Destination and dispatch instructions
- vi. Consignee, including port consignee, if any
- vii. Warranty clause
- viii. Payment terms
- ix. Paying authority

.....

(Signature, name and address of BRBNMPL's authorized official) For and on behalf of
Received and accepted this contract

(Signature, name and address of the supplier's executive duly authorized to sign on behalf of the supplier)
For and on behalf of

(Name and address of the supplier)

.....

(Seal of the supplier)

Date:

Place:

भाग /Section XVII: बोली खोलने के लिए उपस्थित होने का प्राधिकृति पत्र / Letter of Authority for attending a Bid Opening

(Refer to clause 24.2 of GIT)

The General Manager

Unit Address

Subject: Authorization for attending bid opening on _____ (date) in the Tender of _____

Following persons are hereby authorized to attend the bid opening for the tender mentioned above on behalf of _____ (Bidder) in order of preference given below:

Order of Preference	Name	Specimen Signatures
I.		
II.		
Alternate Representative		
Signature of Bidder or Officer authorized to sign the bid Documents on behalf of the bidder		

Note:

1. Maximum of two representatives will be permitted to attend bid opening. In cases where it is restricted to one, first preference will be allowed. Alternate representative will be permitted when regular representatives are not able to attend.
2. Permission for entry to the hall where bids are opened may be refused in case authorization as prescribed above is not produced.

Signature and Stamp of
Bidder

Date: / /2021

(To be submitted by contractor's on their letter Head)

भाग / Section XIX: भुगतान के लिए प्रोफॉर्मा / Proforma of Bills for Payment

Name and Address of the Firm:

Bill No: Dated :.....

To:
The General Manager
Corporate Office,
B.R.B.N.M.P.L,
Bengaluru 560029

Invoice / Bill No. & Date	
PAN No.	
TIN No.	
VAT No.	
GST No.	

Sub: Submission of Bill for payment

Si. No.	Work Order No: & Date	Item Description	Quantity	Rate (₹)	Amount	Amount in Words
1						
Total (Including all taxes) - A separate Detail measurement sheet is to be attached along with this bill.						
2.	Work order amount: ₹					
3	Type of bill:					
4	Area of work:					
5	Starting date of work :					
6	Schedule date of completion:					
7	Actual date of completion:					
8	Reasons for delay:					
11	Liquidated damage (if any) : (For any delay beyond specified schedule time period)					
12	DLP Period:					
13	EMD :					
14	Security Deposit:					
15	Any other details/Remarks:					

I hereby certify that the payment being claimed is strictly in terms of the contract and all the obligations on the part of the supplier for claiming that payment has been fulfilled as required under the contract.

Signature and Stamp of Contractor

संलग्नक / Annexure – 'A': वित्तीय टर्नओवर प्रमाणपत्र का प्रोफॉर्मा / Proforma of Financial Turnover Certificate

(To be issued by practicing Chartered Accountant with membership No. on the letter head)

Certificate

To whom so ever concern

Dear Sir,

Sub: Certificate for turnover and others as per tender conditions.

This is to certify that M/s. _____ (Agency Name & Address) are in the business of contracts execution for last 03 completed years (considered up to 31st March 2020 of last financial year). Their performance report as required under tender conditions for the last 3 years is as follows.

Financial Years	Annual Turnover	Net worth as on year end
2018-19		
2019-20		
2020-21		
Total		

The above information is based on the audited accounts

Place:

Date:

Seal:

Signature of the CA with Membership No.

NATIONAL ELECTRONIC FUND TRANSFER (NEFT) Mandate Form

(Investor / customer's option to receive payments through Credit Clearing Mechanism)
Name of the Scheme and the periodicity of payment

1	Investor / Customer's Name	
2	Particulars of Bank account	
	A Name of the Bank	
	B Name of the branch	
	Address	
	Telephone No	
	Whether Bank branch is NEFT enabled	
C	Code number of the bank and branch appearing on the MICR Cheque issued by the bank	
D	Type of the account (SB, Current or Cash Credit)	
E	Ledger and Ledger Folio number	
F	Account number (as appearing on the Cheque book)	
G	RTGS / IFSC Code No.	
	(In lieu of the bank certificate to be obtained as under, please attach a blank cancelled cheque or photocopy of a cheque or front page of your Savings bank passbook issued by your bank for verification of the above particulars)	
3	Date of effect	

I hereby declare that the particulars given above are correct and complete. If the transaction is delayed or not effected at all for reasons of incomplete or incorrect information, I would not hold the user institution responsible. I have read the option invitation letter and agree to discharge the responsibility expected of me as a participant under the scheme.

(.....)

Signature of the Investor / Customer

Date:

Certified that the particulars furnished above are correct as per our records.

Bank's Stamp

Date:

(.....)

Signature of the authorized official of the Bank

To Whomsoever It May Concern

This is to confirm that we M/s. _____
_____ shall fulfil the Security Deposit formalities as per NIT on
becoming L1.

Dated this _____ day of _____

For & on behalf of

(Seal & signature with date)

(Name and designation)

Duly authorized to sign tender for and on behalf of

(To be submitted on Company letter head duly signed by authorized person)

UNDERTAKING

1) **CONFIDENTIALITY STATEMENT**

"The information, which is contained in this document will not, in whole or in part be reproduced, transferred to other documents/electronic media or disclosed to others without written consent of BRBNMPL". Bidder shall also undertake to maintain secrecy, exclusivity and confidentiality of the high security currency printing environment of BRBNMPL"

2) **BLACKLISTING / DEBARMENT**

"We confirm that that our firm has not been in the list of firms blacklisted / debarred by BRBNMPL / Government of India in the past 5 years ending as on date. We also confirm that there is no Civil and criminal cases and other legal dispute proceedings including arbitration proceedings pending/closed during the last 3 years"

3) **ACCOUNTABILITY STATEMENT**

"In case any ambiguity is noticed in the Documents submitted / information provided is found to be false at any stage, we will be entirely responsible and liable for any action as deemed fit under the Law".

4) **Understanding of the Tender**

"I / We have gone through the terms & conditrons of the tender and accept the same. I / We shall abide by it without any counter conditions".

Yours faithfully,

Authroised Signatory

Name
Signature of Bidder

Seal

Annexure-E**Salient features of revised 'Public Procurement (Preference to Make in India) Order, 2017'**

1. As per the revised Order, suppliers have been classified as 'Class-I local supplier', 'Class-II local supplier' and 'Non-local supplier' as defined below *(para 2 of order)*: -
 - 'Class-I local supplier' - supplier or service provider whose Goods, Services or Works has local content equal to or more than 50% - *shall get purchase preference* provided quoted price falling within margin of price preference i.e. within L1 + 20%
 - 'Class-II local supplier' - supplier or service provider whose Goods, Services or Works has local content more than 20% but less than 50% - *shall not get any purchase preference*
 - 'Non-local supplier' - supplier or service provider whose Goods, Services or Works has local content less than or equal to 20% - *shall not get any purchase preference*
2. Other important definitions *(para 2 of order)*: -
 - 'Local content'- means the amount of value added in India i.e. total value of the item (excluding local taxes) minus the value of import content in the item (including customs duty) as a proportion of the total value of the item, in percent
 - 'Margin of purchase preference' – means the maximum extent to which the price quoted by a 'Class-I local supplier' can be above L1 price for the purpose of purchase preference. The margin of purchase preference shall be 20%
3. Different procurement scenarios in procurement of Goods, Services or Works *(para 3)*: -

S/N	Scenario	Tender Type	Tender value	Eligible bidder	Relaxation
1	There is sufficient local capacity and competition	OTE / NCB	Any value	'Class-I local supplier'	Relaxation (as per para 10 (a) and (b) of order)
2	There isn't sufficient local capacity and competition	OTE / NCB	< ₹200 crore	'Class-I local supplier' 'Class-II local supplier'	Relaxation (as per para 10 (a) and (b) of order)
		GTE / ICB	Any value*	'Class-I local supplier' 'Class-II local supplier' 'Non-local supplier'	Relaxation (as per para 10 (a) and (b) of order) to Class-I and Class-II local suppliers

* For tender value < ₹200 crore, GTE/ICB shall not be issued except with the approval of Competent Authority as per amended Rule 161 (iv) of GFR 2017

4. Procedure for purchase preference to 'Class-I local supplier' applicable for procurement scenario 2 in para 3 above is explained below in brief *(para 3A (b) and (c) of order)*: -
 - i. Procurement of Goods and Works which are *divisible* in nature (e.g. consumables): -
 - If L1 is 'Class-I local supplier' – 100% awarded to L1
 - If L1 is *not* 'Class-I local supplier' – 50% awarded to L1
 - Remaining 50% awarded to lowest bidder among 'Class-I local supplier' falling within L1+20% subject to matching L1 price
 - If unable to match L1 price or accepts less than offered quantity, next lowest 'Class-I local supplier' bidder within L1+20% is invited to match L1 price for remaining quantity and so on and contract will be awarded accordingly
 - If some quantity is left uncovered on 'Class-I local supplier', then such balance quantity can be ordered on the original L1 bidder
 - ii. Procurement of Goods and Works which are *not divisible* in nature (e.g. Varnish Plant) and procurement of Services where bid is evaluated on price alone: -
 - If L1 is 'Class-I local supplier' – 100% awarded to L1
 - If L1 is *not* 'Class-I local supplier'
 - Lowest bidder among 'Class-I local supplier' falling within L1+20% is invited to match L1 price – contract awarded subject to matching L1 price

- If unable to match L1 price, next lowest 'Class-I local supplier' bidder within L1+20% is invited to match L1 price and so on and contract will be awarded accordingly
 - If none of the 'Class-I local supplier' bidder within L1+20% is unable to match L1 price, contract awarded to original L1 bidder
5. Besides above, the bidders have to submit a declaration and undertaking along with their offer as per *Declaration & Undertaking by Micro & Small Scale Enterprises / Start-up Companies / Entities seeking purchase preference under Make In India Policy / Women entrepreneurs / Registration with TReDS/GeM.*

Salient features of 'Public Procurement Policy for Micro and Small Enterprises (MSEs) Order, 2012'

(To be declared upfront in NIT or in any other section of SBD)

CONDITIONS FOR MICRO AND SMALL ENTERPRISES (MSEs)

1. MSEs must be registered with any of the following in order to avail the benefits / preference available under MSEs Order, 2012: -
 - District Industries Centers (DIC)
 - Khadi and Village Industries Commission (KVIC)
 - Khadi and Village Industries Board
 - Coir Board
 - National Small Industries Corporation (NSIC)
 - Directorate of Handicraft and Handloom
 - Any other body specified by Ministry of MSME (MoMSME)
 - Udyog Aadhaar Acknowledgment / Udyog Aadhaar Memorandum issued by MoMSME
2. MSEs participating in the tender must submit valid & authorised copy of certificate of registration with any one of the above agencies. In case of bidders submitting DIC registration certificate, they shall attach original notarised copy of the DIC certificate.
3. The registration certificate issued from any one of the above agencies must be valid as on Bid closing date of the tender. Bidder shall ensure validity of registration certificate in case bid closing date is extended.
4. The MSEs who have applied for registration or renewal of registration with any of the above agencies/bodies, but have not obtained the valid certificate as on closing date of the tender, are not eligible for exemption/preference. Where validity of such certificates such as NSIC certificate has lapsed, it shall be the responsibility of the bidder to seek renewal from the concerned Govt. agency before such expiry. *However, documentary evidence seeking extension before the lapse of validity of such certificate and an authorization letter from the Govt. agency having received application for renewal submitted before the bid closing date shall be accepted.*
5. **Manufacturer for tendered items / Service provider of tendered services:** The MSE bidder must be Manufacturer of tendered items for procurement / Service provider who is capable of rendering the tendered services by themselves to avail the benefits under MSEs Order, 2012. Traders/dealers/resellers/distributors/authorized agents will not be considered for availing benefits under MSEs Order, 2012 as per guidelines issued by MoMSME.
6. The MSEs registered with above mentioned agencies / bodies are exempted from payment of Earnest Money Deposit (EMD) & tender fees.
7. **Relaxation of Norms for Micro & Small Enterprises (MSEs):** Pre-qualification criteria with respect to Prior Turnover and Prior experience may be relaxed for Micro & Small Enterprises as per GOI guidelines subject to meeting of quality and technical specifications.
8. However, there may be circumstances like procurement of items/services related to public safety, health, critical security operations and equipment, etc., wherein BRBNMPL reserves the right to not consider relaxation of Prior Turnover and Prior Experience for Micro and Small Enterprises.
9. Items which are reserved for exclusive purchase from MSEs shall be procured from Micro and Small Enterprises as per Public Procurement Policy.
10. Subject to meeting terms and conditions stated in the tender document, *at least 25%* of the total quantity of the tender is earmarked for MSEs registered with above mentioned agencies / bodies.
11. In case MSE bidder is L1, entire value of the tender is to be ordered on the L1 MSE bidder.
12. In tender, participating MSEs quoting price within price band of L1 + 15% shall also be allowed to supply a portion of requirement by bringing down their price to L1 price in a situation where L1 price is from someone other than a MSE and such MSE shall be allowed to supply at *least 25%* of the total tendered value (where the tender quantity can be split).
13. In case of more than one such MSEs are in the price band of L1 + 15% and matches the L1 price, the supply may be shared proportionately if the job can be split.

14. In case the tendered quantity cannot be split, MSE shall be allowed to supply total tendered quantity provided their quoted price is within a price band of L1 + 15% and they match the L1 price.
15. If the quantity cannot be split and there are more than one eligible MSE bidders (price band within L1+15%) then the opportunity to match the L1 rate of the tender shall be given first to MSE (who have quoted lowest rate among the MSEs within the price band of L1+15%) and the total quantity shall be awarded to him after matching the L1 price of the tender.
16. If the MSE who have quoted lowest rate among the MSEs in the price band of L1 + 15% do not agree to match the rate of L1 of the tender, then the next ranked MSE bidder who has quoted within the price band of L1 + 15% in order shall be given chance to match the rate of L1 for award of the quantity/order.
17. For more clarity in this regard, following table is furnished: -

Type of Tender	Price quoted by MSE	Finalization of tender
Can be Split	L1	Full order on MSE
	Not L1 but within L1+15%	At least 25% order on MSE subject to matching L1 price
Cannot be split	L1	Full Order on MSE
	Not L1 but within L1+15%	Full Order on MSE subject to matching L1 price

18. The purchase preference to MSEs is not applicable for works contracts where supply of goods not produced by MSEs is also involved.
19. **Special provision for MSEs owned by SC & ST entrepreneurs:** Out of the 25% target of annual procurement from MSEs, 4% shall be earmarked for procurement from MSEs owned by SC & ST entrepreneurs. In the event of failure of such MSEs to participate in the tender process or meet the tender requirements and L1 price, 4% sub-target so earmarked shall be met from other MSEs.
20. To qualify for entitlement as SC/ST owned MSE, the SC/ST certificate issued by District Authority in addition to certificate of registration with any one of the agencies mentioned in paragraph 1 above. Alternatively, the bidder shall be responsible to furnish necessary documentary evidence for enabling BRBNMPL to ascertain that the MSE is owned by SC/ST entrepreneurs. MSE owned by SC/ST is defined as:
 - In case of Proprietary MSE, proprietor(s) shall be SC/ST
 - In case of Partnership MSE, the SC/ST partners shall be holding at least 51% shares in the enterprise
 - In case of Private Limited Companies, at least 51% share shall be held by SC/ST promoters
21. **Special provision for MSEs owned by women entrepreneurs:** Out of the 25% target of annual procurement from MSEs, 3% shall be earmarked for procurement from MSEs owned by women entrepreneurs *in addition* to 4% earmarked for MSEs owned by SC/ ST entrepreneurs. MSE owned by Women is defined as:
 - In case of Proprietary MSE, proprietor(s) shall be Women
 - In case of Partnership MSE, the Women partners shall be holding at least 51% shares in the enterprise
 - In case of Private Limited Companies, at least 51% share shall be held by Women promoters
22. Micro & Small Scale Enterprises have to submit a declaration and undertaking along with their offer as per *Declaration & Undertaking by Micro & Small Scale Enterprises / Start-up Companies / Entities seeking purchase preference under Make In India Policy / Women entrepreneurs / Registration with TReDS/GeM.*

CONDITIONS FOR START-UP COMPANIES

1. Subject to meeting of Quality and Technical specifications, BRBNMPL may consider allowing the participation of “Start-up” companies with capability to execute the supply/ services, as per technical specifications / perform the job as per scope of work specified in the tender and subject to meeting extant & relevant guidelines of Government of India. This should be confirmed and substantiated in the technical bid.
2. The bidder who intends to participate as “Start-up” company should enclose the Certificate of Recognition issued by Department for Promotion of Industry and Internal Trade (DPIIT), Ministry of Commerce & Industry, Govt. of India during submission of Technical bid.
3. Start-ups registered with DPIIT are exempted from payment of Earnest Money Deposit (EMD) & tender fees.
4. Prequalification Criteria with respect to Prior Turnover and Prior Experience may be relaxed for Start-ups as per the GOI guidelines.
5. However, there may be circumstances like procurement of items/services related to public safety, health, critical security operations and equipment, etc. wherein BRBNMPL reserves the right to not consider relaxation of Prior Turnover and Prior Experience for Start-up Companies as per GoI guidelines.
6. Start-up Companies who are also registered as MSEs and wish to avail the benefits as applicable to MSE, shall submit relevant documents covered under Conditions for Micro and Small Enterprises elsewhere in this tender.
7. Start-up Companies have to submit a declaration and undertaking along with their offer as per *Declaration & Undertaking by Micro & Small Scale Enterprises / Start-up Companies / Entities seeking purchase preference under Make In India Policy / Women entrepreneurs / Registration with TReDS/ GeM.*

PROCEDURE TO BE ADOPTED WHEN THE BIDDER QUALIFIES AS BOTH MSE AND CLASS-I LOCAL SUPPLIER

The option in case of bidders qualifying under both Policies, namely, Public Procurement Policy for MSEs Order, 2012 (MSEs-2012) and Public Procurement (Preference to Make in India) Order, 2017 (MII-2017) shall be exercised as under:

1. The bidder can avail only one out of the two applicable purchase preference policies, i.e., MSEs-2012 and MII-2017. Therefore, bidder will be required to furnish the option under which he desires to avail purchase preference. This option must be declared within the offer and in case bidder fails to do so although he is eligible under both the Policies, BRBNMPL shall evaluate his offer considering MSEs-2012 as the default chosen option.
2. In case a bidder opts for preference under MSEs-2012, he shall not be eligible to claim benefit under MII-2017 (irrespective of the fact whether he furnishes the details of local content in his offer and the same meets the stipulated local content criteria).
3. In case a bidder opts for purchase preference based on MII-2017, he shall not be entitled to claim benefit of purchase preference as applicable for MSE bidders under MSEs-2012. However, the exemptions from furnishing Bid security (EMD) shall continue to be available to such a bidder.
4. In view of the above,
 - a. The bidder's quoted prices against various items of enquiry shall remain valid even in case of splitting of quantities of the items, except in case of items where the quantity cannot be split since these are to be awarded in a Lot or as a package or Group.
 - b. While evaluating the bids, for price matching opportunities and distribution of quantities among bidders, the order of precedence shall be as under:
 - MSE bidder (MSEs-2012)
 - Class-I local supplier (MII-2017)
5. In case the bidder has not declared his status as to whether he is an MSE Bidder or Class-I local supplier during bid submission, then he will be considered as non MII-2017 compliant bidder and evaluated accordingly. No further correspondence will be made in this regard.

Examples of Purchase Preference:**a. Non divisible item**

L1 bidder is neither MSE nor Class-I local supplier

L2 bidder is Class-I local supplier (within L1 + 20%)

L3 bidder is MSE bidder (within L1 + 15%)

L3 bidder i.e. MSE bidder shall be given preference to match the L1 price. If L3 bidder matches the L1 price, Order shall be placed on him, otherwise, option for matching the L1 price shall be given to L2 bidder (Class-I local supplier)

b. Divisible item

L1 bidder is neither MSE nor Class-I local supplier

L2 bidder is Class-I local supplier (within L1 + 20%)

L3 bidder is MSE bidder (within L1 + 15%)

MSE bidder shall be given preference to match the L1 price. If L3 bidder matches the L1 price, order shall be placed on him for at least 25% of the tendered quantity. For balance quantity (i.e. 50% of tendered quantity/value), option for matching the L1 price shall be given to L2 bidder (Class-I local supplier). Remaining quantity (25%) shall be awarded to natural lowest bidder. For further clarification, in case an item has quantity 4 nos. then 1 no. (25%) can be given to MSE bidder, 2 nos. (50%) to Class-I local supplier and left out 1 no. to natural L1 bidder.

Note:

The above two examples are not applicable to the Works Contracts since MSEs Order, 2012 is not applicable to works contracts.

- In case lowest bidder is a MSE bidder, the entire work shall be awarded to him without resorting to purchase preference to bidders complying under MII-2017.
- In case lowest bidder is a Class-I local supplier, purchase preference shall be resorted to MSE bidder as per provisions specified in the enquiry document w.r.t. MSEs-2012 only.

Annexure- I

(To be in the Company letter head)

Date :.....

Declaration & Undertaking by Micro & Small Scale Enterprises / Start-up Companies / Entities seeking purchase preference under Make In India Policy / Women entrepreneurs / Registration with TReDS/GeM

(To be filled in the Company letter head)

Date:

Sl No	Particulars	Details
1	Is your organization Proprietary / Partnership / Private Limited Company / Public Limited Company / Others
2	Does your organization belong to Micro / Small scale Industry / Start-up / Class-I local supplier / others (Please tick mark appropriate box. Bidders may tick more than one, if eligible)	<input type="checkbox"/> Micro <input type="checkbox"/> Small Scale <input type="checkbox"/> Start-up Company <input type="checkbox"/> Class-I local supplier <input type="checkbox"/> Others
3	In case you belong to Micro / Small Scale Enterprises, whether you are a Manufacturer for the tendered items (supply) / Service Provider for the tendered services (Please tick mark the appropriate box)	<input type="checkbox"/> Manufacturer for supply items <input type="checkbox"/> Service Provider for services <input type="checkbox"/> Trader/dealer/reseller/distributor/ authorized agent <input type="checkbox"/> Non MSE Bidder
4	In case you belong to Micro / Small Scale Enterprises, whether you are registered under SC / ST Category. <i>If yes, valid documentary evidence to be submitted</i> (Please tick mark the appropriate box)	<input type="checkbox"/> Yes <input type="checkbox"/> No If yes, whether <input type="checkbox"/> SC <input type="checkbox"/> ST
5	In case you belong to Micro / Small Scale Enterprises, whether your firm/ organization is owned by Women entrepreneurs? <i>If yes, valid documentary evidence to be submitted</i> (Please tick mark the appropriate box)	<input type="checkbox"/> Yes <input type="checkbox"/> No
	Are your registered under TReDS (Trade Receivable electronic Discounting System approved by RBI) Applicable for Micro, Small and Medium Enterprises (Please tick mark the appropriate box)	<input type="checkbox"/> No <input type="checkbox"/> Yes If yes, whether <input type="checkbox"/> RXIL <input type="checkbox"/> A-Treds <input type="checkbox"/> M1Xchange (Tick agency with whom you are registered along with Regn No.) Regn No.
	Has your firm/organization registered your items/services in Government e-Marketplace (GeM)	<input type="checkbox"/> Yes <input type="checkbox"/> No
	In case you are both a valid MSE bidder and Class-I local supplier (Make in India Policy), please give your preference. (Please tick any one)	<input type="checkbox"/> MSE <input type="checkbox"/> Class-I local supplier
	In case you are claiming benefits under Make in India Policy, whether you are meeting the minimum local content as mentioned in the tender document/ concerned Ministry guidelines/Policy.	<input type="checkbox"/> Yes, Local Content _____ % <input type="checkbox"/> Not applicable for this tender

Sl No	Particulars	Details
	<p>Declaration: I/We hereby declare that the above data submitted are true and back-up documents are attached as proof of the same. In case any submitted data are found to be incorrect/false, my/our bid is liable to be rejected and I/we am/are liable for suitable actions as per relevant BRBNMPL Policy.</p> <p>I/We also understand that in case I/we am/are not claiming benefits under Make in India Policy, or under MSEs Order as per tender requirements, then purchase preference shall apply to other bidders who have quoted accordingly as per policy.</p>	

A. Categorization of MSE/SC-ST & Women Vendors

1. In case of Micro/Small scale Enterprises, kindly attach Registration Certificate issued by DIC/KVIC/KVIB/Coir Board/NSIC/Directorate of Handicrafts and Handlooms, or any other body specified by MSME for authentication such as Udyog Aadhaar Memorandum/ Acknowledgment.
2. SC/ST and Women entrepreneurs registered under MSEs need to submit valid documentary evidence.

B. Categorization of Start-up Companies

Bidder who intends to participate as 'Start-up' company should enclose the Certificate of Recognition issued by Department for Promotion of Industry and Internal Trade, Ministry of Commerce and Industry, Govt. of India and his eligibility shall be valid as on bid closing date.

C. Declaration in case of MSE Bidders / Start-up Companies

In terms of Tender Conditions applicable for Micro & Small Enterprises (MSEs) / Start-ups, we hereby declare as under: -

- a. We are a Micro / Small Enterprise, as on bid closing date of this tender.
- b. We are a Manufacturer of the quoted supply item(s)/service provider for quoted services and valid documentary evidence for same is submitted.
- c. MSE certificate submitted by us is authentic & valid as on bid closing date of this tender.
- d. We are a 'Start-up' company and we are enclosing copy of certificate of recognition issued by Department for Promotion of Industry and Internal Trade, Ministry of Commerce and Industry, Govt. of India.
- e. We are a Micro / Small Enterprise which is owned by SC-ST/women entrepreneurs and we are submitting valid documentary evidence for the same.

D. Declaration in case of entities seeking purchase preference under Make in India Policy

We have read carefully the terms and conditions for availing the benefits of purchase preference under Make in India Policy and we are meeting all the requirements of Local Content and duly certified documents for proving the stipulated local content along with details of the location(s) where local value addition is made as mentioned in this document are enclosed.

We declare the above details are true. In case any of the details are found to be false/untrue, our offer will be liable for rejection /cancellation of order/subjected to appropriate actions as per tender Terms & Conditions.

.....
Authorized Signatory
(With Company Seal & Signature)

(To be submitted on the Bidder's Company's Letterhead)

BID SECURITY DECLARATION IN LIEU OF EARNEST MONEY DEPOSIT

To,
The General Manager
BRBNMPL,
Bengaluru

Sub: Submission of Bid Security Declaration in Lieu of Earnest Money Deposit against Tender
no.for
.....

Dear Sir,

1. I/We have downloaded / obtained the tender document for the above mentioned "Tender/Work" from the BRBNMPL Portal.
2. I/We understand that according to terms and conditions of this tender, bids must be supported by a bid security, which may be in the form of Bid Security Declaration.
3. I/We hereby undertake that if in case I/We withdraw or modify my/our Bid during the period of validity or if I/We are awarded the contract and I/We fail to sign the contract (NoA / LoI / P.O. / W.O. / Agreement etc.) or to submit a performance security before the deadline defined in the request for bids document then I/We will be suspended for the period of 1 (ONE) years from being eligible to submit Bids to BRBNMPL.
4. I/We understand that this Bid Security Declaration shall cease to be valid under the following circumstances:
 - a. I am/we are declared ineligible/ unsuccessful or
 - b. I am/ We are declared as successful bidder and I/we have furnished the Performance Security and Signed the Contract within the stipulated time.

Place: _____

Signature: _____

Date: _____


Name: _____

Designation: _____

Authorized Signatories Seal

(To be filled, signed & stamped and submitted along with Techno-commercial Bid Part-I)

Annexure – H



Reference Drawing for Tender Purposes only
