BHARATIYA RESERVE BANK NOTE MUDRAN (P) LIMITED
(Wholly owned subsidiary of Reserve Bank of India)
P.O. RBNM, Salboni, Dist. Midnapore (W), West Bengal, Pin Code 721132

Part 4

Sl. No.	Details	Uploading as Annexures in MSTC Portal
4.	Revised Price Bid (Schedule 1 & 2) (Section-XI)	Annexure 12 (Schedule-2 Mysuru) (05 pages) & Annexure 13 (Schedule-1 Salboni) (04 pages)

Annexure - 12

Section XI: Price Schedule

[Price bid to be uploaded separately]

MSTC Event No BRBNMPL/Salboni Press/MMD/7/26-27/ET/12[PIDS]

From:

.....

.....

Date:

To

The Senior General Manager

BRBNMPL, Salboni - 721132

Bidders to update the rates at Yellow Marked Highlighted field which has been allowed for editing.

Dear Sir,

Sub.:Price Bid for "DESIGN, ENGINEERING, SUPPLY, INSTALLATION, TESTING, COMMISSIONING AND TRAINING OF AN AI-ENABLED DISTRIBUTED FIBER OPTIC PERIMETER INTRUSION DETECTION SYSTEM (DFOPIDS) AT BRBNMPL, SALBONI AND MYSURU"

Ref.: :Your Tender Enquiry No. 004/SAL/PUR/2026-27 dated 22/06/2026

We have received and understood your e-tender enquiry and are pleased to upload our price bid as under:

Schedule 2: For Mysuru Press

TABLE – I - Bill of Quantities (BOQ) for DFOPIDS System:

[All Figures in INR]

TABLE - I

Sl. No.	Item Description (As per Technical specifications & Scope of work)	Technical Specification/ Features	Unit of Measurement (UoM)	Total Qty. Reqd.	Basic Price inclusive of Packing Charges / per unit	Freight / Delivery & Insurance Charges / per unit, if any	Sub-total Price for tendered qty at A (Excluding Tax)	GST rate on Supply Part @.....(%)	GST Amount on Supply Part	Total Price (F.O.R. General Stores, BRBNMPL, Salboni (Including Tax)
				A	B	C	D = A*(B+C)	E	F = GST on D	G =(D+F)
1	Distributed Fibre Optic Sensor Cable	Armoured single-mode multi- core fibre optic sensing cable.	Mtr. (7.5 km approx.)	50,000			₹ 0.00		₹ 0.00	₹ 0.00
2	Controller	Optical sensing Dual Channel Controller.	Nos.	2			₹ 0.00		₹ 0.00	₹ 0.00
3	Server (With all necessary Licenses)	Latest Enterprise grade Dual socket Intel Xeon Processor suitable for AI/ML model acceleration, equivalent or better , capable of fully supporting all functional, processing and throughput requirments of the system.	Lot	2			₹ 0.00		₹ 0.00	₹ 0.00
4	Client Workstation and LED Display for monitoring	Intel i9 processor or better, with 27" or better, LED display full HD (1920 x 1080) or better for client workstation and 55" LED Display 4K or better for Monitoring display.	Lot	1			₹ 0.00		₹ 0.00	₹ 0.00
5	24 Port, 1 Gigabyte L2 Managed Switch with 4 SFP Modules	19" rack mountable switch with Minimum 24 x10/100/1000 Base-T port and 4x 1 G SFP ports with suitable AC/DC PSU; 4 nos. 1G SM modules should be loaded.	Set	1			₹ 0.00		₹ 0.00	₹ 0.00
6	Rack & Accessories	Rack with cooling fan, cable manager, earthing kit, lockable doors. (For housing all active devices)	Lot	1			₹ 0.00		₹ 0.00	₹ 0.00
7	Earthing System	Maintenance-free chemical earthing with resistance ≤5ohm, copper bonded electrode, 3mtr length, backfilled with carbon and bentonite compound. (For all electrical equipment's)	Lot	2			₹ 0.00		₹ 0.00	₹ 0.00
8	Supply of HDPE pipe 50mm dia.	HDPE pipe required for laying armoured OFC cable from Township boundary wall to control room and any other required areas.	Mtr.	5500			₹ 0.00		₹ 0.00	₹ 0.00
9	Supply of GI pipe 100 mm dia	GI pipe is required for road cutting/boring of road for laying of cable.	Mtr.	200			₹ 0.00		₹ 0.00	₹ 0.00
10	2.5 Sq. mm. armoured copper cable	For power supply to hooter cum strobe connections in the perimeter area (Payment will be made on actual basis).	Mtr.	3000			₹ 0.00		₹ 0.00	₹ 0.00

Manager (Utility)
Mysuru

11	Road cutting	Trench digging, Boring of road/road cutting (bituminous road) for laying of armoured OFC cable with supply of 100mm GI pipe & 50 m HDPE pipe, refilling, reconstructing of cut road as per IS standards Township boundary wall to control room and any other required areas.)	Mtr.	1200			₹ 0.00		₹ 0.00	₹ 0.00
12	Core cutting of surface and installation of OFC cable	Installation of buried OFC cable through bitumen road/concrete surface using core cutting of surface	Mtrs.	5000			₹ 0.00		₹ 0.00	₹ 0.00
13	Soft soil digging and installation of OFC cable	Installation of buried OFC cable through soft soil	Mtrs.	2500			₹ 0.00		₹ 0.00	₹ 0.00
14	Miscellaneous	Any other miscellaneous items such as nylon UV protected heavy duty cable ties, Relay contacts, brackets, fixtures, clamps, route markers, patch cord, switches, suitable size rack for PDU controller, 24 port LIU for fibre cable termination, 4 channel KVM switch as required, OFC jointing kit, software, Licenses, etc. and works like drilling, welding, splicing etc. Any other material/work are not explicitly mentioned above and required to complete the project.	Lot	1			₹ 0.00		₹ 0.00	₹ 0.00
15	Installation, Testing & Commissioning	Complete installation of system and laying OFC cable on concertina coil, Cable unwinding, Cable Lacing by Cable Tie, Splicing, Installation of Splicing Enclosures, Link Units, Termination Unit, Installation of HDPE Pipes for gate areas, Installation of GI pipe, Installation of Racks and other equipments in the control room, electric power cabling etc. Configuration, calibration of DFO-PIDS system and functional testing and any other support charges.	Lot	1			₹ 0.00		₹ 0.00	₹ 0.00
16	Training	Training charges - Operation & Maintenance	Lot	1			₹ 0.00		₹ 0.00	₹ 0.00
17	FOPIDS integration with existing VMS of CCTV system	FOPIDS integration with existing VMS of CCTV system is OPTIONAL for BRBNMPL and may be ordered at a later stage subject to satisfactory performance of newly commissioned FOPIDS system. The price quoted shall be firm and binding and valid till completion of 1st year warranty period of the contract. Integration is OPTIONAL for BRBNMPL, however, bidders have to mandatorily quote in the Price bid for L1 determination.-	Lumpsum	1			₹ 0.00		₹ 0.00	₹ 0.00

18	Ethernet based I/O module	Ethernet based I/O module equipped with a minimum of 2 DI and 2DO, along with other accessories such as network switch with SFP module/media coverter, SMPS etc. shall be deployed using existing fiber optic network across the perimeter (as mentioned in technical specification).	Set	15			₹ 0.00		₹ 0.00	₹ 0.00
19	Hooter cum strobe	12V/24V AC/DC operated Hooter cum strobe for filed installation along with mounting arrangements and poles (5 mtr) with foundation etc in the scope of bidder.	Set	30			₹ 0.00		₹ 0.00	₹ 0.00
20	Manual Soft soil digging and laying of 2.5 sq. mm copper cable for hooter cum strobe	Manual Trench digging (WxD: 300mm x 900mm, laying of underground copper cable through 50 mm HDPE pipe and refilling of trench	Mtr	3000			₹ 0.00		₹ 0.00	₹ 0.00
21	Laying of copper cable	Laying of copper cable over wall through HDPE conduit	Mtr	200			₹ 0.00		₹ 0.00	₹ 0.00
22									Grand Total Price (All Inclusive) on F.O.R. General Stores, BRBNMPL, Salboni basis (Sl. Nos. 1 to 22) :	₹ 0.00

TABLE II - Manpower Deployement during warranty period (Total 02 years from the date of issue of FAC)

Sl. No.	Work Description	SAC Code	Unit	Qty	Basic price per Month including minimum wages as per GOI, PF, ESI, Bonus as per Act, shoes, uniform, etc. (*)	Sub-total Price (Excluding Tax) (Rs.)	GST rate (%)	GST Amount (Rs.)	Grand Total Amount (Rs.)
				A	B	C=A X B	D	E= Cx(D%)	F=ExC
1	Manpower Deplyment : One Residential Engineer as a System Administrator / Senior Technician (Skilled category) in General Shift. The timings will be as per BRBNMPL shift timings. Deployment may be changed as per BRBNMPL's requirement.		Month	24		₹ 0.00		₹ 0.00	₹ 0.00
2		Grand Total Amount aganinst Manpower Deployement during warranty period 02 years (Rs.)							₹ 0.00

(*) Note:

1) Statutory Compliances: Personnel/staff/members employed by the Contractor should be paid @ Minimum Wages as per the notification published by Central / State Govt. (whichever is higher) as applicable from time-to-time calculated on per day basis, besides paying all other Statutory payments including PF, ESIC/WC, Bonus etc. as applicable. The contractor has to maintain all records and legal documents updated as per prevailing statute and has to produce before the Management / Statutory Authorities as and when asked for. Besides the contractor has to indemnify the Company from all types of legal implications due to any negligence on the part of contractor and for which the BRBNMPL is not responsible. The cost for Workmen Compensation Policy for the persons not covered under ESI shall be included and no separate reimbursement shall be entertained.

2) All statutory payments like minimum wages, PF, ESI and Bonus should be maintained in respect of manpower so deployed by the contractor. In case of any complaint regarding non-payment of statutory dues and non-compliance of any statutory provisions, the same shall be deducted from your bill without prejudice to the company's right to cancel the Work Order / Contract.

3) The contractor shall supply Uniforms (approved by BRBNMPL), Personal Protective Equipment like one pair of safety shoes, gloves etc. to manpower engaged.

4) The contractor shall provide detailed price breakup component wise for the price quoted in Table ~~III~~ II - Column no: B.

5) Contract manpower shall be provided leave with wages as per entitlement under the factories Act, 1948 and Rules made thereunder which shall be re-imbursed at actual on submission of documentary evidence. However, during the absence of contract manpower, and if the contractor provides a substitute/ alternate, then the additional expenses incurred for the same shall be claimed at actuals in the subsequent year with production of documentary proof.

6) The Contractor/ Service Provider should provide National Holidays – 03 Days as a statutory requirement. Payment for 09 Days Festival Holidays shall be paid by BRBNMPL to the contract manpower.

7) ESI/Workmen Compensation & any suitable Medical Insurance: The contractor should cover its employees/workman under ESI. In absence of ESI for non- implement area or exceeding ESI Ceiling, the Contractor should undertake Workmen Compensation Policy and a suitable Medical Insurance pertaining to this work and particulars work/s. The Contractor has to submit the relevant documents pertaining to the payment of premium along with a copy of Insurance Policy to us within 15 days from the placement of Work Order.

TABLE - III (Non-Comprehensive AMC for Mysuru Press)						
Non- Comprehensive AMC charges for 3 years after completion of warranty period						
Sl. No.	Particulars	Total Quantity with UoM	Unit price (₹)	GST rate @.....(%)	GST Amount (₹)	Grand Total Price (Including Tax) (₹)
		A	B	C	D=GST on B	E = B + D
	3 years post-warranty on call basis after warranty obligations includes quarterly visit and unlimited breakdown visit.					
1	AMC Charges for 1st Year	1 Lot			₹ 0.00	₹ 0.00
2	AMC Charges for 2nd Year	1 Lot			₹ 0.00	₹ 0.00
3	AMC Charges for 3rd Year	1 Lot			₹ 0.00	₹ 0.00
4	Total Price (All Inclusive) of AMC Charges for 3 Years: Total Price (All Inclusive) on F.O.R. BRBNMPL, Saiboni basis (Sl. Nos. 1 to 3)					₹ 0.00

TABLE - IV		
Sl. No.	Description	GRAND TOTAL AMOUNT SCHEDUEL - 2 (in ₹)
		Sl. No. 22 of Col. G (Table - I) + Sl. No. 2 of Col. F (Table - II) + Sl. No. 4 of Col. E (Table - III)
1	GRAND TOTAL (TABLE - I, TABLE - II and TABLE - III)	₹ 0.00

NOTE: BIDDERS ARE REQUESTED TO FILL THE SHADED CELL AS THEIR QUOTED AMOUNT. OTHER CELLS ARE NOT EDITABLE.

Note for bidders

1. **Price should be quoted in MSTC Portal exactly as per format given above. Multiple rates for single item would lead to rejection of offer.**
2. Not Quoting / Mentioning in all items of Price Schedule are liable for rejection.
3. **Tender shall be finalized on the basis of Schedule wise Lowest (L1) Bidder from eligible bidders as per Section XI and as per terms & conditions of the tender.**
4. Quoted Rate should be on the basis of final completion of works at BRBNMPL, Mysuru (including Unit Rate and GST).
5. Price bids with conditions/Counter conditions shall be liable for rejection.
6. Bidders mentioning prices in any place other than the Price Bid (PART-II) shall be liable for rejection of their bids.
7. Bidders are required to quote the prices within 2 decimal places. Prices quoted with more than 2 decimal places shall be rounded off to 2 decimal places for evaluation.
8. Price bid evaluation shall be subject to purchase preference to Class-I Local Suppliers as per GoI guidelines (Refer Annexure 1 to 5). However, this Purchase Preference shall be executed considering the tender quantity to be "NON-DIVISIBLE" in nature.
9. The prices are quoted with complete awareness of the site conditions

10. Purchase preference shall be given to the participating bidders registered under MSE's/ Start-ups (whether MSEs or otherwise)/Class-I Local Suppliers as per SIT provision for GIT clause No. 35.2 & 35.3 given under Section III: Special Instructions to Tenderers (SIT).

Declaration

- I/We agree that on being successful in the tender, we would carry out the work exactly as per Scope of Work and Responsibility of the Contractor mentioned in Scope of Work (Section-VII) and all other terms and Conditions of the Tender.

- I/We confirm that the quoted prices shall be valid till the completion of entire work and also confirm that the rates quoted is inclusive of taxes as applicable and shall remain firm & binding and no escalation on above on any account shall be admissible during the currency of the contract except for changes in GST payments for which documentary proof should be attached for claiming escalation, if any.

Annexure-13

Section XI: Price Schedule

[Price bid to be uploaded separately]

MSTC Event No BRBNMPL/Salboni Press/MMD/7/26-27/ET/12[PIDS]

From:

.....

.....

Date:

To

The Senior General Manager

BRBNMPL, Salboni – 721132

Bidders to update the rates at Yellow Marked Highlighted field which has been allowed for editing.

Dear Sir,

Sub.:Price Bid for "DESIGN, ENGINEERING, SUPPLY, INSTALLATION, TESTING, COMMISSIONING AND TRAINING OF AN AI-ENABLED DISTRIBUTED FIBER OPTIC PERIMETER INTRUSION DETECTION SYSTEM (DFOPIDS) AT BRBNMPL, SALBONI AND MYSURU"

Ref.: :Your Tender Enquiry No. 004/SAL/PUR/2026-27 dated 22/06/2026

We have received and understood your e-tender enquiry and are pleased to upload our price bid as under:

Schedule 1: For Salboni Press

[All Figures in INR]

TABLE – 1 : Bill of Quantities (BOQ) for DFOPIDS System:

TABLE - 1											
Sl. No.	Item Description (As per Technical specifications & Scope of work)	Technical Specification/ Features	Unit of Measurement (UoM)	Total Qty. Reqd.	Basic Price inclusive of Packing Charges / per unit	Freight / Delivery & Insurance Charges / per unit, if any	Sub-total Price for tendered qty at A (Excluding Tax)	GST rate on Supply Part @.....(%)	GST Amount on Supply Part	Total Price (F.O.R. General Stores, BRBNMPL, Salboni (Including Tax)
				A	B	C	D = A *(B+C)	E	F = GST on D	G = (D+F)
1	Distributed Fibre Optic Sensor Cable	Armoured single-mode multi-core fibre optic sensing cable.	Mtr. (8km approx.)	50,000			₹ 0.00		₹ 0.00	₹ 0.00
2	Controller	Optical sensing Dual Channel Controller.	Nos.	2			₹ 0.00		₹ 0.00	₹ 0.00
3	Server With all necessary Licenses	Intel Xeon Silver series dual socket processor or higher, 5th Gen or higher (12 Cores, up to 3.9 GHz) suitable for AI/ML model acceleration, equivalent or better suitable for AI/ML model acceleration, equivalent or better capable of fully supporting all functional, processing and throughput requirments of the system.	Lot	2			₹ 0.00		₹ 0.00	₹ 0.00
4	Client Workstation and LED Display for monitoring	Intel I9 processor or better, with 27" or better, LED display full HD (1920 x 1080) or better for client workstation and 55" LED Display 4K or better for Monitoring display.	Lot	1			₹ 0.00		₹ 0.00	₹ 0.00
5	Switch (24 Port, 1 Gigabyte L2 Managed Switch with 4 SFP Modules)	24 Port, 1 Gigabyte L2 Managed Switch with 4 SFP Modules: 19" rack mountable switch with Minimum 24 x10/100/1000 Base-T port and 4x 1 G SFP ports with suitable AC/DC PSU; 4 nos. 1G SM modules should be loaded	Set	1			₹ 0.00		₹ 0.00	₹ 0.00
6	Rack & Accessories	Rack with cooling fan, cable manager, earthing kit, lockable doors. (For housing all active devices)	Lot	1			₹ 0.00		₹ 0.00	₹ 0.00
7	Earthing System	Maintenance-free chemical earthing with resistance ≤5ohm, copper bonded electrode, 3mtr length, backfilled with carbon and bentonite compound (For all electrical equipment's)	Nos.	20			₹ 0.00		₹ 0.00	₹ 0.00
8	Lightning Arrestor	Outdoor type (Early streamer emission)/Conventional Lightning arrester.	Nos.	8			₹ 0.00		₹ 0.00	₹ 0.00
9	Supply of HDPE pipe 50mm dia.	HDPE pipe required for laying armoured OFC cable from Township boundary wall to control room and any other required areas.	Mtr.	3000			₹ 0.00		₹ 0.00	₹ 0.00

अतय
Manager (Utility)
Mysuru

10	Supply of GI pipe 100 mm dia	GI pipe is required for road cutting/boring of road for laying of cable.	Mtr.	750			₹ 0.00		₹ 0.00	₹ 0.00
11	2.5 Sq. mm armoured copper cable along with 50 mm HDPE conduit	For power supply to hooter cum strobe connections in the perimeter area (Payment will be made on actual basis)	Mtr.	4500			₹ 0.00		₹ 0.00	₹ 0.00
12	Trench digging	Trench digging, Boring of road/road cutting (bituminous road) for laying of armoured OFC cable with supply of 100mm GI pipe, refilling, reconstructing of cut road as per IS standards (Township Perimeter is 8km (approx.), Township boundary wall to control room and any other required areas.)	Mtr.	10000			₹ 0.00		₹ 0.00	₹ 0.00
13	Miscellaneous	Any other miscellaneous items such as nylon UV protected heavy duty cable ties, Relay contacts, brackets, fixtures, clamps, route markers, patch cord, switches, suitable size rack for PDU controller, 24 port LIU for fibre cable termination, 4 channel KVM switch as required, OFC jointing kit, software, Licenses, etc. and works like drilling, welding, splicing etc. Any other material/work are not explicitly mentioned above and required to complete the project.	Lot	1			₹ 0.00		₹ 0.00	₹ 0.00
14	Installation, Testing & Commissioning	Complete installation of system and laying of pipe, cables and any other equipment's, Configuration, calibration of DFO-PIDS system, integration with VMS, and functional testing and any other support charges.	Lot	1			₹ 0.00		₹ 0.00	₹ 0.00
15	Training	Training charges - Operation & Maintenance	Lot	1			₹ 0.00		₹ 0.00	₹ 0.00
16	a) Ethernet based I/O module	IoT of minimum of 2 DI/DO, Industrial contactor along with other accessories shall be deployed using existing fiber optic network across the perimeter.	Set	32			₹ 0.00		₹ 0.00	₹ 0.00
	b) Supply and Installation of IP65 protected minimum 19U Rack	Supply and Installation of IP65 protected minimum 19U Rack along with accessories such as Network Switch with SFP module, LIU, required patch card etc. Foundation for racks as per IS standard is in the scope of bidder (as mentioned in technical specification)	Set	16			₹ 0.00		₹ 0.00	₹ 0.00
17	Hooter cum strobe	Supply and Installation of Hooter cum strobe along with mounting arrangements and poles (5 mtr) with foundation etc in the scope of bidder.	Set	32			₹ 0.00		₹ 0.00	₹ 0.00
18	Laying of copper cable	Manual Digging (W X D: 300 mm X 900 mm), laying of 2.5 sq. mm copper cable through 50 mm HDPE conduit (for hooter cum strobe) and refilling of trench as per IS standard (Payment will be done on actual basis)	Mtr.	4000			₹ 0.00		₹ 0.00	₹ 0.00
19	Grand Total Price (All Inclusive) on F.O.R. General Stores, BRBNMPL, Salboni basis (Sl. Nos. 1 to 18) :									₹ 0.00

TABLE II - Manpower Deployement during warranty period (Total 02 years from the date of issue of FAC)									
Sl. No.	Work Description	SAC Code	Unit	Qty	Basic price per Month including minimum wages as per GOI, PF, ESI, Bonus as per Act, shoes, uniform, etc. (*)	Sub-total Price (Excluding Tax) (Rs.)	GST rate (%)	GST Amount (Rs.)	Grand Total Amount (Rs.)
				A	B	C=A X B	D	E= Cx(D%)	F=ExC
1	Manpower Deployment : One Residential Engineer as a System Administrator / Senior Technician (Skilled category) in General Shift. The timings will be as per BRBNMPL shift timings. Deployment may be changed as per BRBNMPL's requirement.		Month	24		₹ 0.00		₹ 0.00	₹ 0.00
2		Grand Total Amount aganinst Manpower Deployement during warranty period 02 years (Rs.)							₹ 0.00

(*) Note:

1) Statutory Compliances: Personnel/staff/members employed by the Contractor should be paid @ Minimum Wages as per the notification published by Central / State Govt. (whichever is higher) as applicable from time-to-time calculated on per day basis, besides paying all other Statutory payments including PF, ESIC/WC, Bonus etc. as applicable. The contractor has to maintain all records and legal documents updated as per prevailing statute and has to produce before the Management / Statutory Authorities as and when asked for. Besides the contractor has to indemnify the Company from all types of legal implications due to any negligence on the part of contractor and for which the BRBNMPL is not responsible. The cost for Workmen Compensation Policy for the persons not covered under ESI shall be included and no separate reimbursement shall be entertained.

2) All statutory payments like minimum wages, PF, ESI and Bonus should be maintained in respect of manpower so deployed by the contractor. In case of any complaint regarding non-payment of statutory dues and non-compliance of any statutory provisions, the same shall be deducted from your bill without prejudice to the company's right to cancel the Work Order / Contract.

3) The contractor shall supply Uniforms (approved by BRBNMPL), Personal Protective Equipment like one pair of safety shoes, gloves etc. to manpower engaged.

4) The contractor shall provide detailed price breakup component wise for the price quoted in Table III - Column no: B.

5) Contract manpower shall be provided leave with wages as per entitlement under the factories Act, 1948 and Rules made thereunder which shall be re-imbursed at actual on submission of documentary evidence. However, during the absence of contract manpower, and if the contractor provides a substitute/ alternate, then the additional expenses incurred for the same shall be claimed at actuals in the subsequent year with production of documentary proof.

6) The Contractor/ Service Provider should provide National Holidays – 03 Days as a statutory requirement. Payment for 09 Days Festival Holidays shall be paid by BRBNMPL to the contract manpower.

7) ESI/Workmen Compensation & any suitable Medical Insurance: The contractor should cover its employees/workman under ESI. In absence of ESI for non- implement area or exceeding ESI Ceiling, the Contractor should undertake Workmen Compensation Policy and a suitable Medical Insurance pertaining to this work and particulars work/s. The Contractor has to submit the relevant documents pertaining to the payment of premium along with a copy of Insurance Policy to us within 15 days from the placement of Work Order.

TABLE - III (Non-Comprehensive AMC for Salboni Press)						
Non- Comprehensive AMC charges for 3 years after completion of warranty period						
Sl. No.	Particulars	Total Quantity with UoM	Unit price (₹)	GST rate @.....(%)	GST Amount (₹)	Grand Total Price (Including Tax) (₹)
		A	B	C	D=GST on B	E = B + D
	3 years post-warranty on call basis after warranty obligations includes quarterly visit and unlimited breakdown visit.					
1	AMC Charges for 1st Year	1 Lot			₹ 0.00	₹ 0.00
2	AMC Charges for 2nd Year	1 Lot			₹ 0.00	₹ 0.00
3	AMC Charges for 3rd Year	1 Lot			₹ 0.00	₹ 0.00
4	Total Price (All inclusive) of AMC Charges for 3 Years: Total Price (All inclusive) on F.O.R. BRBNMPL, Salboni basis (Sl. Nos. 1 to 3)					₹ 0.00

TABLE - IV		
Sl. No.	Description	GRAND TOTAL AMOUNT SCHEDUEL - 1 (in ₹)
		Sl. No. 19 of Col. K (Table - I) + Sl. No. 2 of Col. J (Table - II) + Sl. No. 4 of Col. H (Table - III)
1	GRAND TOTAL (TABLE – I, TABLE – II and TABLE – III)	₹ 0.00

NOTE: BIDDERS ARE REQUESTED TO FILL THE SHADED CELL AS THEIR QUOTED AMOUNT, OTHER CELLS ARE NOT EDITABLE.

Note for bidders

1. **Price should be quoted in MSTC Portal exactly as per format given above. Multiple rates for single item would lead to rejection of offer .**
2. Not Quoting / Mentioning in all items of Price Schedule are liable for rejection.
3. **Tender shall be finalized on the basis of Schedule wise Lowest (L1) Bidder from eligible bidders as per Section XI and as per terms & conditions of the tender.**
4. Quoted Rate should be on the basis of final completion of works at BRBNMPL, Salboni (including Unit Rate and GST)
5. Price bids with conditions/Counter conditions shall be liable for rejection.
6. Bidders mentioning prices in any place other than the Price Bid (PART-II) shall be liable for rejection of their bids.
7. Bidders are required to quote the prices within 2 decimal places. Prices quoted with more than 2 decimal places shall be rounded off to 2 decimal places for evaluation.
8. **Price bid evaluation shall be subject to purchase preference to Class-I Local Suppliers as per GoI guidelines [Refer Annexure 1 to 5]. However, this Purchase Preference shall be executed considering the tender quantity to be "NON-DIVISIBLE" in nature.**
9. The prices are quoted with complete awareness of the site conditions
10. Purchase preference shall be given to the participating bidders registered under MSE's/ Start-ups (whether MSEs or otherwise)/Class-I Local Suppliers as per **SIT provision for GIT clause No. 35.2 & 35.3** given under Section III: Special Instructions to Tenderers (SIT).

Declaration

I/We agree that on being successful in the tender, we would carry out the work exactly as per Scope of Work and Responsibility of the Contractor mentioned in Scope of Work (Section-VII) and all other terms and Conditions of the Tender.

I/We confirm that the quoted prices shall be valid till the completion of entire work and also confirm that the rates quoted is inclusive of taxes as applicable and shall remain firm & binding and no escalation on above on any account shall be admissible during the currency of the contract except for changes in GST payments for which documentary proof should be attached for claiming escalation, if any.